

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

### MCPS RADON TESTING – EXECUTIVE SUMMARY

Site Name	Luxmanor
	Elementary School
Date of Test Report	4/6/2022
Round of Testing	Initial
	Follow-up
	Post Remediation
	2 Year Testing
	5 Year Testing
	HVAC Upgrade
	Window Replacement
	New Addition
	New Facility
# Rooms Tested	38
# Rooms $\geq$ 4.0 pCi/L	0
Lowest Value	<0.3 pCi/L
Highest Value	1.1 pCi/L

Project Status: Initial testing completed; no further action needed.

KCI Technologies, Inc. WWW.kci.com

#### ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

April 6, 2022

Brian T. Croyle, PG, CHMM Environmental Specialist Montgomery County Public Schools Gaithersburg, MD 20879

**Re:** Radon Testing Services

KCI Job # 122108316

Location: Luxmanor ES

6201 Tilden Lane Rockville, MD 20852

Dear Mr. Croyle:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Luxmanor ES, located at 6201 Tilden Lane Rockville, MD 20852 (subject site).

#### **Scope of Services:**

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Proficiency Program (NRPP) Radon Measurement Specialist (certification #111004 RT) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from <a href="https://www.montgomeryschoolsmd.org">https://www.montgomeryschoolsmd.org</a> or <a href="https://www.montgomeryschoolsmd.org">www.epa.gov/radon</a>.

KCI visited the site on February 7, 2022 and deployed forty four (44) activated charcoal (AC) radon test kits. KCI deployed radon test kits in all frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance.

A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI also included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on February 10, 2022 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc.

KCI Technologies, Inc. WWW.kci.com

is a NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

#### **Evaluation of Testing Conditions:**

These tests represent:

• Initial testing.

These tests were conducted to:

• Evaluate radon centration levels at the facility.

According to AARST, Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room during the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate low temperatures were in the 30s and high temperatures ranged from the mid 30s to the mid 50s Fahrenheit. Maximum sustained winds ranged from 3-12 miles per hour. Average humidity was around 23% with 0.1 inches of precipitation (rain) was recorded during testing period.

#### **Results:**

The sampling locations and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). Sampling locations and associated test kit identification numbers and relevant field observations are listed on Table 3 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	None	N/A
<4.0 piC/L	See Attachment B	

KCI TECHNOLOGIES, INC. WWW.kci.com

Quality Control Samples		
Results of Blank Canisters: The office blanks, and lab transit blanks had test results		
less than the laboratory detection limit of 0.3 pCi/L.		
Adequate Laboratory Precision? Review of the duplicate sample analysis indicates that		
adequate laboratory measurement precision was achieved		
Spike Sample Analysis:	alysis: The Spike Sample analysis results indicate the laboratory i	
	operating within statistical control limits.	

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 891-1769.

Sincerely,

Tyler P. McCleaf

Radon Measurement Provider

#111004 RT

KCI Technologies, Inc.

Tyler McCleaf

Attachments: A- Floor Plan with Test Locations

B- Table 1-3, Radon Test Summary Spreadsheets

C- Laboratory Analytical Results

## ATTACHMENT A

### Floor Plan With Test Locations

### ATTACHMENT B

# Radon Test Summary Spreadsheet

#### **Table Notes:**

AC- Activated Charcoal

ACI- Air Check, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

OC- Quality Control

Table 1- Radon Testing Results	
Luxmanor ES	
	7

Test Period: 02/7/2022 - 02/10/2022

Kit Number	Room / Area	Result
11114976	100	< 0.3
11114959	101	< 0.3
11114957	102	< 0.3
11114949	103	< 0.3
11114950	104	< 0.3
11114974	105	0.6
11114978	107	0.8
11114977	108	< 0.3
11114984	109	< 0.3
11114983	110	< 0.3
11114982	111	0.7
11114985	112	0.6
11114986	112	< 0.3
11114969	114	< 0.3
11114956	115	< 0.3
11107387	117	< 0.3
11114965	118	1.1
11114972	118	1.1
11114966	119	< 0.3
11107363	120	0.8
11114967	121	0.5
11107370	122	< 0.3
11107369	123	< 0.3
11107364	124	< 0.3
11114968	125	0.7
11114962	151	0.8
11107372	226	< 0.3
11107388	226	< 0.3
11107390	226	< 0.3
11107379	231	< 0.3
11107389	303	0.8
11114975	100A	1.0
11114980	100B	0.6
11114979	100C	0.7
11114981	100F	< 0.3
11114902	116D	< 0.3
11114961	156A	0.5
11114960	161A	< 0.3
11114963	АР	0.7
11114964	АР	< 0.3
11114970	АР	< 0.3
11114973	AP	< 0.3

Table 1- Radon Testing Results				
	Luxmanor ES			
Т	Test Period: 02/7/2022 - 02/10/2022			
Kit Number	Room / Area	Result		
11114958	GYM	< 0.3		
11114971	GYM	< 0.3		

Table 2- Radon Testing Results					
	Luxman	or ES			
	Test Period: 02/7/20	)22 - 02/10/2022			
Kit Number	QC Type	Room / Area	Result		
11114986	D	112	< 0.3		
11114964 D AP < 0.3					
11114973 FB AP < 0.3					
11114965 D 118 1.1					
11107372	11107372 D 226 < 0.3				
11107388	11107388 FB 226 < 0.3				
11113481	11113481 OB OFFICE BLANK < 0.3				
11113483	11113483 TB TRAVEL BLANK < 0.3				

Summary of Missed Locations			
Luxmanor ES			
Test Period: 02/7/22 - 02/10/22			
Kit Number	Room/Area	Result	
	NA		

Summary of Missing, Compromised and >/= 4 piC/L Tests			
Luxmanor ES			
Test Period: 02/7/22 - 02/10/22			
Kit Number Room/Area Res			
	NA		

#### Table Note:

<sup>\*</sup> Missing or Compromised Sample

# ATTACHMENT C

# Laboratory Analytical Results

# Radon test result report for: LUXMANOR ES

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11114976	100	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-14
11114975	100A	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	$1.0 \pm 0.4$	2022-02-14
11114980	100B	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	$0.6 \pm 0.4$	2022-02-14
11114979	100C	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	$0.7 \pm 0.3$	2022-02-14
11114981	100F	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-14
11114959	101	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-14
11114957	102	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-14
11114949	103	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-14
11114950	104	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-15
11114974	105	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	$0.6 \pm 0.3$	2022-02-14
11114978	107	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	$0.8 \pm 0.4$	2022-02-15
11114977	108	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-14
11114984	109	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-15
11114983	110	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-15
11114982	111	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	$0.7 \pm 0.4$	2022-02-14
11114986	112	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-14
11114985	112	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	$0.6 \pm 0.4$	2022-02-15
11114969	114	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-14
11114956	115	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-14
11114902	116D	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-14
11107387	117	2022-02-07 @ 2:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-14
11114965	118	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	$1.1 \pm 0.4$	2022-02-15
11114972	118	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	$1.1 \pm 0.4$	2022-02-15
11114966	119	2022-02-07 @ 2:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-15
11107363	120	2022-02-07 @ 2:00 pm	2022-02-10 @ 11:00 am	$0.8 \pm 0.4$	2022-02-15
11114967	121	2022-02-07 @ 2:00 pm	2022-02-10 @ 11:00 am	$0.5 \pm 0.3$	2022-02-14
11107370	122	2022-02-07 @ 2:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-15
11107369	123	2022-02-07 @ 2:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-15
11107364	124	2022-02-07 @ 2:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-14
11114968	125	2022-02-07 @ 2:00 pm	2022-02-10 @ 11:00 am	$0.7 \pm 0.4$	2022-02-15
11114962	151	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	$0.8 \pm 0.4$	2022-02-14
11114961	156A	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	$0.5 \pm 0.3$	2022-02-14
11114960	161A	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-14
11107388	226	2022-02-07 @ 2:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-14
11107372	226	2022-02-07 @ 2:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-14
11107390	226	2022-02-07 @ 2:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-15
11107379	231	2022-02-07 @ 2:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-15

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

### \*\* LABORATORY ANALYSIS REPORT \*\*

# Radon test result report for: LUXMANOR ES

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11107389	303	2022-02-07 @ 2:00 pm	2022-02-10 @ 11:00 am	$0.8 \pm 0.4$	2022-02-15
11114964	AP	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-14
11114973	AP	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-14
11114970	AP	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-14
11114963	AP	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	$0.7 \pm 0.4$	2022-02-15
11114958	GYM	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-15
11114971	GYM	2022-02-07 @ 1:00 pm	2022-02-10 @ 11:00 am	< 0.3	2022-02-15
		1			

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

### **EXPOSURE IN BOWSER-MORNER RADON CHAMBER**

CLIENT KCI Technologies	Inc. Job Number 204186
	pCi/L Rel. Hum 50.1 % Temp. 70.9
Date Start: <u>a / 18 b-2</u> Date Stop: <u>2/a 1/a</u>	2 Date Start: Date Stop:
Time Start: Q911 Time Stop: Q911	Time Start: Time Stop:
Device No.'s: (3) Char Bog 5-	Device No.'s:
11113484, 11112998, 20107126	
23 Right	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
	×
(C)	
9	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
	3:

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background =  $7 \mu R/h$  Elevation = 820 ft

### \*\* LABORATORY ANALYSIS REPORT \*\*

Pg 1 of 1

MCPS - Spike Sample Lab Results. Measured values are satisfactory, i.e., within  $\pm$  25% of the chamber's reference value (25.7 pCi/L).

Kit Number	<b>Start Date</b>	<b>Start Time</b>	<b>End Date</b>	<b>End Time</b>	Temp.	Facility	Building	Room	Project ID	Floor	Result
11113484	2022-02-18	9:00 am	2022-02-21	9:00 am	71	OFFICE	MAIN	SK1		1	27.9
11122998	2022-02-18	9:00 am	2022-02-21	9:00 am	71	OFFICE	MAIN	SK2		1	26.0
20107126	2022-02-18	9:00 am	2022-02-21	9:00 am	71	OFFICE	MAIN	SK3		1	27.6

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498



Engineers • Planners • Scientists • Construction Managers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

#### **Radon Test Kit Chain of Custody**

Project Name: MCPS Radon - February 2022 Schools

#### Name of Schools:

- 1. Lincoln Center
- 2. Wootton HS
- 3. Rockville HS
- 4. Richard Montgomery HS
- 5. Rocking Horse Rd. Center
- 6. Blair G. Ewing Center
- 7. Twinbrook ES
- 8. Rock Creek Valley ES
- 9. Luxmanor ES
- 10.Tilden MS

	Date	Initials
Radon Test Kits Deployed	02/07/2022	n
Radon Test Kits Collected	02/10/2022	(In
Radon Test Kits Shipped to Lab*	02/10/2022	M
Radon Test Kits Received by Lab*	02/14/2022	a

<sup>\*</sup>All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759