

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

### MCPS RADON TESTING – EXECUTIVE SUMMARY

Site Name	Downcounty Maintenance and		
	Operations Service Center		
	(Formerly Randolph Maintenance and		
	Transportation Depot)		
Date of Test Report	01/20/2022		
Round of Testing	Initial		
	Follow-up		
	Post Remediation		
	2 Year Testing		
	5 Year Testing		
	HVAC Upgrade		
	Window Replacement		
	New Addition		
	New Facility		
# Rooms Tested	23		
# Rooms $\geq 4.0 \text{ pCi/L}$	0		
Lowest Value	<0.3 pCi/L		
Highest Value	2.4 pCi/L		

### **Project Status**

Current Project Status at this time: Testing Complete; no further action.

KCI Technologies, Inc. WWW.kci.com

#### ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

January 20, 2022

Mr. Richard Cox Indoor Air Quality Team Leader Montgomery County Public Schools Gaithersburg, MD 20879

Re: Radon Testing Services

KCI Job # 122108316

Location: Downcounty Maintenance and Operations Service Center

1801 Old Randolph Rd. Silver Spring, MD 20901

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for Downcounty Maintenance and Operations Service Center (Formerly Randolph Maintenance and Transportation Depot), located at 1801 Old Randolph Rd. Silver Spring, MD 20901 (subject site).

#### **Scope of Services:**

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Proficiency Program (NRPP) Radon Measurement Specialist (certification #111004 RT) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from https://www.montgomeryschoolsmd.org or www.epa.gov/radon.

KCI visited the site on December 13, 2021 and deployed twenty-seven (27) activated charcoal (AC) radon test kits. KCI deployed radon test kits in all frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance.

A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI also included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on December 16, 2021 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc. is a NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

#### **Evaluation of Testing Conditions:**

These tests represent:

• Follow-up to initial testing.

These tests were conducted to:

• Evaluate radon concentrations at the facility.

According to AARST, Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room during the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate low temperatures were in the low 30°Fs and high temperatures ranged from the mid 50°Fs to the high 60°Fs. Maximum sustained winds ranged from 3-12 miles per hour. Average humidity was around 50% with 0.0 inches of precipitation (rain) was recorded during testing period.

#### **Results:**

The sampling locations and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). Sampling locations and associated test kit identification numbers and relevant field observations are listed on Table 3 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	NA	NA
<4.0 piC/L	See Attachn	nent B

KCI TECHNOLOGIES, INC. WWW.kci.com

Quality Control Samples			
Results of Blank Canisters: The office blanks, and lab transit blanks had test result			
less than the laboratory detection limit of 0.3 pCi/L.			
Adequate Laboratory Precision? Review of the duplicate sample analysis indicates that			
adequate laboratory measurement precision was achieved			
Spike Sample Analysis:	The Spike Sample analysis results indicate the laboratory is		
operating within statistical control limits.			

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 891-1769.

Sincerely,

Tyler P. McCleaf

Radon Measurement Provider

#111004 RT

KCI Technologies, Inc.

Tyler McCleaf

Attachments: A- Floor Plan with Test Locations

B- Table 1-3, Radon Test Summary Spreadsheets

C- Laboratory Analytical Results

## ATTACHMENT A

## Floor Plan With Test Locations

## ATTACHMENT B

# Radon Test Summary Spreadsheets

### **Table Notes:**

AC- Activated Charcoal

ACI- Air Check, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

OC- Quality Control

Table 1- Radon Testing Results			
Randolph Maintenance Depot			
Test P	eriod: 12/13/2021-12/16/20	021	
Kit Number	Room / Area	Result	
9339923	OFFICE 4	2.4	
9341763	OFFICE 2	1.5	
9348002	CARPENTER SHOP	2.3	
9348003	2		
9348005	BREAKROOM 2	< 0.3	
9348006	LEFT OFFICE	1.5	
9348015	BREAKROON 2	1.4	
9348021	CARPENTER SHOP	2.3	
9348022 OFFICE 1 1.5			
9348024 OFFICE 3 1.4			
9348028	CARPENTER SHOP	2	
9348031	FRONT OFFICE	0.9	
9348032 BREAKROOM 0.9			

Table 1- Radon Testing Results				
Randolph Transportation Depot				
Test P	eriod: 12/13/2021-12/16/20	021		
Kit Number	Room / Area	Result		
9339704	OFFICE 1	< 0.3		
9339910	FRONT OFFICE	0.5		
9348007	OFFICE 3	< 0.3		
9348008	< 0.3			
9348009	< 0.3			
9348010	MAIN OFFICE	0.5		
9348011	11 OFFICE 1			
9348012	OFFICE 4	< 0.3		
9348013 BREAK ROOM 0.6				
9348014 OFFICE 2 < 0.3				
9348017 OFFICE 2 < 0.3				
9348018	OFFICE 4	0.5		
9348019	BREAKROOM	< 0.3		
9348020 BREAKROOM < 0.3				

Table 2- Radon Testing Results						
	Randolph Mainte	enace Depot				
	Test Period: 12/13/2	021-12/16/2021				
Kit Number	Kit Number QC Type Room / Area Result					
9348021 D Carpenter Shop 2.3						
9348005 FB Breakroom < 0.3						
9347000 OB OFFICE BLANK < 0.3						
9347992	ТВ	TRAVEL BLANK	< 0.3			

Table 2- Radon Testing Results						
	Randolph Transpo	rtation Depot				
	Test Period: 12/13/2021-12/16/2021					
Kit Number QC Type Room / Area Result						
9348012 D Office 4 < 0.3						
9348020 FB Breakroom < 0.3						
9347000 OB OFFICE BLANK < 0.3						
9347992						

Company of Missard Locations				
Summary of Missed Locations				
	Randolph Maintenance Depot	24		
les	t Period: 12/13/2021 - 12/16/20	21		
Kit Number	Room/Area	Result		
	NA			

Missing, Compromised and >/= 4 pi	iC/L Tests
t Period: 12/13/2021 - 12/16/2021	
Room/Area	Result
	Missing, Compromised and >/= 4 pi Randolph Maintenance Depot t Period: 12/13/2021 - 12/16/2021  Room/Area  NA

Table Note:

<sup>\*</sup> Missing or Compromised Sample

Summary of Missed Locations					
	Randolph Transportation Depot				
Tes	Test Period: 12/13/2021 - 12/16/2021				
	, , , , , , , , , , , , , , , , , , , ,				
Kit Number	Room/Area	Result			
	NA				

Summary of Missing, Compromised and >/= 4 piC/L Tests								
	Randolph Transportation Depot							
Test	Period: 12/13/2021 - 12/16/2021							
Kit Number	Kit Number Room/Area Result							
	NA							
<del></del>								
		í						

Table Note:

<sup>\*</sup> Missing or Compromised Sample

## ATTACHMENT C

# Laboratory Analytical Results

# Radon test result report for: RANDOLPH MAINTENANCE DEPOT

<b>T7</b> 0, II	D 11	G 1	P. 1.1	C! T	
Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9348032	BREAKROOM	2021-12-13 @ 1	1:00 am 2021-12-16 @ 9:00 am	$0.9 \pm 0.3$	2021-12-17
9348005	BREAKROOM 2	2021-12-13 @ 1	1:00 am 2021-12-16 @ 9:00 am	< 0.3	2021-12-17
9348015	BREAKROON 2	2021-12-13 @ 1	1:00 am 2021-12-16 @ 9:00 am	$1.4 \pm 0.3$	2021-12-17
9348002	CARPENTER SHOP	2021-12-13 @ 1	1:00 am 2021-12-16 @ 9:00 am	$2.3 \pm 0.3$	2021-12-17
9348003	CARPENTER SHOP	2021-12-13 @ 1	1:00 am 2021-12-16 @ 9:00 am	$2.0 \pm 0.3$	2021-12-17
9348021	CARPENTER SHOP	2021-12-13 @ 1	1:00 am 2021-12-16 @ 9:00 am	$2.3 \pm 0.3$	2021-12-17
9348028	CARPENTER SHOP	2021-12-13 @ 1	1:00 am 2021-12-16 @ 9:00 am	$2.0 \pm 0.3$	2021-12-17
9348031	FRONT OFFICE	2021-12-13 @ 1	1:00 am 2021-12-16 @ 9:00 am	$0.9 \pm 0.3$	2021-12-17
9348006	LEFT OFFICE	2021-12-13 @ 1	1:00 am 2021-12-16 @ 9:00 am	$1.5 \pm 0.3$	2021-12-17
9348022	OFFICE 1	2021-12-13 @ 1	1:00 am 2021-12-16 @ 9:00 am	$1.5 \pm 0.3$	2021-12-17
9341763	OFFICE 2	2021-12-13 @ 1	1:00 am 2021-12-16 @ 9:00 am	$1.5 \pm 0.3$	2021-12-17
9348024	OFFICE 3	2021-12-13 @ 1	1:00 am 2021-12-16 @ 9:00 am	$1.4 \pm 0.3$	2021-12-17
9339923	OFFICE 4	2021-12-13 @ 1	1:00 am 2021-12-16 @ 9:00 am	$2.4 \pm 0.3$	2021-12-17

## \*\* LABORATORY ANALYSIS REPORT \*\*

# Radon test result report for: RANDOLPH TRANSPORTATION DEPOT

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
9348008	BREAKROOM	2021-12-13 @ 10:00 am	2021-12-16 @ 9:00 am	< 0.3	2021-12-17
9339910	FRONT OFFICE	2021-12-13 @ 10:00 am	2021-12-16 @ 9:00 am	$0.5 \pm 0.3$	2021-12-17
9339704	OFFICE 1	2021-12-13 @ 10:00 am	2021-12-16 @ 9:00 am	< 0.3	2021-12-17

# Radon test result report for: RANDOLPH TRANSPORTATION DEPOT

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
9348009	BREAKROOM	2021-12-13 @ 10:00 a	am 2021-12-16 @ 9:00 am	< 0.3	2021-12-17
9348010	MAIN OFFICE	2021-12-13 @ 10:00 a	am 2021-12-16 @ 9:00 am	$0.5 \pm 0.3$	2021-12-17
9348011	OFFICE 1	2021-12-13 @ 10:00 a	am 2021-12-16 @ 9:00 am	< 0.3	2021-12-17
9348014	OFFICE 2	2021-12-13 @ 10:00 a	am 2021-12-16 @ 9:00 am	< 0.3	2021-12-17
9348017	OFFICE 2	2021-12-13 @ 10:00 a	am 2021-12-16 @ 9:00 am	< 0.3	2021-12-17
9348007	OFFICE 3	2021-12-13 @ 10:00 a	am 2021-12-16 @ 9:00 am	< 0.3	2021-12-17
9348012	OFFICE 4	2021-12-13 @ 10:00 a	am 2021-12-16 @ 9:00 am	< 0.3	2021-12-17
9348018	OFFICE 4	2021-12-13 @ 10:00 a	am 2021-12-16 @ 9:00 am	$0.5 \pm 0.3$	2021-12-17

## \*\* LABORATORY ANALYSIS REPORT \*\*

# Radon test result report for: RANDOLPH TRANSPORTATION DEPOT

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
9348013	BREAK ROOM	2021-12-13 @ 10:00 am	2021-12-16 @ 9:00 am	$0.6 \pm 0.3$	2021-12-17
9348019	BREAKROOM	2021-12-13 @ 10:00 am	2021-12-16 @ 9:00 am	< 0.3	2021-12-17
9348020	BREAKROOM	2021-12-13 @ 10:00 am	2021-12-16 @ 9:00 am	< 0.3	2021-12-17

## **EXPOSURE IN BOWSER-MORNER RADON CHAMBER**

CLIENT KCI Technologie	5, Jac. Job Number 203404
	_pCi/L Rel. Hum <u>28.8</u> % Temp. <u>59.9</u> F
Date Start: 12/24/21 Date Stop: 12/27/2	Date Start: Date Stop:
Time Start: 0809 Time Stop: 0809	Time Start: Time Stop:
Device No.'s: (2) Char Bags-	Device No.'s:
9341721, 9341722	I .
,	=
Gy loft	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
	*
E 0	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
=	
	2

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background =  $7 \mu R/h$  Elevation = 820 ft

December 31, 2021

## \*\* LABORATORY ANALYSIS REPORT \*\*

### Radon test result report for:

SK MA MCPS - Spike Sample Lab Results. Measured values are satisfactory, i.e., within ± 25% of the chamber's reference value (16.2 pCi/L).

9341721 1 2021-12-24 @ 8:00 am 2021-12-27 @ 8:00 am $11.6 \pm 0.9$			Ended	Started	Room Id	Kit #
	2021-12-31	$11.6 \pm 0.9$	2021-12-27 @ 8:00 am	2021-12-24 @ 8:00 am	1	9341721
9341722 1 2021-12-24 @ 8:00 am 2021-12-27 @ 8:00 am $15.4 \pm 1.2$	2021-12-31	$15.4 \pm 1.2$	2021-12-27 @ 8:00 am	2021-12-24 @ 8:00 am	1	9341722

### Engineers • Planners • Scientists • Construction Managers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

## **Radon Test Kit Chain of Custody**

Project Name: MCPS Radon - December 2021 Schools

#### Name of Schools:

- 1. 45 Gude
- 2. Concord Center
- 3. English Manor
- 4. Smith Education Center
- 5. Randolph Main. & Tran.
- 6. Rollingwood Center
- 7. Ewing at Plum Orchard

	Date	Initials
Radon Test Kits Deployed	12/13/2021	M
Radon Test Kits Collected	12/16/2021	The
Radon Test Kits Shipped to Lab*	12/16/2021	m
Radon Test Kits Received by Lab*	12/17/2021	M

<sup>\*</sup>All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759