

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

MCPS RADON TESTING

Executive Summary: Stonegate Elementary School

Date of Test Report:	4/6/2016 (Rev 1)
Round of Testing:	Initial
	Follow-up
	Post Remediation
# Rooms Tested:	33
# Rooms \geq 4.0 pCi/L:	0
Low Value:	< 0.3
High Value:	2.4

Project Status:

Initial testing completed; one sample missing (Principal Office). No further action at this time based on the results for other rooms in the facility.

KCI TECHNOLOGIES, INC. WWW.kci.com

ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

April 6, 2016 (Rev 1)

Mr. Richard Cox Indoor Air Quality Team Leader Montgomery County Public Schools 850 Hungerford Drive Rockville, MD 20850

Re: Radon Testing Services

KCI Job # 12146341.26

Location: Stonegate Elementary School

14811 Notley Road Silver Spring, MD 20905

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to the Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Stonegate Elementary School, located at 14811 Notley Road in Silver Spring, Maryland 20905 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS056) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

KCI visited the site on February 1, 2016 and deployed forty-three (43) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted six (6) test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on February 4, 2016 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc. is a NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936

KCI TECHNOLOGIES, INC. WWW.kci.com

Butler Bridge Road, Mills River, North Carolina.

Evaluation of Testing Conditions:

The operating condition that represents the greatest amount of significantly occupied time for this building is; heating active, with outdoor temperature averages $\leq 65^{\circ}$ F.

KCI concludes that the test period reasonably represents normal conditions when the building is significantly occupied. Clear characterization of the radon hazard is most likely to be observed under this normal operating condition. Based on the evaluation of test conditions, this test should reasonably characterize radon hazards.

KCI also conducted observations of field conditions which could affect the results of the test and compiled weather data for the testing period. KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

Results:

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	none n/a	
<4.0 piC/L	See Attachment B	

Notes:

D- Duplicate sample

The field blanks, office blank, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L. Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C). Laboratory results and exposure data for the spike samples are also included in Attachment C.

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 316-7800.

KCI TECHNOLOGIES, INC. WWW.kci.com

Mr. Richard Cox April 6, 2016 Page 4

Sincerely,

James M. Moulsdale

James Makler

Radon Measurement Specialist

KCI Technologies, Inc.

Attachments: A- Floor Plan with Test Locations

B- Table 1-Radon Test Summary Spreadsheet

C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Chek, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

QC- Quality Control

Radon Testing Results Stonegate Elementary School Test Period: 02/01/16-02/04/16 Kit Number Room / Area Result 7731608 1.5 7731617 2 1.7 7731613 3 8.0 7731606 4 0.7 7731604 5 1.7 7731614 0.7 6 7731620 10 8.0 7731621 11 0.6 12 7731623 < 0.3 7731605 13 0.7 7731603 14 0.6 7731602 15 0.6 7726780 17 0.7 21 7726785 0.6 7731625 22 < 0.3 7726776 26 0.9 7726790 CONF 1.5 7726772 **FAC** 0.9 7726787 G4 1.0 7726793 G4 1.3 GOF 7731619 1.5 7731622 HE 1.5 7726783 IMC 2.0 7726784 IMC 2.4 7731611 KIT 1.1 7731618 ML408 < 0.3 7731616 ML488 8.0 7731615 ML554 < 0.3 7731624 ML752 < 0.3 7726778 MPR 1.5 7726782 MPR 1.1 7731612 PΕ 1.9 7726794 PEO 1.0 7721409 PRN (Missing) 7731601 SHARK SHACK 0.9 7726779 WR 1.5

^{*} Missing or Compromised Sample

	Radon Testing Results Stonegate Elementary School		
Test Period: 02/01/16-02/04/16			
Kit Number	QC Type	Result	
7731609	D (11)	0.8	
7726774	D (17)	< 0.3	
7731610	D (2)	1.3	
7726777	D (GOF)	1.3	
7731607	FB (3)	< 0.3	
7726773	FB (PEO)	< 0.3	
7726788	OB (0)	< 0.3	

ATTACHMENT C

Laboratory Analytical Results

Radon test result report for:
STONEGATE ELEMENTARY SCHOOL
MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7726788	0	2016-02-01 @ 11:00 am	2016-02-04 @ 10:00 am	< 0.3	2016-02-09
7731608	1	2016-02-01 @ 9:00 am	2016-02-04 @ 8:00 am	1.5 ± 0.5	2016-02-09
7731620	10	2016-02-01 @ 9:00 am	2016-02-04 @ 8:00 am	0.8 ± 0.4	2016-02-08
7731609	11	2016-02-01 @ 9:00 am	2016-02-04 @ 8:00 am	0.8 ± 0.3	2016-02-08
7731621	11	2016-02-01 @ 9:00 am	2016-02-04 @ 8:00 am	0.6 ± 0.4	2016-02-09
7731623	12	2016-02-01 @ 9:00 am	2016-02-04 @ 8:00 am	< 0.3	2016-02-09
7731605	13	2016-02-01 @ 9:00 am	2016-02-04 @ 8:00 am	0.7 ± 0.4	2016-02-09
7731603	14	2016-02-01 @ 9:00 am	2016-02-04 @ 8:00 am	0.6 ± 0.3	2016-02-08
7731602	15	2016-02-01 @ 9:00 am	2016-02-04 @ 8:00 am	0.6 ± 0.4	2016-02-09
7726774	17	2016-02-01 @ 10:00 am	2016-02-04 @ 9:00 am	< 0.3	2016-02-08
7726780	17	2016-02-01 @ 10:00 am	2016-02-04 @ 9:00 am	0.7 ± 0.4	2016-02-08
7731610	2	2016-02-01 @ 9:00 am	2016-02-04 @ 8:00 am	1.3 ± 0.4	2016-02-09
7731617	2	2016-02-01 @ 9:00 am	2016-02-04 @ 8:00 am	1.7 ± 0.4	2016-02-09
7726785	21	2016-02-01 @ 10:00 am	2016-02-04 @ 9:00 am	0.6 ± 0.4	2016-02-09
7731625	22	2016-02-01 @ 10:00 am	2016-02-04 @ 9:00 am	< 0.3	2016-02-09
7726776	26	2016-02-01 @ 11:00 am	2016-02-04 @ 9:00 am	0.9 ± 0.4	2016-02-09
7731607	3	2016-02-01 @ 9:00 am	2016-02-04 @ 8:00 am	< 0.3	2016-02-09
7731613	3	2016-02-01 @ 9:00 am	2016-02-04 @ 8:00 am	0.8 ± 0.4	2016-02-09
7731606	4	2016-02-01 @ 9:00 am	2016-02-04 @ 8:00 am	0.7 ± 0.4	2016-02-08
7731604	5	2016-02-01 @ 9:00 am	2016-02-04 @ 8:00 am	1.7 ± 0.4	2016-02-09
7731614	6	2016-02-01 @ 9:00 am	2016-02-04 @ 8:00 am	0.7 ± 0.4	2016-02-09
7726790	CONF	2016-02-01 @ 10:00 am	2016-02-04 @ 8:00 am	1.5 ± 0.4	2016-02-09
7726772	FAC	2016-02-01 @ 10:00 am	2016-02-04 @ 9:00 am	0.9 ± 0.4	2016-02-09
7726787	G4	2016-02-01 @ 10:00 am	2016-02-04 @ 9:00 am	1.0 ± 0.4	2016-02-09
7726793	G4	2016-02-01 @ 10:00 am	2016-02-04 @ 9:00 am	1.3 ± 0.4	2016-02-09
7726777	GOF	2016-02-01 @ 9:00 am	2016-02-04 @ 8:00 am	1.3 ± 0.4	2016-02-09
7731619	GOF	2016-02-01 @ 9:00 am	2016-02-04 @ 8:00 am	1.5 ± 0.4	2016-02-09
7731622	HE	2016-02-01 @ 10:00 am	2016-02-04 @ 8:00 am	1.5 ± 0.4	2016-02-09
7726783	IMC	2016-02-01 @ 10:00 am	2016-02-04 @ 9:00 am	2.0 ± 0.5	2016-02-09
7726784	IMC	2016-02-01 @ 10:00 am	2016-02-04 @ 9:00 am	2.4 ± 0.5	2016-02-09
7731611	KIT	2016-02-01 @ 10:00 am	2016-02-04 @ 9:00 am	1.1 ± 0.4	2016-02-09
7726778	MPR	2016-02-01 @ 10:00 am	2016-02-04 @ 8:00 am	1.5 ± 0.4	2016-02-09
7726782	MPR	2016-02-01 @ 10:00 am	2016-02-04 @ 8:00 am	1.1 ± 0.4	2016-02-09
7731612	PE	2016-02-01 @ 10:00 am	2016-02-04 @ 8:00 am	1.9 ± 0.5	2016-02-09
7726773	PEO	2016-02-01 @ 10:00 am	2016-02-04 @ 9:00 am	< 0.3	2016-02-09
7726794	PEO	2016-02-01 @ 10:00 am	2016-02-04 @ 9:00 am	1.0 ± 0.4	2016-02-09
7721409	PRN	@	@		

February LABORATORY ANALYSIS 23, REPORT **

Radon test result report for:
STONEGATE ELEMENTARY SCHOOL MAIN

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7731601	SHARK SHACK	2016-02-01 @ 9:00 am	2016-02-04 @ 8:00 am	0.9 ± 0.4	2016-02-09
7726779	WR	2016-02-01 @ 10:00 am	2016-02-04 @ 8:00 am	1.5 ± 0.4	2016-02-09

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

February LABORATORY ANALYSIS 23, REPORT **

Radon test result report for:
STONEGATE ELEMENTARY SCHOOL PORTABLE

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7731618	ML408	2016-02-01 @ 9:00 am	2016-02-04 @ 8:00 am	< 0.3	2016-02-09
7731616	ML488	2016-02-01 @ 8:00 am	2016-02-04 @ 8:00 am	0.8 ± 0.4	2016-02-09
7731615	ML554	2016-02-01 @ 9:00 am	2016-02-04 @ 8:00 am	< 0.3	2016-02-09
7731624	ML752	2016-02-01 @ 9:00 am	2016-02-04 @ 8:00 am	< 0.3	2016-02-09
7731624	ML752	2016-02-01 @ 9:00 am	2016-02-04 @ 8:00 am	< 0.3	2010

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

February LABORATORY ANALYSIS 23, REPORT **

Radon test result report for:
TRANSIT- PHASE 7, 8, 9
NONE

Rit# Room Id Started Started PCi/L Analyzed						
7734946 10 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7734955 11 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734956 12 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734959 13 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734959 14 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734953 15 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734954 16 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734940 17 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734943 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734942 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734939 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734939 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 21 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 25 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 25 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 29 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 31 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734931 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 4 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2	7734937	1	2016-02-19 @ 3:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734956 12 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734959 13 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734930 14 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734953 15 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734954 16 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734940 17 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734939 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734929 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734929 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734933 22 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 25 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734937 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734937 31 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734937 31 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734931 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734931 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734931 31 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 201	7734946	10	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734959 13 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734955	11	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734930 14 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am	7734956	12	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734953 15 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am	7734959	13	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734954 16 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734930	14	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734940 17 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734953	15	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734954	16	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734948 19 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734940	17	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734939 2 2016-02-19 @ 3:00 pm 2016-02-22 @ 11:00 am < 0.3	7734949	18	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734942 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734948	19	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734929 21 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734939	2	2016-02-19 @ 3:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734933 22 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734942	20	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734929	21	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734936 24 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734933	22	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734943 25 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734934	23	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734944 26 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734936	24	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734943	25	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734928 28 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734944	26	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734952 29 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734935	27	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734947 3 2016-02-19 @ 3:00 pm 2016-02-22 @ 11:00 am < 0.3	7734928	28	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734931 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734952	29	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734932 31 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734947	3	2016-02-19 @ 3:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7718520 32 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734931	30	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7718523 33 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734932	31	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7718522 34 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7718520	32	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7718521 35 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7718523	33	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734945 4 2016-02-19 @ 3:00 pm 2016-02-22 @ 11:00 am < 0.3	7718522	34	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	
7734960 5 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7718521	35	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734958 6 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734951 7 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734957 8 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23	7734945	4	2016-02-19 @ 3:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734951 7 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734957 8 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23		5	1			2016-02-23
7734957 8 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23	7734958	6	•	2016-02-22 @ 11:00 am		2016-02-23
<u>.</u>	7734951	7	•			2016-02-23
7734938 9 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23			•			
	7734938	9	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

February LABORATORY ANALYSIS 15, REPORT **

Spike Sample Laboratory Results

Radon test result report for: MCPS

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7718273	101A	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.5 ± 0.6	2016-02-04
7718281	102B	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.4 ± 0.6	2016-02-04
7718282	103C	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.3 ± 0.6	2016-02-04
7718288	104D	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.7 ± 0.6	2016-02-04
7718289	105E	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.6 ± 0.6	2016-02-04
7718291	106F	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.5 ± 0.6	2016-02-04

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Note: Spike samples are test canisters that are deliberately exposed to a controlled high level of radon in a laboratory. They provide a quality control measure in the testing process and do NOT reflect radon levels in the building being tested.

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI Technologica	Inc. Job Number 173704
	pCi/L Rel. Hum 45.9 % Temp. 79.0
Date Start: 1/30/16 Date Stop: 2/1/16	Date Start: Date Stop:
Time Start: <u>O9ab</u> Time Stop: <u>O9ab</u>	Time Start: Time Stop:
Device No.'s: (6) Char. Bags-	Device No.'s:
7718281, 7718282, 7718291,	
7718288, 7718289, 7718273	
E3 Left	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
	· · · · · · · · · · · · · · · · · · ·

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = $7 \mu R/h$ Elevation = 820 ft



Engineers • Planners • Scientists • Construction Managers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon Phase 7 (2-1-2016)

Name of School/Facility:

1.	Wyngate E.S.	10. Bethesda Depot	18. Stone Mill E.S.
2.	Seven Locks E.S.	11. Bethesda Trans Depot	19. Strawberry Knoll E.S.
3.	Takoma Park M.S.	12. Sligo M.S.	20. Shady Grove M.S.
4.	Somerset E.S.	13. Stonegate E.S.	21. Washington Grove E.S.
5.	Silver Spring Int. M.S.	14. Randolph Transportation	22. Sherwood E.S.
6.	Sligo Creek E.S.	15. Earl B. Wood M.S.	23. Woodfield E.S.
7.	Tilden M.S.	16. Sargent Shriver E.S.	24. Taylor Learning Center
8.	Tilden Center	17. Thomas Wooten H.S.	25. Kingsley Wilderness

9. Bethesda Annex

	Date	Initials
Radon Test Kits Deployed	2/1/16	M
Radon Test Kits Collected	2/4/16	JM
Radon Test Kits Shipped to Lab*	2/4/16	UM
Radon Test Kits Received by Lab*	2/8/16	JM

^{*}All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759



Engineers • Planners • Scientists • Construction Managers

Corporate Office: 936 Ridgebrook road • Sparks, Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon Phase 7 (2-2-2016)

Name of School/Facility:

4	_			_	
7	()	ncor	'M'	Or	ntar

- 2. Lynnbrook Center
- 3. Carver (CESC)
- 4. Spring Mill (area 1 Office)
- 5. Wheaton H.S
- 6. Montrose Center
- 7. West Farm Trans Depot

- 8. Food & Nutritional Services
- 9. Fairland Center
- 10. Redland M.S. (retest)
- 11. Clarksburg Trans Depot
- 12. Clarksburg Main Depot
- 13. Clarksburg E.S.

	Date	Initials
Radon Test Kits Deployed	2/2/16	JM
Radon Test Kits Collected	2/5/16	JM
Radon Test Kits Shipped to Lab*	2/5/16	UM
Radon Test Kits Received by Lab*	2/9/16	JU

^{*}All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759