936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

MCPS RADON TESTING – EXECUTIVE SUMMARY

Site Name	Cannon Road
	Elementary School
Date of Test Report	3/2/2023
Round of Testing	Initial
	Follow-up
	Post Remediation
	2 Year Testing
	5 Year Testing
	HVAC Upgrade
	Window Replacement
	New Addition
	New Facility
# Rooms Tested	46
# Room Re-tested	2
# Rooms ≥ 4.0 pCi/L	0
Lowest Value	<0.3 pCi/L
Highest Value	1.0 pCi/L

Project Status:

- 1. Initial testing completed;
- 2. Missing or compromised samples need re-test.
 - 3. Retesting Completed 2/14/23 2/17/23.
 - 4. 5-Year Testing Completed.

KCI Technologies, Inc. WWW.kci.com

Employee-Owned Since 1988



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

March 2, 2023

Mr. Brian Croyle Environmental Specialist Montgomery County Public Schools Gaithersburg, MD 20879

Re: Radon Testing Services

KCI Job # 122210551

Location: Cannon Road Elementary School

901 Cannon Road

Silver Spring, MD 20904

Dear Mr. Croyle:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Cannon Road Elementary School, located at 901 Cannon Rd. Silver Spring, MD 20904 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Proficiency Program (NRPP) Radon Measurement Specialist (certification #111004 RT) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from https://www.montgomeryschoolsmd.org or www.epa.gov/radon.

KCI visited the site initially on January 23, 2023 and deployed fifty one (51) activated charcoal (AC) radon test kits. KCI deployed radon test kits in all frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance.

KCI returned to the site on January 26, 2023 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Accustar Labs - MA. for analysis by gamma-ray spectroscopy. Accustar Labs - MA is a NRSB certified analytical laboratory for radon analysis (certification #ARL0017) located at 2 Saber Way, Ward Hill, MA 01835.

KCI re-visited the site on February 14, 2023 to deploy four (4) activated charcoal (AC) radon test kits for testing of missed rooms or compromised test kits during initial testing.

KCI returned to the site on February 17, 2023 to retrieve the radon re-sampling test kits. KCI shipped all radon tests via overnight delivery to Accustar Labs – MA for analysis by gamma-ray spectroscopy. Accustar Labs – MA is a NRSB certified analytical laboratory for radon analysis (certification #ARL0017) located at 2 Saber Way, Ward Hill, MA 01835.

A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI also included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

Evaluation of Testing Conditions:

These tests represent:

• Follow up to initial testing.

These tests were conducted to:

• Evaluate radon concentration levels at the facility.

According to AARST, Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room during the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate temperatures ranged from the 31°F to 52°F. Maximum sustained winds ranged from 5-25 miles per hour. Average humidity was around 60% with .32 inches of precipitation (rain) was recorded during testing period.

During the re-testing period, weather records indicate low temperatures were in the mid-20s°F and high temperatures ranged to the 70s°F. Maximum sustained winds ranged from 0-33 miles per hour. Average humidity was around 62% with 1.01 inches of precipitation (rain) was recorded during testing period.

KCI TECHNOLOGIES, INC. WWW.kci.com

Employee-Owned Since 1988

Results:

The sampling locations and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). Sampling locations and associated test kit identification numbers and relevant field observations are listed on Table 3 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	None	N/A
<4.0 piC/L	See Attachment B	

The results of the radon re-testing analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	None	N/A
<4.0 piC/L	See Attachment B	

Quality Control Samples		
Results of Blank Canisters:	The office blanks, and lab transit blanks had test results of	
	less than the laboratory detection limit of 0.3 pCi/L.	
Adequate Laboratory Precision?	Review of the duplicate sample analysis indicates that	
	adequate laboratory measurement precision was achieved.	
Spike Sample Analysis:	The Spike Sample analysis results indicate the laboratory is	
	operating within statistical control limits.	

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 891-1769.

Sincerely,

Tyler P. McCleaf

Radon Measurement Provider

#111004 RT

KCI Technologies, Inc.

Tyler McCleaf

Attachments: A- Floor Plan with Test Locations

B- Table 1-3, Radon Test Summary Spreadsheets

C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Check, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

OC- Quality Control

Table 1- Radon Testing Results	
Cannon Road FS	

Test Period: 01/23/2023 - 01/26/2023

Kit Number	Room / Area	Result
11287559	100	< 0.3
11287560	100	0.6
11287558	102	< 0.3
11287580	105	0.6
11287563	107	< 0.3
11287566	107	< 0.3
11287570	107	< 0.3
11287572	111	< 0.3
11287565	112	0.6
11287577	115	< 0.3
11287564	116	< 0.3
11287576	117	< 0.3
11287571	120	< 0.3
11287578	121	< 0.3
11287573	124	0.5
11287574	124	< 0.3
11287561	126	< 0.3
11287575	130	< 0.3
11287589	140	0.6
11287590	140	0.9
11287547	141	0.5
11287554	145	0.6
11287587	146	< 0.3
11287582	150	< 0.3
11287588	151	N/A
11287579	154	0.6
11287581	154	< 0.3
11287586	154	< 0.3
11287583	156	< 0.3
11287592	157	< 0.3
11287585	158	< 0.3
11287597	162	< 0.3
11287595	166	0.5
11287596	170	< 0.3
11287548	179	1.0
11287556	179	< 0.3
11287555	180	0.6
11287599	200	< 0.3
11287600	200	< 0.3
11287594	211	< 0.3
11287593	232	< 0.3
11287591	242	< 0.3

Table 1- Radon Testing Results				
	Cannon Road ES			
Tes	st Period: 01/23/2023 - 01/26/2023	3		
Kit Number	Room / Area	Result		
11287598	279	0.5		
11287569	100A	< 0.3		
11287568	100B	0.6		
11287567	100C	0.8		
11287562	100H	< 0.3		
11287557	102B	< 0.3		
11287584	140A	N/A		
11287553	179B.1	< 0.3		
11287552	182A	0.5		
11287549	GYM 182	0.6		
11287550	GYM 182	1.0		

Table 2- Radon Testing Results			
	Canı	non Road ES	
	Test Period:	01/23/23 - 01/26/23	
Kit Number	QC Type	Room / Area	Result
11287560	D	100	0.6
11287563	FB	107	< 0.3
11287570	D	107	< 0.3
11287574	D	124	< 0.3
11287581	D	154	< 0.3
11287586	FB	154	< 0.3
11287600	D	200	< 0.3
11633990	ОВ	OFFICE BLANK	< 0.3
11633992	ТВ	TRAVEL BLANK	< 0.3

Summary of Missed Locations			
	Cannon Road ES		
Т	est Period: 01/23/23 - 01/26/23		
Kit Number	Room/Area	Result	
	N/A		

Summary of	of Missing, Compromised and >/= 4	4 piC/L Tests			
	Cannon Road ES				
	Test Period: 01/23/23 - 01/26/23	3			
Kit Number Room/Area Resu					
11287584	140A	Missing			
11287588	151	Missing			

Table Note:

^{*} Missing or Compromised Sample

Table 1- Radon Testing Results			
	Cannon Road ES RT		
Tes	t Period: 02/14/2023 - 02/17/2023	3	
Kit Number Room / Area Result			
11633989 151 (0.6	
11634053 151 < 0.3		< 0.3	
11634051 140A 0.7			
11634052	140A	0.6	

Table 2- Radon Testing Results				
	Canno	on Road ES RT		
	Test Period: (02/14/23 - 02/17/23		
Kit Number	QC Type	Room / Area	Result	
11634052	D	140a	0.6	
11634053	FB	151	< 0.3	
11634060	OB	OFFICE BLANK	< 0.3	
11634067	ТВ	TRAVEL BALNK	< 0.3	

Summary of Missed Locations				
Cannon Road ES RT				
Т	Test Period: 02/14/23 - 02/17/23			
Kit Number	Room/Area	Result		
	N/A			

Summary of Mi	issing, Compromised and >/	= 4 piC/L Tests
	Cannon Road ES RT	
Tes	t Period: 02/14/23 - 02/17/	23
Kit Number	Room/Area	Result
	N/A	

Table Note:

^{*} Missing or Compromised Sample

ATTACHMENT C

Laboratory Analytical Results

Radon test result report for: CANNON ROAD ES MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11287559	100	2023-01-23 @ 8:00 am	2023-01-26 @ 1:00 pm	< 0.3	2023-01-30
11287560	100	2023-01-23 @ 8:00 am	2023-01-26 @ 1:00 pm	0.6 ± 0.3	2023-01-30
11287569	100A	2023-01-23 @ 8:00 am	2023-01-26 @ 1:00 pm	< 0.3	2023-01-30
11287568	100B	2023-01-23 @ 8:00 am	2023-01-26 @ 1:00 pm	0.6 ± 0.3	2023-01-30
11287567	100C	2023-01-23 @ 8:00 am	2023-01-26 @ 1:00 pm	0.8 ± 0.3	2023-01-30
11287562	100H	2023-01-23 @ 8:00 am	2023-01-26 @ 1:00 pm	< 0.3	2023-01-30
11287558	102	2023-01-23 @ 8:00 am	2023-01-26 @ 1:00 pm	< 0.3	2023-01-30
11287557	102B	2023-01-23 @ 8:00 am	2023-01-26 @ 1:00 pm	< 0.3	2023-01-30
11287580	105	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	0.6 ± 0.3	2023-01-30
11287563	107	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287570	107	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287566	107	2023-01-23 @ 8:00 am	2023-01-26 @ 1:00 pm	< 0.3	2023-01-30
11287572	111	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287565	112	2023-01-23 @ 8:00 am	2023-01-26 @ 1:00 pm	0.6 ± 0.3	2023-01-30
11287577	115	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287564	116	2023-01-23 @ 8:00 am	2023-01-26 @ 1:00 pm	< 0.3	2023-01-30
11287576	117	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287571	120	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287578	121	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287573	124	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	0.5 ± 0.3	2023-01-30
11287574	124	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287561	126	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287575	130	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287589	140	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	0.6 ± 0.3	2023-01-30
11287590	140	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	0.9 ± 0.3	2023-01-30
11287547	141	2023-01-23 @ 8:00 am	2023-01-26 @ 1:00 pm	0.5 ± 0.3	2023-01-30
11287554	145	2023-01-23 @ 8:00 am	2023-01-26 @ 1:00 pm	0.6 ± 0.3	2023-01-30
11287587	146	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287582	150	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287579	154	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	0.6 ± 0.3	2023-01-30
11287586	154	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287581	154	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287583	156	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287592	157	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287585	158	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287597	162	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287595	166	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	0.5 ± 0.3	2023-01-30
			_		

Radon test result report for: CANNON ROAD ES MAIN

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
11287596	170	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287548	179	2023-01-23 @ 8:00 am	2023-01-26 @ 1:00 pm	1.0 ± 0.3	2023-01-30
11287556	179	2023-01-23 @ 8:00 am	2023-01-26 @ 1:00 pm	< 0.3	2023-01-30
11287553	179B.1	2023-01-23 @ 8:00 am	2023-01-26 @ 1:00 pm	< 0.3	2023-01-30
11287555	180	2023-01-23 @ 8:00 am	2023-01-26 @ 1:00 pm	0.6 ± 0.3	2023-01-30
11287552	182A	2023-01-23 @ 8:00 am	2023-01-26 @ 1:00 pm	0.5 ± 0.3	2023-01-30
11287600	200	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287599	200	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287594	211	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287593	232	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287591	242	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	< 0.3	2023-01-30
11287598	279	2023-01-23 @ 9:00 am	2023-01-26 @ 2:00 pm	0.5 ± 0.3	2023-01-30
11287549	GYM 182	2023-01-23 @ 8:00 am	2023-01-26 @ 1:00 pm	0.6 ± 0.3	2023-01-30
11287550	GYM 182	2023-01-23 @ 8:00 am	2023-01-26 @ 1:00 pm	1.0 ± 0.3	2023-01-30

February 20, 2023

** LABORATORY ANALYSIS REPORT **

Radon test result report for: CANNON ROAD ES 1

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11634051	140A	2023-02-14 @ 9:00 am	2023-02-17 @ 10:00 am	0.7 ± 0.3	2023-02-20
11634052	140A	2023-02-14 @ 9:00 am	2023-02-17 @ 10:00 am	0.6 ± 0.3	2023-02-20
11633989	151	2023-02-14 @ 9:00 am	2023-02-17 @ 10:00 am	0.6 ± 0.3	2023-02-20
11634053	151	2023-02-14 @ 9:00 am	2023-02-17 @ 10:00 am	< 0.3	2023-02-20

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI TECHNOLOGI	ES, /NC Job Number 208802
	_pCi/L Rel. Hum <u> </u>
Date Start: 1/27/23 Date Stop: 1/30/	3 Date Start: Date Stop:
	Time Start: Time Stop:
Device No.'s: (5) CHAR BAGS.	Device No.'s:
11633682,11633687,11633688	
11633695 11633696	
F3 Celt	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
B 1 22	Device No.'s:
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = $7 \mu R/h$ Elevation = 820 ft

February 3, 2023

** LABORATORY ANALYSIS REPORT **

Radon test result report for: OFFICE MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11633696	SK10	2023-01-27 @ 8:00 am	2023-01-30 @ 8:00 am	24.2 ± 1.9	2023-02-03
11633682	SK6	2023-01-27 @ 8:00 am	2023-01-30 @ 8:00 am	26.9 ± 2.1	2023-02-03
11633687	SK7	2023-01-27 @ 8:00 am	2023-01-30 @ 8:00 am	23.8 ± 1.9	2023-02-03
11633688	SK8	2023-01-27 @ 8:00 am	2023-01-30 @ 8:00 am	25.9 ± 2.1	2023-02-03
11633695	SK9	2023-01-27 @ 8:00 am	2023-01-30 @ 8:00 am	27.0 ± 2.2	2023-02-03



Engineers • Planners • Scientists • Construction Managers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon - Week 2 Retesting January Schools

Name of Schools:

- 1. A. Mario Loiederman MS
- 2. Cannon Road ES
- 3. Forest Knolls ES
- 4. Glen Haven ES
- 5. Goshen ES
- 6. Highland View ES
- 7. John F. Kennedy HS
- 8. Lakelands Park MS
- 9. Montgomery Village MS
- 10.Poolesville HS
- 11.Springbrook HS

	Date	Initials
Radon Test Kits Deployed	02/14/2023	BMU
Radon Test Kits Collected	02/17/2023	BMMI
Radon Test Kits Shipped to Lab*	02/17/2023	pen
Radon Test Kits Received by Lab*	02/20/2023	Bon

^{*}All samples sent to Air Check, Inc., 2 Saber Way, Ward Hill, MA 01835

RADON SCREENING SURVEY – FOLLOW-UP CANNON ROAD ELEMENTARY SCHOOL

901 Cannon Road,

Silver Spring, Maryland 20904

EXECUTIVE SUMMARY

Date of Test Report:	3/20/19
Round of Testing:	Initial
	Follow-up
	Post Remediation
# Rooms Tested	1
# Rooms ≥ 4.0 pCi/L:	0
Low Value:	3.0
High Value:	3.0
Confirmed Rooms ≥ 4.0 pCi/L US EPA	0
Action Level	

Summary of Sampling Events ≥ 4.0 pCi/L

Room	Result (pCi/L) 2/13/19	Result (pCi/L) 3/20/19	Average Result (pCi/L)
140A	4.3	3.0	3.7



MONTGOMERY COUNTY PUBLIC SCHOOLS RADON TESTING

Executive Summary: Cannon Road Elementary School

901 Cannon Road, Silver Spring, MD 20904

Date of Test Report:	3/20/2019
Round of Testing:	Initial
	Follow-up
	Post Remediation
	2 Year Testing
	5 Year Testing
	HVAC Upgrade
	Window Replacement
	New Addition
	New Facility
# of Rooms Tested:	1
# of Rooms ≥ 4.0 pCi/L:	0
Low Value:	3.0
High Value:	3.0

Project Status

Retesting completed: No further action at this time.



March 20, 2019

Mr. Richard Cox Indoor Air Quality Team Leader Montgomery County Public Schools 850 Hungerford Drive Rockville, MD 20850

Re: Radon Testing Services

Location: Cannon Road Elementary School

901 Cannon Road,

Silver Spring, MD 20904

Dear Mr. Cox:

Intertek-PSI (PSI) is pleased to submit the following report to the Montgomery County Public Schools (MCPS) for completion of a "short-term" 3-day radon test for Cannon Road Elementary School, located at 901 Cannon Road, Silver Spring, MD 20904 (subject site).

Scope of Services:

PSI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. PSI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS007) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

PSI visited the site on February 25, 2019 and deployed one (1) activated charcoal (AC) radon test kit. PSI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. PSI returned to the site on February 28, 2019 to retrieve the radon sampling test kit. A floor plan map of the building with the test location is included as Attachment A of this report.

PSI shipped all radon tests via overnight delivery to AccuStar Labs for analysis by gamma-ray spectroscopy. Accustar Labs is a NRSB certified analytical laboratory for radon analysis located at 929 Mount Zion Road, Lebanon, Pennsylvania (certification # ARL0007).

Evaluation of Testing Conditions:

The operating condition that represents the greatest amount of significantly occupied time for this building is; heating active, with outdoor temperature averages \leq 65°F.

PSI concludes that the test period reasonably represents normal conditions when the building is significantly occupied. Clear characterization of the radon hazard is most likely to be observed under this normal operating condition. Based on the evaluation of test conditions, this test should reasonably characterize radon hazards.



PSI also conducted observations of field conditions which could affect the results of the test and compiled weather data for the testing period. PSI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

Results:

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥ 4.0 pCi/L	None	NA
≤ 4.0 pCi/L	See Attachment B	

Notes:

D - Duplicate Sample

The office blank and lab transit blanks had test results of less than the laboratory detection limit of 0.4 pCi/L. Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C).

Laboratory results and exposure data for the spike samples are also included in Attachment C. Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (703) 698-9300.

Respectfully Submitted,

INTERTEK - PSI

Nand Kaushik, P.E.

Department Manager, Environmental Services

Nand.Kaushik@intertek.com

Non-April Coulin

Attachments: A – Floor Plan with Test Locations

B – Table 1 – Radon Test Summary Spreadsheet

C – Laboratory Analytical Results

ATTACHMENT B

Radon Test Summary Spreadsheet

Radon Testing Results					
Cannon Road Elementary School					
Testing period: 2/25/19 - 2/28/19					
Kit Number	Room / Area	Result (pCi/L)			
3923470	140A (IMC Office)	3.0			

Table Notes:

- D Duplicate
- FB Field Blank
- OB Office Blank
- TB Transit Blank
- QC Quality Control

ATTACHMENT C

Laboratory Analytical Results



NRPP 105011 AL NRSB ARL0007 EPA Method #402-R-92-004 Charcoal Canister NRPP Device Code 6048 NRSB Device Code 10317

Laboratory Report for: Property Tested: Project # 04481387-1

Intertek-PSI (VA) MCPS Radon Survey Cannon Road ES 2930 Eskridge Road 901 Cannon Road Fairfax VA 22031 Silver Spring MD 20904

 Log
 Device Number
 Test Exposure Duration:
 Area Tested
 Result pCi/L

 3220704
 3923470
 02/25/2019
 12:30 pm
 02/28/2019
 11:10 am
 Floor Main Room 140A (IMC Office)
 3.0

Comment: A copy of this report was e-mailed to Intertek-PSI (VA)

Distributed by: Intertek-PSI (VA)

Date Received: 03/04/2019 Date Logged: 03/04/2019 Date Analyzed: 03/05/2019 Date Reported: 03/05/2019

Report Reviewed By: _

Disclaimer:

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



MONTGOMERY COUNTY PUBLIC SCHOOLS RADON TESTING

Executive Summary: Cannon Road Elementary School

901 Cannon Road, Silver Spring, MD 20904

Date of Test Report:	2/13/2018		
Round of Testing:	Initial		
	Follow-up		
	Post Remediation		
	2 Year Testing		
	5 Year Testing		
	HVAC Upgrade		
	Window Replacement		
	New Addition		
	New Facility		
# of Rooms Tested:	44		
# of Rooms ≥ 4.0 pCi/L:	1		
Low Value:	< 0.4		
High Value:	4.3		
Rooms with Results ≥ 4.0 pCi/L:	140A		

Project Status

Initial testing complete: Re-test needed for results ≥ 4.0 pCi/L.



February 13, 2019

Mr. Richard Cox Indoor Air Quality Team Leader Montgomery County Public Schools 850 Hungerford Drive Rockville, MD 20850

Re: Radon Testing Services

Location: Cannon Road Elementary School

901 Cannon Road,

Silver Spring, MD 20904

Dear Mr. Cox:

Intertek-PSI (PSI) is pleased to submit the following report to the Montgomery County Public Schools (MCPS) for completion of a "short-term" 3-day radon test for Cannon Road Elementary School, located at 901 Cannon Road, Silver Spring, MD 20904 (subject site).

Scope of Services:

PSI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. PSI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS007) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

PSI visited the site on November 13, 2018 and deployed fifty-seven (57) activated charcoal (AC) radon test kits. PSI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. PSI returned to the site on November 16, 2018 to retrieve the radon sampling test kits. A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, PSI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, PSI submitted ten (10) test kits to Bowser-Morner Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner Inc. prior to being returned to the laboratory for analysis.

PSI shipped all radon tests via overnight delivery to AccuStar Labs for analysis by gamma-ray spectroscopy. Accustar Labs is a NRSB certified analytical laboratory for radon analysis located at 929 Mount Zion Road, Lebanon, Pennsylvania (certification # ARL0007) and 2 Saber Way, Haverhill, Massachusetts (certification # ARL0017).



Evaluation of Testing Conditions:

The operating condition that represents the greatest amount of significantly occupied time for this building is; heating active, with outdoor temperature averages \leq 65°F.

PSI concludes that the test period reasonably represents normal conditions when the building is significantly occupied. Clear characterization of the radon hazard is most likely to be observed under this normal operating condition. Based on the evaluation of test conditions, this test should reasonably characterize radon hazards.

PSI also conducted observations of field conditions which could affect the results of the test and compiled weather data for the testing period. PSI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

Results:

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result	
≥ 4.0 pCi/L	140A	4.3	
≤ 4.0 pCi/L	See Attachment B		

Notes:

D - Duplicate Sample

The office blank and lab transit blanks had test results of less than the laboratory detection limit of 0.4 pCi/L. Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C).

Laboratory results and exposure data for the spike samples are also included in Attachment C. Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (703) 698-9300.



Respectfully Submitted,

INTERTEK-PSI

Nand Kaushik, P.E.

Department Manager, Environmental Services

Nand.Kaushik@intertek.com

Non-April Coulin

Attachments: A – Floor Plan with Test Locations

B – Table 1 – Radon Test Summary Spreadsheet

C – Laboratory Analytical Results

ATTACHMENT B

Radon Test Summary Spreadsheet

	Radon Testing Results						
	annon Road Elementary Scho						
Testing period: 11/13/18 - 11/16/18							
Kit Number	Room / Area	Result (pCi/L)					
3918211	100	0.5					
3918210	102	< 0.4					
3918206	105	0.7					
3918231	107	1.0					
3918212	111	2.4					
3918204	112	0.4					
3918201	115	1.8					
3918024	116	0.7					
3918228	117	1.6					
3918221	120	0.4					
3918041	121	0.9					
3918025	124	2.3					
3918031	126	0.4					
3918226	130	0.4					
3918233	140	2.1					
3918234	140	2.9					
3918232	141	< 0.4					
3918236	145	0.8					
3918238	146	1.3					
3918222	149	0.7					
3918239	150	< 0.4					
3918237	151	< 0.4					
3918161	154	0.5					
3918162	154	0.5					
3918163	156	< 0.4					
3918166	157	0.7					
3918164	158	1.4					
3918165	162	0.4					
3918167	166	1.2					
3918168	170	0.6					
3881191	179	1.1					
3881232	179	1.3					
3918169	180	0.5					
3881240	182	0.4					
3881242	182	0.4					
3918217	204	0.5					
3918218	215	0.6					
3918216	244	< 0.4					
3918208	100A	< 0.4					
3918209	100B	0.9					
3918202	100C	2.5					
3918227	100G	0.4					
3918205	100H	0.9					

	Radon Testing Results						
	Cannon Road Elementary School						
Tes	Testing period: 11/13/18 - 11/16/18						
Kit Number	Kit Number Room / Area Result (pCi/L)						
3918203	102B	< 0.4					
3918235	140A	4.3					
3918220	179B	0.7					
3918214	179B	1.7					
3918213	182A	< 0.4					

	Radon Testing Results							
Cannon Road Elementary School								
Te	Testing period: 11/13/18 - 11/16/18							
Kit Number	Kit Number QC Type Result (pCi/L)							
3918224	111 (D)	0.9						
3918207	112 (D)	< 0.4						
3918215	149 (D)	0.9						
3918240	150 (D)	0.6						
3918170	180 (D)	0.4						
3916033	Field Blank	< 0.4						
3916035	Field Blank	< 0.4						
3918005	Office Blank	< 0.4						
3918006	Trip Blank	< 0.4						

Table Notes:

- D Duplicate
- FB Field Blank
- OB Office Blank
- TB Transit Blank
- QC Quality Control

ATTACHMENT C

Laboratory Analytical Results



EPA Method #402-R-92-004 Charcoal Canister NRPP Device Code 6048 NRSB Device Code 10317

Laboratory Report for:

Intertek-PSI (VA) 2930 Eskridge Road

Fairfax VA 22031

Property Tested: Project # 04481387-1

MCPS Radon Survey
Cannon Road Elementary School
MD 20904

Log Number	Device Number		Test Expo	sure Duratio	on:	Area Tested	Result pCi/L
2393808	3918226	11/13/2018	4:12 pm	11/16/2018	12:28 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	0.4
2393809	3918041	11/13/2018	4:15 pm	11/16/2018	12:28 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	0.9
2393810	3918228	11/13/2018	4:17 pm	11/16/2018	12:25 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	1.6
2393811	3918201	11/13/2018	4:19 pm	11/16/2018	12:25 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	1.8
2393812	3918212	11/13/2018	4:23 pm	11/16/2018	12:23 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	2.4
2393813	3918224	11/13/2018	4:23 pm	11/16/2018	12:23 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	0.9
2393814	3918231	11/13/2018	4:26 pm	11/16/2018	12:22 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	1.0
2393815	3918232	11/13/2018	4:29 pm	11/16/2018	12:29 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	< 0.4
2393816	3918233	11/13/2018	4:32 pm	11/16/2018	12:29 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	2.1
2393817	3918234	11/13/2018	4:32 pm	11/16/2018	12:29 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	2.9
2393818	3918235	11/13/2018	4:37 pm	11/16/2018	12:29 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	4.3

Comment: A copy of this report was emailed to Intertek-PSI (VA).

Distributed by: Intertek-PSI (VA)

Date Received: 11/19/2018 Date Logged: 11/19/2018 Date Analyzed: 11/19/2018 Date Reported: 12/21/2018

Report Reviewed By: __________

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



EPA Method #402-R-92-004 **Charcoal Canister** NRPP Device Code 6048 NRSB Device Code 10317

Laboratory Report for:

Intertek-PSI (VA) 2930 Eskridge Road

Fairfax VA 22031

MCPS Radon Survey

Cannon Road Elementary School

Property Tested: Project # 04481387-1

MD 20904

Log Number	Device Number		Test Expo	sure Duratio	on:	Area Tested	Result pCi/L
2393819	3918236	11/13/2018	4:38 pm	11/16/2018	12:36 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	0.8
2393820	3918237	11/13/2018	4:39 pm	11/16/2018	12:36 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	< 0.4
2393821	3918238	11/13/2018	4:43 pm	11/16/2018	12:36 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	1.3
2393822	3918239	11/13/2018	4:45 pm	11/16/2018	12:36 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	< 0.4
2393823	3918240	11/13/2018	4:45 pm	11/16/2018	12:37 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	0.6
2393824	3918161	11/13/2018	4:48 pm	11/16/2018	12:37 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	0.5
2393825	3918162	11/13/2018	4:48 pm	11/16/2018	12:38 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	0.5
2393826	3918163	11/13/2018	4:51 pm	11/16/2018	12:39 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	< 0.4
2393827	3918164	11/13/2018	4:53 pm	11/16/2018	12:39 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	1.4
2393828	3918165	11/13/2018	4:56 pm	11/16/2018	12:40 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	0.4
2393829	3918166	11/13/2018	4:57 pm	11/16/2018	12:40 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	0.7

Comment: A copy of this report was emailed to Intertek-PSI (VA).

Distributed by: Intertek-PSI (VA)

Date Received: 11/19/2018 11/19/2018 Date Analyzed: 11/19/2018 Date Reported: 12/21/2018 Date Logged:

Report Reviewed By: __________

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



EPA Method #402-R-92-004 **Charcoal Canister** NRPP Device Code 6048 NRSB Device Code 10317

Property Tested: Project # 04481387-1

Laboratory Report for:

MCPS Radon Survey

Intertek-PSI (VA)	MCPS Radon Survey
2930 Eskridge Road	Cannon Road Elementary School
Fairfax VA 22031	MD 20904

Log Number	Device Number		Test Expo	sure Duratio	on:	Area Tested	Result pCi/L
2393830	3918167	11/13/2018	4:59 pm	11/16/2018	12:41 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	1.2
2393831	3918168	11/13/2018	5:00 pm	11/16/2018	12:44 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	0.6
2393832	3918169	11/13/2018	5:03 pm	11/16/2018	12:45 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	0.5
2393833	3918170	11/13/2018	5:03 pm	11/16/2018	12:45 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	0.4
2393834	3918213	11/13/2018	5:05 pm	11/16/2018	12:48 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	< 0.4
2393835	3918214	11/13/2018	5:11 pm	11/16/2018	12:50 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	1.7
2393836	3918220	11/13/2018	5:12 pm	11/16/2018	12:51 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	0.7
2393837	3918222	11/13/2018	5:19 pm	11/16/2018	12:53 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	0.7
2393838	3918215	11/13/2018	5:19 pm	11/16/2018	12:53 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	0.9
2393839	3918216	11/13/2018	5:21 pm	11/16/2018	12:53 pm	Bldg Cannon Road Elementary School Flr 2 Rm 2	< 0.4
2393840	3918217	11/13/2018	5:22 pm	11/16/2018	12:53 pm	Bldg Cannon Road Elementary School Flr 2 Rm 2	0.5

Comment: A copy of this report was emailed to Intertek-PSI (VA).

Distributed by: Intertek-PSI (VA)

Date Received: 11/19/2018 11/19/2018 Date Analyzed: 11/19/2018 Date Reported: 12/21/2018 Date Logged:

Report Reviewed By: 4ff

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



EPA Method #402-R-92-004 Charcoal Canister NRPP Device Code 6048 NRSB Device Code 10317

Laboratory Report for:

Property Tested: Project # 04481387-1

Intertek-PSI (VA)
2930 Eskridge Road
Fairfax VA 22031

MCPS Radon Survey
Cannon Road Elementary School
MD 20904

Log Number	Device Number		Test Expo	sure Duratio	on:	Area Tested	Result pCi/L
2393841	3918218	11/13/2018	5:23 pm	11/16/2018	12:53 pm	Bldg Cannon Road Elementary School Flr 2 Rm 2	0.6
2393842	3918227	11/13/2018	5:30 pm	11/16/2018	12:53 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	0.4
2393843	3916033	11/13/2018	3:41 pm	11/16/2018	12:53 pm	Bldg Cannon Road Elementary School	< 0.4
2393844	3916035	11/13/2018	3:41 pm	11/16/2018	12:53 pm	Bldg Cannon Road Elementary School	< 0.4
2393845	3918005	11/13/2018	6:00 am	11/16/2018	12:53 pm	Bldg Cannon Road Elementary School	< 0.4
2393846	3918006	11/13/2018	6:00 am	11/16/2018	12:53 pm	Bldg Cannon Road Elementary School	< 0.4
2393847	3918211	11/13/2018	3:41 pm	11/16/2018	12:15 pm	Bldg Cannon Road Elementary School Fir 1 Rm 1	0.5
2393848	3918210	11/13/2018	3:43 pm	11/16/2018	12:18 pm	Bldg Cannon Road Elementary School Fir 1 Rm 1	< 0.4
2393849	3918203	11/13/2018	3:47 pm	11/16/2018	12:18 pm	Bldg Cannon Road Elementary School Fir 1 Rm 1	< 0.4
2393850	3918208	11/13/2018	3:49 pm	11/16/2018	12:16 pm	Bldg Cannon Road Elementary School Fir 1 Rm 1	< 0.4
2393851	3918209	11/13/2018	3:50 pm	11/16/2018	12:16 pm	Bldg Cannon Road Elementary School Flr 1 Rm 1	0.9

Comment: A copy of this report was emailed to Intertek-PSI (VA).

Distributed by: Intertek-PSI (VA)

Date Received: 11/19/2018 Date Logged: 11/19/2018 Date Analyzed: 11/19/2018 Date Reported: 12/21/2018

Report Reviewed By: __________

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

Disclaimer:

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



EPA Method #402-R-92-004 Charcoal Canister NRPP Device Code 6048 NRSB Device Code 10317

Laboratory Report for:

Property Tested: Project # 04481387-1

Intertek-PSI (VA)
2930 Eskridge Road
Fairfax VA 22031

MCPS Radon Survey
Cannon Road Elementary School
MD 20904

Log Number	Device Number		Test Expo	sure Duratio	on:	Area Tested		Result pCi/L
2393852	3918202	11/13/2018	3:51 pm	11/16/2018	12:18 pm	Bldg Cannon Road Elementary School	Flr 1 Rm 1	2.5
2393853	3918205	11/13/2018	3:54 pm	11/16/2018	12:19 pm	Bldg Cannon Road Elementary School	Flr 1 Rm 1	0.9
2393854	3918206	11/13/2018	3:58 pm	11/16/2018	12:20 pm	Bldg Cannon Road Elementary School	Flr 1 Rm 1	0.7
2393855	3918204	11/13/2018	3:59 pm	11/16/2018	12:20 pm	Bldg Cannon Road Elementary School	Flr 1 Rm 1	0.4
2393856	3918207	11/13/2018	3:59 pm	11/16/2018	12:20 pm	Bldg Cannon Road Elementary School	Flr 1 Rm 1	< 0.4
2393857	3918024	11/13/2018	4:06 pm	11/16/2018	12:22 pm	Bldg Cannon Road Elementary School	Flr 1 Rm 1	0.7
2393858	3918221	11/13/2018	4:09 pm	11/16/2018	12:23 pm	Bldg Cannon Road Elementary School	Flr 1 Rm 1	0.4
2393859	3918025	11/13/2018	2:19 pm	11/16/2018	12:25 pm	Bldg Cannon Road Elementary School	Flr 1 Rm 1	2.3
2393860	3918031	11/13/2018	4:11 pm	11/16/2018	12:28 pm	Bldg Cannon Road Elementary School	Flr 1 Rm 1	0.4

Comment: A copy of this report was emailed to Intertek-PSI (VA).

Distributed by: Intertek-PSI (VA)

Date Received: 11/19/2018 Date Logged: 11/19/2018 Date Analyzed: 11/19/2018 Date Reported: 12/21/2018

Report Reviewed By: __________

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



EPA Method #402-R-92-004 Liquid Scintillation NRPP Device Code 8088 NRSB Device Code 12193

Laboratory Report for:

Property Tested: Project # 04481387-1

Intertek-PSI (VA) 2930 Eskridge Road Fairfax VA 22031

MCPS Radon Survey Cannon Road Elementary School Cloverly MD 20905

Log Number	Device Number		Test Expos	sure Duratio	on:	Area Tested	Result pCi/L
2393057	3881191	11/13/2018	5:14 pm	11/16/2018	12:53 pm	Bldg. Cannon Road Elementary School Flr 1 Rm 1	1.1
2393060	3881232	11/13/2018	5:01 pm	11/16/2018	12:51 pm	Bldg. Cannon Road Elementary School Flr 1 Rm 1	1.3
2393061	3881240	11/13/2018	5:07 pm	11/16/2018	12:48 pm	Bldg. Cannon Road Elementary School Fir 1 Rm 1	0.4
2393062	3881242	11/13/2018	5:07 pm	11/16/2018	12:51 pm	Bldg. Cannon Road Elementary School Flr 1 Rm 1	0.4

Comment: A copy of this report was emailed to Intertek-PSI (VA).

Distributed by: Intertek-PSI (VA)

Date Received: 11/18/2018 11/18/2018 Date Analyzed: 11/19/2018 Date Logged: Date Reported: 12/13/2018

Report Reviewed By: __________

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



NRPP 105011 AL NRSB ARL0007 Ohio RL41

EPA Method #402-R-92-004 **Charcoal Canister** NRPP Device Code 6048 NRSB Device Code 10317

Laboratory Report for:

Property Tested:

Intertek-PSI (VA) 2930 Eskridge Road Fairfax VA 22031

MCPS Radon Survey 4514 Taylorsville Road Dayton OH 45424

Log Device Number Number	Test Exposure Duration:	Area Tested	Result pCi/L
3204125 3926831 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	36.1
3204126 3926832 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	34.8
3204127 3926833 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	33.7
3204128 3926834 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	35.8
3204129 3926835 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	35.0
3204130 3926836 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	34.5
3204131 3926837 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	34.6
3204132 3926838 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	34.3
3204133 3926839 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	33.2
3204134 3926840 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	34.0

Comment: A copy of this report was e-mailed to Intertek-PSI (VA)

Test Performed By: Unknown

Distributed by: Intertek-PSI (VA)

Date Received: 12/12/2018 12/12/2018 Date Analyzed: 12/12/2018 Date Reported: 12/13/2018 Date Logged:

Report Reviewed By: _

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT Intertell - P5	I ,	ob Number 187732
NOMINAL Conditions: Radon Conc 39.6	pCi/L Rel. Hum	19.1 % Temp. 70.1
Date Start: 12/7/18 Date Stop: 12/10/18	Date Start:	Date Stop:
Time Start: <u>0947</u> Time Stop: <u>0947</u>	Time Start:	Time Stop:
Device No.'s: (10) Char. Cans-	Device No.'s:	
3926831 Thro 3926840		
GU Loft		
Date Start: Date Stop:	Date Start:	Date Stop:
Time Start: Time Stop:	Time Start:	Time Stop:
Device No.'s:	Device No.'s:	<u>74)</u>
Date Start: Date Stop:	Date Start:	Date Stop:
Time Start: Time Stop:	Time Start:	Time Stop:
Device No.'s:	Device No.'s:	
		
		14

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = $7 \mu R/h$ Elevation = 820 ft



Chain of Custody

Project Name: MCPS Radon Survey 2018

Name of Schools:

1. Highland View ES

2. Kemp Mill ES

3. Sligo Creek ES

4. Highland ES

5. Kennedy HS

6. EB Lee MS

7. Forest Knolls ES

8. Galway ES

9. Wheaton HS

10. Briggs Chaney MS

11. Cannon Rd ES

12. Cloverly ES

13. Springbrook HS

	Date	Initials
Radon Test Kits Deployed	11/13/2018	NL
Radon Test Kits Sampled	11/16/2018	NL
Radon Test Kits Shipped to Lab*	11/16/2018	NL
	11/17/2018;	
Radon Test Kits Received by Lab*	11/18/2018;	NU
	11/20/2018	

^{*}All samples sent to AccuStar Laboratories, 929 Mount Zion Road, Lebanon, PA 17046 and 2 Saber Way, Haverhill, MA 01835

RADON SCREENING SURVEY – FOLLOW-UP CANNON ROAD ELEMENTARY SCHOOL

901 Cannon Road, Silver Spring, Maryland 20904

EXECUTIVE SUMMARY

Date of Test Report:	3/11/16 Follow-Up	
Round of Testing:	Initial	
	Follow-up	
	Post Remediation	
# Rooms Tested	16	
# Rooms ≥ 4.0 pCi/L:	0	
Low Value:	<0.3	
High Value:	2.8	
Confirmed Rooms ≥ 4.0 pCi/L US EPA	0	
Action Level		

Summary of Sampling Events ≥ 4.0 pCi/L

Room	Result (pCi/L)	Result (pCi/L)	Average Result
	3/7/16 (Rev 1 Initial)	3/11/16 Follow-Up	(pCi/L)
102C	<0.3 Tampered	<0.3	<0.3
105	0.7 Tampered	1.2	1.0
107	Missing	<0.3	<0.3
121	0.7 Tampered	<0.3	0.5
124	Missing	Missing	No result
140	1.0 Tampered	2.3	1.7
140A	1.0 Tampered	2.8	1.9
141	0.6 Tampered	1.3	1.0
146	1.0 Tampered	1.0	1.0
154	0.7 Tampered	1.1	0.9
179	2.0 Tampered	2.6	2.3
182	0.6 Tampered	0.6	0.6
232	<0.3 Tampered	<0.3	<0.3
241	0.6 Tampered	0.8	0.7
279	0.6 Tampered	0.6	0.6
112 (D)	1.0 Tampered	0.5	0.8



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

MCPS RADON TESTING

Executive Summary: Cannon Road Elementary School

Date of Test Report:	3/11/2016
Round of Testing:	Initial
	Follow-up
	Post Remediation
# Rooms Tested:	16
# Rooms \geq 4.0 pCi/L:	0
Low Value:	< 0.3
High Value:	2.8

Project Status:

Retesting completed; missing or compromised samples need re-test.

KCI TECHNOLOGIES, INC. WWW.kci.com

ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

March 11, 2016

Mr. Richard Cox Indoor Air Quality Team Leader Montgomery County Public Schools 850 Hungerford Drive Rockville, MD 20850

Re: Radon Testing Services

KCI Job # 12146341.29

Location: Cannon Road Elementary School

901 Cannon Road

Silver Spring, Maryland 20904

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to the Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Cannon Road Elementary School, located at 901 Cannon Road, Silver Spring, Maryland 20904 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS056) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

KCI visited the site on February 22, 2016 and deployed twenty-one (21) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted six (6) test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on February 25, 2016 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc. is a NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936

KCI TECHNOLOGIES, INC. WWW.kci.com

Butler Bridge Road, Mills River, North Carolina.

Evaluation of Testing Conditions:

The operating condition that represents the greatest amount of significantly occupied time for this building is; heating active, with outdoor temperature averages $\leq 65^{\circ}$ F.

KCI concludes that the test period reasonably represents normal conditions when the building is significantly occupied. Clear characterization of the radon hazard is most likely to be observed under this normal operating condition. Based on the evaluation of test conditions, this test should reasonably characterize radon hazards.

KCI also conducted observations of field conditions which could affect the results of the test and compiled weather data for the testing period. Note that strong storms and heavy rainfall were recorded during the test period. The unusual weather conditions may have resulted in atypical radon test results for this facility.

KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

Results:

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	none	n/a
<4.0 piC/L	See Attachment B	

Notes:

D- Duplicate sample

The field blank, office blanks, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L. Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C). Laboratory results and exposure data for the spike samples are also included in Attachment C.

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 316-7800.

KCI TECHNOLOGIES, INC. WWW.kci.com

Sincerely,

James M. Moulsdale

Radon Measurement Specialist

KCI Technologies, Inc.

Attachments: A- Floor Plan with Test Locations

B- Table 1-Radon Test Summary Spreadsheet

C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Chek, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank*

PM- Project Manager

QC- Quality Control

*Office blanks were submitted at a rate of 1% for all samples deployed in Phase 9 testing. Office blanks were not submitted under each school individually.

	Radon Testing Results Cannon Rd Elementary School Test Period: 02/22/16-02/25/16							
Kit Number	Kit Number Room / Area Result							
7731423	105	1.2						
7731401	107	< 0.3						
7731428	112	0.5						
7731424	121	< 0.3						
7731433	140	2.3						
7731420	141	1.3						
7731431	146	1.0						
7731432	154	1.1						
7731427	179	2.6						
7731429	179	2.2						
7731416	182	0.6						
7731408	182	0.6						
7731421	232	< 0.3						
7731422	241	0.8						
7731430	279	< 0.3						
7731402	102C	< 0.3						
7731434 *	124 (Missing)	-						
7731441	140A	2.8						

Table Note:
* Missing or Compromised Sample

	Radon Testing Results				
	Cannon Rd Elementary School				
	Test Period: 02/22/16-02/25/16				
Kit Number	Kit Number QC Type Result				
7731407	D (107)	< 0.3			
7731403	D (279)	0.6			
7731415	FB (102C)	< 0.3			

ATTACHMENT C

Laboratory Analytical Results

Radon test result report for:
CANNON RD ELEMENTARY SCHOOL
MAIN

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
		2002		-	•
7731402	102C	2016-02-22 @ 9:00 am	2016-02-25 @ 8:00 am	< 0.3	2016-02-29
7731415	102C	2016-02-22 @ 9:00 am	2016-02-25 @ 8:00 am	< 0.3	2016-02-29
7731423	105	2016-02-22 @ 9:00 am	2016-02-25 @ 8:00 am	1.2 ± 0.3	2016-02-29
7731401	107	2016-02-22 @ 9:00 am	2016-02-25 @ 8:00 am	< 0.3	2016-02-29
7731407	107	2016-02-22 @ 9:00 am	2016-02-25 @ 8:00 am	< 0.3	2016-02-29
7731428	112	2016-02-22 @ 10:00 am	2016-02-25 @ 8:00 am	0.5 ± 0.3	2016-02-29
7731424	121	2016-02-22 @ 9:00 am	2016-02-25 @ 8:00 am	< 0.3	2016-02-29
7731434	124	@	@		
7731433	140	2016-02-22 @ 9:00 am	2016-02-25 @ 8:00 am	2.3 ± 0.4	2016-02-29
7731441	140A	2016-02-22 @ 9:00 am	2016-02-25 @ 8:00 am	2.8 ± 0.4	2016-02-29
7731420	141	2016-02-22 @ 9:00 am	2016-02-25 @ 8:00 am	1.3 ± 0.3	2016-02-29
7731431	146	2016-02-22 @ 9:00 am	2016-02-25 @ 8:00 am	1.0 ± 0.3	2016-02-29
7731432	154	2016-02-22 @ 9:00 am	2016-02-25 @ 8:00 am	1.1 ± 0.3	2016-02-29
7731427	179	2016-02-22 @ 10:00 am	2016-02-25 @ 8:00 am	2.6 ± 0.4	2016-02-29
7731429	179	2016-02-22 @ 10:00 am	2016-02-25 @ 8:00 am	2.2 ± 0.4	2016-02-29
7731408	182	2016-02-22 @ 9:00 am	2016-02-25 @ 8:00 am	0.6 ± 0.3	2016-02-29
7731416	182	2016-02-22 @ 9:00 am	2016-02-25 @ 8:00 am	0.6 ± 0.3	2016-02-29
7731421	232	2016-02-22 @ 9:00 am	2016-02-25 @ 8:00 am	< 0.3	2016-02-29
7731422	241	2016-02-22 @ 9:00 am	2016-02-25 @ 8:00 am	0.8 ± 0.3	2016-02-29
7731403	279	2016-02-22 @ 10:00 am	2016-02-25 @ 8:00 am	0.6 ± 0.3	2016-02-29
7731430	279	2016-02-22 @ 10:00 am	2016-02-25 @ 8:00 am	< 0.3	2016-02-29

March** LABORATORY ANALYSIS 9, REPORT **

Radon test result report for: MCPS

Phase 9 Office Blanks

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7712568	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29
7712584	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29
7719460	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29
7719481	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29
7719497	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29
7719498	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29

March** LABORATORY ANALYSIS 9, REPORT **

Radon test result report for:

MCPS
Phase 9 Office Blanks

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7731626	0	2016-02-23 @ 2:00 pm	2016-02-26 @ 3:00 pm	< 0.3	2016-03-01
7731633	0	2016-02-23 @ 2:00 pm	2016-02-26 @ 3:00 pm	< 0.3	2016-03-01
7735204	0	2016-02-23 @ 2:00 pm	2016-02-26 @ 3:00 pm	< 0.3	2016-03-01
7733204		2010-02-23 @ 2.00 pm	2010-02-20 @ 3.00 pm	V 0.5	2010-03-0

February LABORATORY ANALYSIS 23, REPORT **

Radon test result report for:
TRANSIT- PHASE 7, 8, 9
NONE

Rit# Room Id Started Started PCi/L Analyzed						
7734946 10 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7734955 11 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734956 12 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734959 13 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734959 14 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734953 15 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734954 16 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734940 17 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734939 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734942 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734939 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734939 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 21 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 25 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 25 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 29 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 31 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734931 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 4 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 20	7734937	1	2016-02-19 @ 3:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734956 12 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734959 13 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734930 14 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734953 15 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734954 16 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734940 17 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734939 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734929 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734929 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734933 22 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 25 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734937 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734931 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734931 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734931 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734931 31 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 201	7734946	10	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734959 13 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734955	11	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734930 14 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am	7734956	12	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734953 15 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am	7734959	13	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734954 16 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734930	14	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734940 17 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734953	15	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734954	16	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734948 19 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734940	17	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734939 2 2016-02-19 @ 3:00 pm 2016-02-22 @ 11:00 am < 0.3	7734949	18	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734942 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734948	19	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734929 21 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734939	2	2016-02-19 @ 3:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734933 22 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734942	20	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734929	21	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734936 24 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734933	22	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734943 25 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734934	23	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734944 26 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734936	24	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734943	25	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734928 28 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734944	26	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734952 29 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734935	27	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734947 3 2016-02-19 @ 3:00 pm 2016-02-22 @ 11:00 am < 0.3	7734928	28	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734931 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734952	29	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734932 31 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734947	3	2016-02-19 @ 3:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7718520 32 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734931	30	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7718523 33 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734932	31	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7718522 34 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7718520	32	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7718521 35 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7718523	33	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734945 4 2016-02-19 @ 3:00 pm 2016-02-22 @ 11:00 am < 0.3	7718522	34	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	
7734960 5 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7718521	35	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734958 6 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734951 7 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734957 8 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23	7734945	4	2016-02-19 @ 3:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734951 7 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734957 8 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23		5	1			2016-02-23
7734957 8 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23	7734958	6	•	2016-02-22 @ 11:00 am		2016-02-23
<u>.</u>	7734951	7	•			2016-02-23
7734938 9 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23			•			
	7734938	9	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23

February LABORATORY ANALYSIS 15, REPORT **

Spike Sample Laboratory Results

Radon test result report for: MCPS

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7718273	101A	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.5 ± 0.6	2016-02-04
7718281	102B	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.4 ± 0.6	2016-02-04
7718282	103C	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.3 ± 0.6	2016-02-04
7718288	104D	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.7 ± 0.6	2016-02-04
7718289	105E	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.6 ± 0.6	2016-02-04
7718291	106F	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.5 ± 0.6	2016-02-04

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Note: Spike samples are test canisters that are deliberately exposed to a controlled high level of radon in a laboratory. They provide a quality control measure in the testing process and do NOT reflect radon levels in the building being tested.

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

s Inc. Job Number 173704
pCi/L Rel. Hum 45.9 % Temp. 79.0
Date Start: Date Stop:
Time Start: Time Stop:
Device No.'s:
Date Start: Date Stop:
Time Start: Time Stop:
Device No.'s:
Date Start: Date Stop:
Time Start: Time Stop:
Device No.'s:
·

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = $7 \mu R/h$ Elevation = 820 ft



Engineers • Planners • Scientists • Construction M anagers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon Phase 9

15. Briggs Chaney MS

Name of Schools:

1	Docking Harca Boad ES	16. Broad Acres ES	31. Rosa Parks MS
1.	Rocking Horse Road ES	10. Blodu Acres ES	31. ROSA PATKS IVIS
2.	Rockwell ES	17. Belmont ES	32. Rosemary Hills ES
3.	Oakland Terrace ES	18. Emory Grove Center	33. Sequoyah ES
4.	Rosemont ES	19. Forest Knolls ES	34. Damascus HS
5.	Beall ES	20. Baker MS	35. Einstein ES
6.	Cresthaven ES	21. MLK MS	36. Forest Oak MS
7.	Quince Orchard HS	22. Richard Montgomery HS	37. Hoover MS
8.	Smith Center	23. Sherwood HS	38. Julius West MS
9.	Ashburton ES	24. Walter Johnson HS	39. John F. Kennedy HS
10	. Bannockburn ES	25. Diamond ES	40. Travilah ES
11	. Bradley Hills ES	26. Newport Mill MS	41. Watkins Mill HS
12	. Cannon Road ES	27. Drew ES	42. Northwood HS
13	. Flora M. Singer ES	28. Monocacy ES	43. Lincoln Center
14	. Clarksburg HS	29. Potomac ES	

30. Rock Terrace School

	Date	Initials
Radon Test Kits Deployed	2/22/16	JM
Radon Test Kits Collected	2/25/16	JM
Radon Test Kits Shipped to Lab*	2/25/16	UM
Radon Test Kits Received by Lab*	2/29/16	JM

^{*}All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759



Engineers • Planners • Scientists • Construction M anagers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon Phase 9

Name of Schools:

- 1. Banneker MS
- 2. Bethesda-Chevy Chase HS
- 3. Burtonsville ES
- 4. Chevy Chase ES
- 5. Clopper Mill ES
- 6. Edison HS
- 7. Flower Hill ES
- 8. Flower Valley ES
- 9. Greencastle ES

- 10. Maryvale ES
- 11. Montgomery Blair HS
- 12. Poolesville HS
- 13. Rachel Carson ES
- 14. Stedwick ES
- 15. Watkins Mill ES
- 16. Laytonsville ES
- 17. Lincoln Center

	Date	Initials
Radon Test Kits Deployed	2/23/16	(/M
Radon Test Kits Collected	2/26/16	JM
Radon Test Kits Shipped to Lab*	2/26/16	JM
Radon Test Kits Received by Lab*	3/01/16	JM

^{*}All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759

February LABORATORY ANALYSIS 15, REPORT **

Spike Sample Laboratory Results

Radon test result report for: MCPS

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7718273	101A	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.5 ± 0.6	2016-02-04
7718281	102B	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.4 ± 0.6	2016-02-04
7718282	103C	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.3 ± 0.6	2016-02-04
7718288	104D	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.7 ± 0.6	2016-02-04
7718289	105E	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.6 ± 0.6	2016-02-04
7718291	106F	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.5 ± 0.6	2016-02-04

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Note: Spike samples are test canisters that are deliberately exposed to a controlled high level of radon in a laboratory. They provide a quality control measure in the testing process and do NOT reflect radon levels in the building being tested.

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI Technologia	5 Inc. Job Number 173704
	pCi/L Rel. Hum 45.9 % Temp. 79.0
Date Start: 1/30/16 Date Stop: 2/1/16	Date Start: Date Stop:
Time Start: 9986 Time Stop: 986	Time Start: Time Stop:
Device No.'s: (6) Char. Bags-	Device No.'s:
7718281, 7718282, 7718291,	
7718288, 7718289, 7718273	
E3 Left	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
·	<u> </u>
	· · · · · · · · · · · · · · · · · · ·
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
	·
1,	,

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = $7 \mu R/h$ Elevation = 820 ft



Engineers • Planners • Scientists • Construction M anagers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon Phase 9

15. Briggs Chaney MS

Name of Schools:

1.	Rocking Horse Road ES	16.	Broad Acres ES	31.	Rosa Parks MS
2.	Rockwell ES	17.	Belmont ES	32.	Rosemary Hills ES
3.	Oakland Terrace ES	18.	Emory Grove Center	33.	Sequoyah ES
4.	Rosemont ES	19.	Forest Knolls ES	34.	Damascus HS
5.	Beall ES	20.	Baker MS	35.	Einstein ES
6.	Cresthaven ES	21.	MLK MS	36.	Forest Oak MS
7.	Quince Orchard HS	22.	Richard Montgomery HS	37.	Hoover MS
8.	Smith Center	23.	Sherwood HS	38.	Julius West MS
9.	Ashburton ES	24.	Walter Johnson HS	39.	John F. Kennedy HS
10.	Bannockburn ES	25.	Diamond ES	40.	Travilah ES
11.	Bradley Hills ES	26.	Newport Mill MS	41.	Watkins Mill HS
12.	Cannon Road ES	27.	Drew ES	42.	Northwood HS
13.	Flora M. Singer ES	28.	Monocacy ES	43.	Lincoln Center
14.	Clarksburg HS	29.	Potomac ES		

30. Rock Terrace School

	Date	Initials
Radon Test Kits Deployed	2/22/16	JM
Radon Test Kits Collected	2/25/16	JM
Radon Test Kits Shipped to Lab*	2/25/16	M
Radon Test Kits Received by Lab*	2/29/16	JM

^{*}All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759



Engineers • Planners • Scientists • Construction Managers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon Phase 9

Name of Schools:

- 1. Banneker MS
- 2. Bethesda-Chevy Chase HS
- 3. Burtonsville ES
- 4. Chevy Chase ES
- 5. Clopper Mill ES
- 6. Edison HS
- 7. Flower Hill ES
- 8. Flower Valley ES
- 9. Greencastle ES

- 10. Maryvale ES
- 11. Montgomery Blair HS
- 12. Poolesville HS
- 13. Rachel Carson ES
- 14. Stedwick ES
- 15. Watkins Mill ES
- 16. Laytonsville ES
- 17. Lincoln Center

	52.0	
	Date	Initials
Radon Test Kits Deployed	2/23/16	\/M
Radon Test Kits Collected	2/26/16	JM
Radon Test Kits Shipped to Lab*	2/26/16	JM
Radon Test Kits Received by Lab*	3/01/16	JM

^{*}All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

MCPS RADON TESTING

Executive Summary: Cannon Road Elementary School

Date of Test Report:	3/7/2016 (Rev 1)
Round of Testing:	Initial
	Follow-up
	Post Remediation
# Rooms Tested:	45
# Rooms \geq 4.0 pCi/L:	0
Low Value:	< 0.3
High Value:	2.3

Project Status:

Initial testing completed; missing or compromised samples need re-test

KCI TECHNOLOGIES, INC. WWW.kci.com

ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

March 7, 2016 (Rev 1)

Mr. Richard Cox Indoor Air Quality Team Leader Montgomery County Public Schools 850 Hungerford Drive Rockville, MD 20850

Re: Radon Testing Services

KCI Job # 12146341.20

Location: Cannon Road Elementary School

901 Cannon Road

Silver Spring, MD 20904

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to the Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Cannon Road Elementary School, located at 901 Cannon Road in Silver Spring, Maryland 20904 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS056) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

KCI visited the site on December 21, 2015 and deployed fifty-eight (58) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. Prior to sampling, KCI returned 1% of the test batch to the laboratory for analysis as lab transit blanks. In addition, KCI submitted six (6) test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on December 24, 2015 to retrieve the radon sampling test kits. KCI shipped all

radon tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc. is a NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

Evaluation of Testing Conditions:

The operating condition that represents the greatest amount of significantly occupied time for this building is; heating active, with outdoor temperature averages $\leq 65^{\circ}$ F.

KCI concludes that the test period reasonably represents normal conditions when the building is significantly occupied. Clear characterization of the radon hazard is most likely to be observed under this normal operating condition. Based on the evaluation of test conditions, this test should reasonably characterize radon hazards.

KCI also conducted observations of field conditions which could affect the results of the test and compiled weather data for the testing period. KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

Results:

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result	
≥4.0 piC/L	None	n/a	
<4.0 piC/L	See Attachment B		

Notes:

D- Duplicate sample

All field blanks, office blank, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L. Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C). Laboratory results and exposure data for the spike samples are also included in Attachment C.

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 316-7800.

KCI Technologies, Inc. WWW.kci.com

Employee-Owned Since 1988

Sincerely,

James M. Moulsdale

Radon Measurement Specialist

KCI Technologies, Inc.

Attachments: A- Floor Plan with Test Locations

B- Table 1-Radon Test Summary Spreadsheet

C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Chek, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

QC- Quality Control

Radon Testing Results								
Cannon Road ES								
Test Period: 12/21/15-12/24/15								
Kit Number Room / Area Result								
7713958	100	0.6						
7713927	102	< 0.3						
7713921	111	0.6						
7713972	112	0.6						
7713956	115	1.1						
7713974	116	< 0.3						
7713955	117	0.7						
7713967	120	< 0.3						
7713969	126	0.6						
7713922	130	0.8						
7713957	140	1.6						
7713933	145	1.7						
7713936	150	0.7						
7713934	151	0.7						
7713968	156	< 0.3						
7713971	157	0.8						
7713961	158	< 0.3						
7713944	162	< 0.3						
7713945	166	< 0.3						
7713943	170	0.8						
7713946	179	2.3						
7713970	180	< 0.3						
7713903	182	0.6						
7713954	205	< 0.3						
7713902	211	< 0.3						
7713965	242	< 0.3						
7713926	100A	< 0.3						
7713929	100B	0.6						
7713925	100C	0.9						
7713928	102B	< 0.3						
7713962	* 102C (tampered)	< 0.3						
7713932	* 105 (tampered)	0.7						
7713920	* 107 (missing)	-						
7713919	* 121 (tampered)	0.7						
7713966	* 124 (missing)	-						
7713931	* 140 (tampered)	1.0						
7713937	* 140A (tampered)	1.0						
7713930	* 141 (tampered)	0.6						
7713935	* 146 (tampered)	1.0						
7713940	* 154 (tampered)	0.7						
7713938	* 179 (tampered)	2.0						
7713942	179B	1.8						
7713939	179B.1	1.3						
7713951	* 182 (tampered)	0.6						
7713822	182A	0.8						
7713963	* 232 (tampered)	< 0.3						

Table Note:
* Missing or Compromised Sample

	Radon Testing Results						
		Cannon Road ES					
	Tes	st Period: 12/21/15-12/24/15					
Kit Number	Kit Number Room / Area Result						
7713964	*	241 (tampered)	0.6				
7713950	*	279 (tampered)	0.6				

Radon Testing Results Cannon Road ES Test Period: 12/21/15-12/24/15						
	16311 61104. 12/21/10-12/24/10					
Kit Number	QC Type	Result				
7713923	D (100C)	< 0.3				
7713918	* D (112:tampered)	1.0				
7713941	D (146)	1.3				
7713947	D (179)	2.0				
7713949	D (279)	< 0.3				
7713924	FB (100C)	< 0.3				
7713952	FB (154)	< 0.3				
7713948	FB (179)	< 0.3				
7713953	FB (279)	< 0.3				
7713901	OB (0)	< 0.3				

ATTACHMENT C

Laboratory Analytical Results

Radon test result report for: CANNON ROAD ES MAIN

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7713901	0	2015-12-21 @ 3:00 pm	2015-12-24 @ 10:00 am	< 0.3	2015-12-29
7713958	100	2015-12-21 @ 12:00 pm	2015-12-24 @ 8:00 am	0.6 ± 0.3	2015-12-29
7713926	100A	2015-12-21 @ 12:00 pm	2015-12-24 @ 8:00 am	< 0.3	2015-12-29
7713929	100B	2015-12-21 @ 12:00 pm	2015-12-24 @ 8:00 am	0.6 ± 0.3	2015-12-29
7713923	100C	2015-12-21 @ 12:00 pm	2015-12-24 @ 8:00 am	< 0.3	2015-12-29
7713924	100C	2015-12-21 @ 12:00 pm	2015-12-24 @ 8:00 am	< 0.3	2015-12-29
7713925	100C	2015-12-21 @ 12:00 pm	2015-12-24 @ 8:00 am	0.9 ± 0.3	2015-12-29
7713927	102	2015-12-21 @ 12:00 pm	2015-12-24 @ 8:00 am	< 0.3	2015-12-28
7713928	102B	2015-12-21 @ 12:00 pm	2015-12-24 @ 8:00 am	< 0.3	2015-12-28
7713962	102C	2015-12-21 @ 12:00 pm	2015-12-24 @ 8:00 am	< 0.3	2015-12-29
7713932	105	2015-12-21 @ 12:00 pm	2015-12-24 @ 9:00 am	0.7 ± 0.3	2015-12-29
7713920	107	@	@		
7713921	111	2015-12-21 @ 12:00 pm	2015-12-24 @ 8:00 am	0.6 ± 0.3	2015-12-28
7713918	112	2015-12-21 @ 12:00 pm	2015-12-24 @ 8:00 am	1.0 ± 0.3	2015-12-28
7713972	112	2015-12-21 @ 12:00 pm	2015-12-24 @ 8:00 am	0.6 ± 0.3	2015-12-28
7713956	115	2015-12-21 @ 12:00 pm	2015-12-24 @ 8:00 am	1.1 ± 0.3	2015-12-28
7713974	116	2015-12-21 @ 12:00 pm	2015-12-24 @ 8:00 am	< 0.3	2015-12-28
7713955	117	2015-12-21 @ 12:00 pm	2015-12-24 @ 8:00 am	0.7 ± 0.3	2015-12-28
7713967	120	2015-12-21 @ 12:00 pm	2015-12-24 @ 8:00 am	< 0.3	2015-12-28
7713919	121	2015-12-21 @ 12:00 pm	2015-12-24 @ 8:00 am	0.7 ± 0.3	2015-12-29
7713966	124	@	@		
7713969	126	2015-12-21 @ 12:00 pm	2015-12-24 @ 8:00 am	0.6 ± 0.4	2015-12-29
7713922	130	2015-12-21 @ 12:00 pm	2015-12-24 @ 8:00 am	0.8 ± 0.3	2015-12-28
7713957	140	2015-12-21 @ 12:00 pm	2015-12-24 @ 9:00 am	1.6 ± 0.4	2015-12-29
7713931	140	2015-12-21 @ 12:00 pm	2015-12-24 @ 9:00 am	1.0 ± 0.4	2015-12-29
7713937	140A	2015-12-21 @ 12:00 pm	2015-12-24 @ 9:00 am	1.0 ± 0.4	2015-12-29
7713930	141	2015-12-21 @ 12:00 pm	2015-12-24 @ 8:00 am	0.6 ± 0.3	2015-12-29
7713933	145	2015-12-21 @ 12:00 pm	2015-12-24 @ 9:00 am	1.7 ± 0.4	2015-12-29
7713935	146	2015-12-21 @ 12:00 pm	2015-12-24 @ 9:00 am	1.0 ± 0.3	2015-12-28
7713941	146	2015-12-21 @ 12:00 pm	2015-12-24 @ 9:00 am	1.3 ± 0.4	2015-12-29
7713936	150	2015-12-21 @ 12:00 pm	2015-12-24 @ 9:00 am	0.7 ± 0.3	2015-12-29
7713934	151	2015-12-21 @ 12:00 pm	2015-12-24 @ 9:00 am	0.7 ± 0.3	2015-12-29
7713952	154	2015-12-21 @ 12:00 pm	2015-12-24 @ 9:00 am	< 0.3	2015-12-29
7713940	154	2015-12-21 @ 12:00 pm	2015-12-24 @ 9:00 am	0.7 ± 0.3	2015-12-29
7713968	156	2015-12-21 @ 12:00 pm	2015-12-24 @ 9:00 am	< 0.3	2015-12-29
7713971	157	2015-12-21 @ 1:00 pm	2015-12-24 @ 9:00 am	0.8 ± 0.3	2015-12-29
7713961	158	2015-12-21 @ 12:00 pm	2015-12-24 @ 9:00 am	< 0.3	2015-12-29

January LABORATORY ANALYSIS 12, REPORT **

Radon test result report for: CANNON ROAD ES MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7713944	162	2015-12-21 @ 12:00 pm	2015-12-24 @ 9:00 am	< 0.3	2015-12-29
7713945	166	2015-12-21 @ 1:00 pm	2015-12-24 @ 9:00 am	< 0.3	2015-12-29
7713943	170	2015-12-21 @ 1:00 pm	2015-12-24 @ 9:00 am	0.8 ± 0.3	2015-12-28
7713938	179	2015-12-21 @ 1:00 pm	2015-12-24 @ 9:00 am	2.0 ± 0.3	2015-12-28
7713947	179	2015-12-21 @ 1:00 pm	2015-12-24 @ 9:00 am	2.0 ± 0.3	2015-12-28
7713948	179	2015-12-21 @ 1:00 pm	2015-12-24 @ 9:00 am	< 0.3	2015-12-29
7713946	179	2015-12-21 @ 1:00 pm	2015-12-24 @ 9:00 am	2.3 ± 0.4	2015-12-29
7713942	179B	2015-12-21 @ 1:00 pm	2015-12-24 @ 9:00 am	1.8 ± 0.4	2015-12-29
7713939	179B.1	2015-12-21 @ 1:00 pm	2015-12-24 @ 9:00 am	1.3 ± 0.3	2015-12-28
7713970	180	2015-12-21 @ 1:00 pm	2015-12-24 @ 9:00 am	< 0.3	2015-12-28
7713951	182	2015-12-21 @ 1:00 pm	2015-12-24 @ 9:00 am	0.6 ± 0.3	2015-12-28
7713903	182	2015-12-21 @ 1:00 pm	2015-12-24 @ 9:00 am	0.6 ± 0.3	2015-12-29
7713822	182A	2015-12-21 @ 1:00 pm	2015-12-24 @ 9:00 am	0.8 ± 0.3	2015-12-28
7713954	205	2015-12-21 @ 1:00 pm	2015-12-24 @ 9:00 am	< 0.3	2015-12-29
7713902	211	2015-12-21 @ 1:00 pm	2015-12-24 @ 9:00 am	< 0.3	2015-12-29
7713963	232	2015-12-21 @ 1:00 pm	2015-12-24 @ 9:00 am	< 0.3	2015-12-28
7713964	241	2015-12-21 @ 1:00 pm	2015-12-24 @ 9:00 am	0.6 ± 0.3	2015-12-29
7713965	242	2015-12-21 @ 1:00 pm	2015-12-24 @ 9:00 am	< 0.3	2015-12-29
7713949	279	2015-12-21 @ 1:00 pm	2015-12-24 @ 9:00 am	< 0.3	2015-12-29
7713950	279	2015-12-21 @ 1:00 pm	2015-12-24 @ 9:00 am	0.6 ± 0.3	2015-12-29
7713953	279	2015-12-21 @ 1:00 pm	2015-12-24 @ 9:00 am	< 0.3	2015-12-29

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

December LABORATORY ANALYSIS 29, REPORT **

Radon test result report for:
TRANSIT DEC 14 2015
NONE

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
		2002000		-	•
7704395	TRANSIT 1	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706508	TRANSIT 10	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706510	TRANSIT 11	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706511	TRANSIT 12	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706505	TRANSIT 13	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704371	TRANSIT 14	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706506	TRANSIT 15	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704381	TRANSIT 16	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704399	TRANSIT 17	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704390	TRANSIT 18	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704396	TRANSIT 2	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704364	TRANSIT 3	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704370	TRANSIT 4	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704368	TRANSIT 5	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706524	TRANSIT 6	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706526	TRANSIT 7	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706518	TRANSIT 8	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706516	TRANSIT 9	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

December LABORATORY ANALYSIS 23, REPORT **

Spike Sample Laboratory Results

Radon test result report for: MCPS

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7706380	101	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	25.2	2015-12-23
7706381	102	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	26.5	2015-12-23
7706208	103	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	27.7	2015-12-23
7705132	104	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	28.6	2015-12-23
7706366	105	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	26.5	2015-12-23
7706211	106	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	26.1	2015-12-23

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Note: Spike samples are test canisters that are deliberately exposed to a controlled high level of radon in a laboratory. They provide a quality control measure in the testing process and do NOT reflect radon levels in the building being tested.

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI Technologies.	Inc. Job Number 173224
	pCi/L Rel. Hum <u>49.6</u> % Temp. <u>69.9</u>
Date Start: 12/18/15 Date Stop: 12/21/5	Date Start: Date Stop:
Time Start: <u>0929</u> Time Stop: <u>0929</u>	Time Start: Time Stop:
Device No.'s: 7705132,7766208	Device No.'s:
7706211,7706366,	
7706380, 7706381	
F3 Left	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
	-
1	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = $7 \mu R/h$ Elevation = 820 ft



Engineers • Planners • Scientists • Construction Managers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Chain of Custody

Project Name: MCPS Radon Phase II

School Names:

1.	Bannonckburn ES	11. Sherwood HS	21.	Fairland ES
2.	Walt Whitman HS	12. Hadley Farms	22.	Cannon Road ES
3.	Walter Johnson HS	13. S. Christa McAuliffe ES	23.	Richard Montgomery HS
4.	North Chevy Chase ES	14. Ronald A. McNair ES	24.	Brooke Grove ES
5.	Piney Branch ES	15. MLK MS	25.	Belmont ES
6.	Forest Knolls ES	16. Ashburton ES	26.	Emory Grove
7.	Newport Mill MS	17. Bradley Hills ES	27.	Clarksburg HS
8.	Broad Acres ES	18. Flora M. Singer ES	28.	Clarksburg ES
9.	Briggs Chaney MS	19. Woodlin ES	29.	John T. Baker MS
10.	Blair G. Ewing Center	20. Montgomery Knolls ES		

	Date	Initials
Radon Test Kits Deployed	12/21/2015	JM
Radon Test Kits Collected	12/24/2015	IM
Radon Test Kits Shipped to Lab*	12/24/2015	IM
Radon Test Kits Received by Lab*	12/28/2015	UM

^{*}All samples sent to Air Check, Inc., 1936 Butler Bridge Road, Mills River, NC 28758

M. A. CECIL & ASSOCIATES, INC.

4475 Shannon Way, Port Republic, Maryland 20676 (301) 855-7710 INDUSTRIAL HYGIENE AND ENVIRONMENTAL HEALTH

August 8, 2012

Mr. Sean Yarup Montgomery County Public Schools 16651 Crabbs Branch Way Rockville, Maryland 20855

Re: Radon Evaluation- Cannon Road Elementary School

Dear Mr. Yarup:

Environmental radon testing has been completed at Cannon Road Elementary School.

Twenty two charcoal canisters were placed in various rooms throughout the school. The canisters were placed on July 20, 2012 and retrieved on July 23, 2012.

The detected radon concentrations were below the EPA recommended level of 4.0 pico curies per liter (pCi/l) of air with the exception of the MPR which had a concentration of 28.3 pCi/l. Remedial action to reduce the radon concentration is not recommended at this time. This room should be retested within two to three months. The test locations and results are summarized in the attached table.

Should you have any questions concerning this report please do not hesitate to contact us.

Sincerely,

Michael A. Cecil, CIH

Cannon Road Elementary School Environmental Radon Results July 20-23, 2012

Location	Detected Radon
	Concentration (pCi/l)
MPR	28.3
Room 145	0.8
Room 121	< 0.5
Gym	< 0.5
Room 151	0.9
Room 170	0.6
IMC	1.4
Room 124	1.5
Room 117	1.3
Staff Lounge	1.3
Room 115	1.6
Room 107	3.2
Room 111	0.9
Computer Lab	1.3
Room 116	1.3
Room 166	1.2
Room 126	1.1
Main Office	0.9
Room 162	1.8
Room 130	1.2
Room 120	0.8
Room 158	1.9