936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

MCPS RADON TESTING – EXECUTIVE SUMMARY

Site Name	Poolesville High
	School
Date of Test Report	3/2/2023
Round of Testing	Initia
	Follow-up
	Post Remediation
	2 Year Testing
	5 Year Testing
	HVAC Upgrade
	Window Replacement
	New Addition
	New Facility
# Rooms Tested	101
# Rooms Re-tested	5
# Rooms ≥ 4.0 pCi/L	0
Lowest Value	<0.3 pCi/L
Highest Value	1.9 pCi/L

Project Status:

- 1. Initial testing completed;
- 2. Missing or compromised samples need re-test.
 - 3. Retesting Completed 2/14/23 2/17/23.
 - 4. 5-Year Testing Completed.

KCI Technologies, Inc. WWW.kci.com



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

March 3, 2023

Mr. Brian Croyle Environmental Specialist Montgomery County Public Schools Gaithersburg, MD 20879

Re: Radon Testing Services

KCI Job # 122210551

Location: Poolesville High School

17501 West Willard Road Poolesville, MD 20837

Dear Mr. Croyle:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Poolesville High School, located at 17501 West Willard Road, Poolesville, MD 20837 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Proficiency Program (NRPP) Radon Measurement Specialist (certification #111004 RT) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from https://www.montgomeryschoolsmd.org or www.epa.gov/radon.

KCI visited the site initially on January 23, 2023 and deployed one hundred sixteen (116) activated charcoal (AC) radon test kits. KCI deployed radon test kits in all frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance.

KCI returned to the site on January 26, 2023 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Accustar Labs - MA. for analysis by gamma-ray spectroscopy. Accustar Labs - MA is a NRSB certified analytical laboratory for radon analysis (certification #ARL0017) located at 2 Saber Way, Ward Hill, MA 01835.

KCI re-visited the site on February 14, 2023 to deploy seven (7) activated charcoal (AC) radon test kits for testing of missed rooms or compromised test kits during initial testing.

www.kci.com

KCI returned to the site on February 17, 2023 to retrieve the radon re-sampling test kits. KCI shipped all radon tests via overnight delivery to Accustar Labs – MA for analysis by gamma-ray spectroscopy. Accustar Labs – MA is a NRSB certified analytical laboratory for radon analysis (certification #ARL0017) located at 2 Saber Way, Ward Hill, MA 01835.

A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI also included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

Evaluation of Testing Conditions:

These tests represent:

• Follow up to initial testing.

These tests were conducted to:

• Evaluate radon concentration levels at the facility.

According to AARST, Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room during the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate temperatures ranged from the 31°F to 52°F. Maximum sustained winds ranged from 5-25 miles per hour. Average humidity was around 60% with .32 inches of precipitation (rain) was recorded during testing period.

During the re-testing period, weather records indicate low temperatures were in the mid-20s°F and high temperatures ranged to the 70s°F. Maximum sustained winds ranged from 0-33 miles per hour. Average humidity was around 62% with 1.01 inches of precipitation (rain) was recorded during testing period.

KCI Technologies, Inc. WWW.kci.com

Employee-Owned Since 1988

Results:

The sampling locations and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). Sampling locations and associated test kit identification numbers and relevant field observations are listed on Table 3 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	None	N/A
<4.0 piC/L	See Attachment B	

The results of the radon re-testing analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	None	N/A
<4.0 piC/L	See Attachment B	

Quality Control Samples		
Results of Blank Canisters:	The office blanks, and lab transit blanks had test results of	
less than the laboratory detection limit of 0.3 pCi/L.		
Adequate Laboratory Precision?	Review of the duplicate sample analysis indicates that	
adequate laboratory measurement precision was achieved.		
Spike Sample Analysis:	The Spike Sample analysis results indicate the laboratory is	
operating within statistical control limits.		

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 891-1769.

Sincerely,

Tyler P. McCleaf

Radon Measurement Provider

#111004 RT

KCI Technologies, Inc.

Tyler McCleaf

Attachments: A- Floor Plan with Test Locations

B- Table 1-3, Radon Test Summary Spreadsheets

C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Check, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

OC- Quality Control

Table 1- Radon Testing Results	
Poolesvilles HS	

Test Period: 01/24/2023 - 01/27/2023

Kit Number	Room / Area	Result
11634274	12	0.5
11634128	13	< 0.3
11634275	14	0.6
11634132	15	< 0.3
11634131	16	0.5
11634138	17	< 0.3
11634135	18	< 0.3
11634136	18	0.7
11634276	19	< 0.3
11634277	20	< 0.3
11634279	22	< 0.3
11634246	23	< 0.3
11634253	23	< 0.3
11634273	24	< 0.3
11634266	25	< 0.3
11634272	26	< 0.3
11634270	28	< 0.3
11634267	29	< 0.3
11634263	30	< 0.3
11634255	31	< 0.3
11634256	31	< 0.3
11634257	31	< 0.3
11634262	32	< 0.3
11634254	33	< 0.3
11634245	34	< 0.3
11634137	35	< 0.3
11634154	39	< 0.3
11634157	39	< 0.3
11634127	41	0.5
11634105	44	< 0.3
11634102	45	< 0.3
11634103	46	0.8
11634104	47	0.5
11634108	49	< 0.3
11634124	51	< 0.3
11634110	52	< 0.3
11634111	53	< 0.3
11634112	53	< 0.3
11634113	53	< 0.3
11634289	54	< 0.3
11634133	55	0.6
11634299	59	< 0.3

Table 1- Radon Testing Results	
Poolesvilles HS	

Test Period: 01/24/2023 - 01/27/2023

Kit Number	Room / Area	Result
11634294	60	< 0.3
11634291	61	< 0.3
11634298	61	< 0.3
11634293	63	< 0.3
11634300	64	0.6
11634149	184	< 0.3
11634141	189	< 0.3
11634143	189	< 0.3
11634144	189	< 0.3
11634153	195	< 0.3
11634151	199	< 0.3
11634148	285	< 0.3
11634140	17A	< 0.3
11634142	17B	< 0.3
11634150	184A	< 0.3
11634152	189A	< 0.3
11634278	22A	< 0.3
11634268	26 OFFICE	< 0.3
11634271	26 OFFICE	< 0.3
11634269	28A	< 0.3
11634259	32 OFFICE	< 0.3
11634260	33 OFFICE	< 0.3
11634258	33A	< 0.3
11634265	33B	< 0.3
11634146	39A	0.6
11634145	39B	0.5
11634147	39C	< 0.3
11634155	39D	0.8
11634156	39E	< 0.3
11634121	41 BREAK ROOM	< 0.3
11634117	41 BUS. ADMIN	< 0.3
11634118	41 CONF.	< 0.3
11634126	41 FINANCE	< 0.3
11634120	42A	< 0.3
11634123	42A	< 0.3
11634115	42A BOOTH	0.6
11634116	42A RECORDING STUIDO	< 0.3
11634101	45A	< 0.3
11634106	45B	0.6
11634109	45B	< 0.3
11634107	49A	< 0.3
11634286	54 OFFICE	< 0.3

Table 1- Radon Testing Results			
Poolesvilles HS			
Tes	Test Period: 01/24/2023 - 01/27/2023		
Kit Number	Room / Area	Result	
11634130	58A	0.6	
11634129	58B	< 0.3	
11634134	58C	< 0.3	
11634295	60 OFFICE	< 0.3	
11634248	ADMIN SECRETARY	< 0.3	
11634251	ASST SCHOOL ADMIN	1.9	
11634252	ASST. PRINCIPAL	< 0.3	
11634290	AUDITORIUM	< 0.3	
11634292	AUDITORIUM	< 0.3	
11634244	CAFETERIA	< 0.3	
11634247	CAFETERIA	< 0.3	
11634287	DRAMA OFFICE	< 0.3	
11634280	GIRLS AUX LOCKER ROOM	0.6	
11634281	GIRLS AUX LOCKER ROOM	0.5	
11634282	GIRLS AUX LOCKER ROOM	< 0.3	
11634284	GIRLS LOCKER OFFICE	0.7	
11634283	GIRLS LOCKER ROOM	< 0.3	
11634261	GYM CONDITIONING OFFICE	0.8	
11634264	GYM OFFICE	< 0.3	
11634296	HEALTH OFFICE	< 0.3	
11634243	KITCHEN OFFICE	< 0.3	
11634242	MAIN OFFICE	< 0.3	
11634119	MEDIA	< 0.3	
11634122	MEDIA	0.5	
11634125	MEDIA OFFICE	< 0.3	
11634114	MEDIA WORKROOM	< 0.3	
11634285	NEW GYM	< 0.3	
11634297	NEW GYM	< 0.3	
11634249	PRINCIPAL	< 0.3	
11634139	SECURITY	< 0.3	
11634250	SECURITY	< 0.3	
11634288	STAGE	< 0.3	

Table 2- Radon Testing Results			
	Poolesville HS		
	Test Period:	01/24/23 - 01/27/23	
Kit Number	QC Type	Room / Area	Result
11634135	D	18	< 0.3
11634253	D	23	< 0.3
11634255	D	31	< 0.3
11634256	FB	31	< 0.3
11634154	D	39	< 0.3
11634112	FB	53	< 0.3
11634113	D	53	< 0.3
11634143	D	189	< 0.3
11634144	FB	189	< 0.3
11634271	D	26 office	< 0.3
11634120	D	42a	< 0.3
11634123	FB	42a	< 0.3
11634106	D	45b	0.6
11634280	D	Girls aux locker room	0.6
11634282	FB	Girls aux locker room	< 0.3
11633975	ОВ	OFFICE BLANK	< 0.3
11633983	ТВ	TRAVEL BLANK	< 0.3

Summary of Missed Locations			
Poolesville HS			
	Test Period: 01/24/23 - 01/27/23		
Kit Number	Room/Area	Result	
N/A	57	N/A	
N/A	40	N/A	
N/A	Boys Locker Room	N/A	
N/A	17	N/A	
N/A	21	N/A	
N/A	1	Under Construction	
N/A	2	Under Construction	
N/A	3	Under Construction	
N/A	4	Under Construction	
N/A	5	Under Construction	
N/A	6	Under Construction	
N/A	7	Under Construction	
N/A	8	Under Construction	
N/A	9	Under Construction	
N/A	10	Under Construction	
N/A	11	Under Construction	
N/A	Cousnelor Suite	Under Construction	
N/A	Main Office	Under Construction	
	<u> </u>		

Summary of Missing, Compromised and >/= 4 piC/L Tests		
Poolesville HS		
	Test Period: 01/24/23 - 01/27/23	
Kit Number	Room/Area	Result
	N/A	

Table Note:

^{*} Missing or Compromised Sample

Table 1- Radon Testing Results				
	Poolesville HS RT			
Tes	t Period: 02/14/2023 - 02/17/2023	3		
Kit Number	Room / Area	Result		
11634068 17 < 0.3				
11634064 21 < 0.3				
11634069 40 0.7				
11633978 57 < 0.				
11634019 57 < 0.3				
11634063 57 0.6				
11634050	BOYS LR	1.2		

Table 2- Radon Testing Results						
	Poolesville HS RT					
	Test Period: (02/14/23 - 02/17/23				
Kit Number QC Type Room / Area Result						
11634019 D 57 <						
11633978 FB 57 < 0.3						
11634060 OB OFFICE BLANK < 0.3						
11634067						

Summary of Missed Locations					
Poolesville HS RT					
Test Period: 02/14/23 - 02/17/23					
Kit Number	Result				
	N/A				

Summary of Missing, Compromised and >/= 4 piC/L Tests					
Poolesville HS RT					
Test Period: 02/14/23 - 02/17/23					
Kit Number	Room/Area	Result			
	N/A				

Table Note:

^{*} Missing or Compromised Sample

ATTACHMENT C

Laboratory Analytical Results

Radon test result report for: POOLESVILLE HS MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11634274	12	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	0.5 ± 0.3	2023-01-31
11634128	13	2023-01-24 @ 3:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634275	14	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	0.6 ± 0.3	2023-01-31
11634132	15	2023-01-24 @ 3:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634131	16	2023-01-24 @ 3:00 pm	2023-01-27 @ 12:00 pm	0.5 ± 0.3	2023-01-31
11634138	17	2023-01-24 @ 3:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634140	17A	2023-01-24 @ 2:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634142	17B	2023-01-24 @ 2:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634136	18	2023-01-24 @ 3:00 pm	2023-01-27 @ 12:00 pm	0.7 ± 0.3	2023-01-31
11634135	18	2023-01-24 @ 3:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634276	19	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634277	20	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634279	22	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634278	22A	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634246	23	2023-01-24 @ 10:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634253	23	2023-01-24 @ 10:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634273	24	2023-01-24 @ 11:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634266	25	2023-01-24 @ 10:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634272	26	2023-01-24 @ 11:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634271	26 OFFICE	2023-01-24 @ 11:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634268	26 OFFICE	2023-01-24 @ 11:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634270	28	2023-01-24 @ 11:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634269	28A	2023-01-24 @ 11:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634267	29	2023-01-24 @ 11:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634263	30	2023-01-24 @ 11:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634257	31	2023-01-24 @ 11:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634255	31	2023-01-24 @ 11:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634256	31	2023-01-24 @ 11:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634262	32	2023-01-24 @ 11:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634259	32 OFFICE	2023-01-24 @ 11:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634254	33	2023-01-24 @ 11:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634260	33 OFFICE	2023-01-24 @ 11:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634258	33A	2023-01-24 @ 11:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634265	33B	2023-01-24 @ 11:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634245	34	2023-01-24 @ 10:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634137	35	2023-01-24 @ 2:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634127	41	2023-01-24 @ 1:00 pm	2023-01-27 @ 12:00 pm	0.5 ± 0.3	2023-01-31

Radon test result report for: POOLESVILLE HS MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11634121	41 BREAK ROOM	2023-01-24 @ 2:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634117	41 BUS. ADMIN	2023-01-24 @ 2:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634118	41 CONF.	2023-01-24 @ 2:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634126	41 FINANCE	2023-01-24 @ 1:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634120	42A	2023-01-24 @ 2:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634123	42A	2023-01-24 @ 2:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634115	42A BOOTH	2023-01-24 @ 2:00 pm	2023-01-27 @ 12:00 pm	0.6 ± 0.3	2023-01-31
11634116	42A RECORDING STUIDO	2023-01-24 @ 2:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634105	44	2023-01-24 @ 1:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634102	45	2023-01-24 @ 1:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634109	45B	2023-01-24 @ 1:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634106	45B	2023-01-24 @ 1:00 pm	2023-01-27 @ 12:00 pm	0.6 ± 0.3	2023-01-31
11634103	46	2023-01-24 @ 1:00 pm	2023-01-27 @ 12:00 pm	0.8 ± 0.3	2023-01-31
11634104	47	2023-01-24 @ 1:00 pm	2023-01-27 @ 12:00 pm	0.5 ± 0.3	2023-01-31
11634108	49	2023-01-24 @ 1:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634107	49A	2023-01-24 @ 1:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634124	51	2023-01-24 @ 2:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634110	52	2023-01-24 @ 1:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634113	53	2023-01-24 @ 1:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634112	53	2023-01-24 @ 1:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634111	53	2023-01-24 @ 1:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634289	54	2023-01-24 @ 1:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634286	54 OFFICE	2023-01-24 @ 1:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634133	55	2023-01-24 @ 3:00 pm	2023-01-27 @ 12:00 pm	0.6 ± 0.3	2023-01-31
11634130	58A	2023-01-24 @ 3:00 pm	2023-01-27 @ 12:00 pm	0.6 ± 0.3	2023-01-31
11634129	58B	2023-01-24 @ 3:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634134	58C	2023-01-24 @ 3:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634299	59	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634294	60	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634295	60 OFFICE	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634298	61	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634291	61	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634293	63	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634300	64	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	0.6 ± 0.3	2023-01-31
11634248	ADMIN SECRETARY	2023-01-24 @ 10:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634251	ASST SCHOOL ADMIN	2023-01-24 @ 10:00 am	2023-01-27 @ 12:00 pm	1.9 ± 0.4	2023-01-31
11634252	ASST. PRINCIPAL	2023-01-24 @ 10:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31

Radon test result report for: POOLESVILLE HS MAIN

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
11634292	AUDITORIUM	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634290	AUDITORIUM	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634244	CAFETERIA	2023-01-24 @ 10:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634247	CAFETERIA	2023-01-24 @ 10:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634287	DRAMA OFFICE	2023-01-24 @ 1:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634280	GIRLS AUX LOCKER ROOM	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	0.6 ± 0.3	2023-01-31
11634281	GIRLS AUX LOCKER ROOM	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	0.5 ± 0.3	2023-01-31
11634282	GIRLS AUX LOCKER ROOM	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634284	GIRLS LOCKER OFFICE	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	0.7 ± 0.3	2023-01-31
11634283	GIRLS LOCKER ROOM	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634261	GYM CONDITIONING OFFICE	2023-01-24 @ 11:00 am	2023-01-27 @ 12:00 pm	0.8 ± 0.3	2023-01-31
11634264	GYM OFFICE	2023-01-24 @ 11:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634296	HEALTH OFFICE	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634243	KITCHEN OFFICE	2023-01-24 @ 10:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634242	MAIN OFFICE	2023-01-24 @ 10:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634122	MEDIA	2023-01-24 @ 2:00 pm	2023-01-27 @ 12:00 pm	0.5 ± 0.3	2023-01-31
11634119	MEDIA	2023-01-24 @ 2:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634125	MEDIA OFFICE	2023-01-24 @ 2:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634114	MEDIA WORKROOM	2023-01-24 @ 2:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634285	NEW GYM	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634297	NEW GYM	2023-01-24 @ 12:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634249	PRINCIPAL	2023-01-24 @ 10:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634139	SECURITY	2023-01-24 @ 2:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634250	SECURITY	2023-01-24 @ 10:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634288	STAGE	2023-01-24 @ 1:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31

Radon test result report for: POOLESVILLE HS SCIENCE

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
11634149	184	2023-01-24 @ 3:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634150	184A	2023-01-24 @ 3:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634150	184A	2023-01-24 @ 3:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634141	189	2023-01-24 @ 3:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634143	189	2023-01-24 @ 3:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634144	189	2023-01-24 @ 3:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634152	189A	2023-01-24 @ 3:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634153	195	2023-01-24 @ 3:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634151	199	2023-01-24 @ 3:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634148	285	2023-01-24 @ 4:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634154	39	2023-01-24 @ 4:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634157	39	2023-01-24 @ 4:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634146	39A	2023-01-24 @ 4:00 pm	2023-01-27 @ 12:00 pm	0.6 ± 0.3	2023-01-31
11634145	39B	2023-01-24 @ 4:00 pm	2023-01-27 @ 12:00 pm	0.5 ± 0.3	2023-01-31
11634147	39C	2023-01-24 @ 4:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
11634155	39D	2023-01-24 @ 4:00 pm	2023-01-27 @ 12:00 pm	0.8 ± 0.3	2023-01-31
11634156	39E	2023-01-24 @ 4:00 pm	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31

February 2, 2023

** LABORATORY ANALYSIS REPORT **

Radon test result report for: POOLESVILLE HS MAIN

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
11634101	45A	2023-01-24 @ 11:00 am	2023-01-27 @ 12:00 pm	< 0.3	2023-01-31
			•		

Table 1- Radon Testing Results				
	Poolesville HS RT			
Tes	t Period: 02/14/2023 - 02/17/2023	3		
Kit Number	Room / Area	Result		
11634068 17 < 0.3				
11634064 21 < 0.3				
11634069 40 0.7				
11633978 57 < 0.				
11634019 57 < 0.3				
11634063 57 0.6				
11634050	BOYS LR	1.2		

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI TECHNOLOGI	ES, /NC Job Number 208802
	_pCi/L Rel. Hum <u> </u>
Date Start: 1/27/23 Date Stop: 1/30/	3 Date Start: Date Stop:
	Time Start: Time Stop:
Device No.'s: (5) CHAR BAGS.	Device No.'s:
11633682,11633687,11633688	
11633695 11633696	
F3 Celt	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
B 1 22	Device No.'s:
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = $7 \mu R/h$ Elevation = 820 ft

February 3, 2023

** LABORATORY ANALYSIS REPORT **

Radon test result report for: OFFICE MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11633696	SK10	2023-01-27 @ 8:00 am	2023-01-30 @ 8:00 am	24.2 ± 1.9	2023-02-03
11633682	SK6	2023-01-27 @ 8:00 am	2023-01-30 @ 8:00 am	26.9 ± 2.1	2023-02-03
11633687	SK7	2023-01-27 @ 8:00 am	2023-01-30 @ 8:00 am	23.8 ± 1.9	2023-02-03
11633688	SK8	2023-01-27 @ 8:00 am	2023-01-30 @ 8:00 am	25.9 ± 2.1	2023-02-03
11633695	SK9	2023-01-27 @ 8:00 am	2023-01-30 @ 8:00 am	27.0 ± 2.2	2023-02-03



Engineers • Planners • Scientists • Construction Managers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon - Week 2 Retesting January Schools

Name of Schools:

- 1. A. Mario Loiederman MS
- 2. Cannon Road ES
- 3. Forest Knolls ES
- 4. Glen Haven ES
- 5. Goshen ES
- 6. Highland View ES
- 7. John F. Kennedy HS
- 8. Lakelands Park MS
- 9. Montgomery Village MS
- 10.Poolesville HS
- 11.Springbrook HS

	Date	Initials
Radon Test Kits Deployed	02/14/2023	BMU
Radon Test Kits Collected	02/17/2023	BMMI
Radon Test Kits Shipped to Lab*	02/17/2023	pen
Radon Test Kits Received by Lab*	02/20/2023	Bon

^{*}All samples sent to Air Check, Inc., 2 Saber Way, Ward Hill, MA 01835

RADON SCREENING SURVEY – FOLLOW-UP POOLESVILLE HIGH SCHOOL

17501 West Willard Road, Poolesville, Maryland 20837

EXECUTIVE SUMMARY

Date of Test Report:	3/16/16 Follow-Up	
Round of Testing:	Initial	
	Follow-up	
	Post Remediation	
# Rooms Tested	5	
# Rooms ≥ 4.0 pCi/L:	0	
Low Value:	<0.3	
High Value:	0.7	
Confirmed Rooms ≥ 4.0 pCi/L US EPA	0	
Action Level		

Summary of Sampling Events ≥ 4.0 pCi/L

Room	Result (pCi/L) 1/26/16 Initial	Result (pCi/L) 3/16/16 Follow-Up	Average Result (pCi/L)
61	<0.3 Tampered	<0.3	<0.3
1001D	Locked	0.7	0.7
1001F	Locked	<0.3	<0.3
100E	Locked	0.6	0.6
1045E	Locked	<0.3	<0.3



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

MCPS RADON TESTING

Executive Summary: Poolesville High School

Date of Test Report:	3/16/2016
Round of Testing:	Initial
	Follow-up
	Post Remediation
# Rooms Tested:	5
# Rooms \geq 4.0 pCi/L:	0
Low Value:	< 0.3
High Value:	0.7

Project Status:

Retesting completed; no further action at this time.

KCI TECHNOLOGIES, INC. WWW.kci.com

ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

March 16, 2016

Mr. Richard Cox Indoor Air Quality Team Leader Montgomery County Public Schools 850 Hungerford Drive Rockville, MD 20850

Re: Radon Testing Services

KCI Job # 12146341.29

Location: Poolesville High School

17501 West Willard Road Poolesville, MD 20837

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to the Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Poolesville High School, located at 17501 West Willard Road in Poolesville, Maryland 20837 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS056) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

KCI visited the site on February 23, 2016 and deployed seven (7) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted six (6) test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on February 26, 2016 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc. is a NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936

KCI TECHNOLOGIES, INC. WWW.kci.com

Butler Bridge Road, Mills River, North Carolina.

Evaluation of Testing Conditions:

The operating condition that represents the greatest amount of significantly occupied time for this building is; heating active, with outdoor temperature averages $\leq 65^{\circ}$ F.

KCI concludes that the test period reasonably represents normal conditions when the building is significantly occupied. Clear characterization of the radon hazard is most likely to be observed under this normal operating condition. Based on the evaluation of test conditions, this test should reasonably characterize radon hazards.

KCI also conducted observations of field conditions which could affect the results of the test and compiled weather data for the testing period. Note that strong storms and heavy rainfall were recorded during the test period. The unusual weather conditions may have resulted in atypical radon test results for this facility.

KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

Results:

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	none	n/a
<4.0 piC/L	See Attachment B	

Notes:

D- Duplicate sample

The field blank, office blanks, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L. Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C). Laboratory results and exposure data for the spike samples are also included in Attachment C.

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 316-7800.

KCI TECHNOLOGIES, INC. WWW.kci.com

Mr. Richard Cox March 16, 2016 Page 4

Sincerely,

James M. Moulsdale

Radon Measurement Specialist

KCI Technologies, Inc.

Attachments: A- Floor Plan with Test Locations

B- Table 1-Radon Test Summary Spreadsheet

C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Chek, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank*

PM- Project Manager

QC- Quality Control

*Office blanks were submitted at a rate of 1% for all samples deployed in Phase 9 testing. Office blanks were not submitted under each school individually.

Radon Testing Results Poolesville High School Test Period: 02/23/16-02/26/16		
Kit Number	Room / Area	Result
7719490	61	< 0.3
7719492	1001D	0.7
7732176	1001F	< 0.3
7732177	100E	0.6
7730693	1045E	< 0.3

	Radon Testing Results		
	Poolesville High School		
	Test Period: 02/23/16-02/26/16		
V:4 Normala a v	OC Tyme	Dogulf	
Kit Number	QC Type	Result	
7732168	D (1001F)	0.5	
7729913	FB (1001F)	< 0.3	

ATTACHMENT C

Laboratory Analytical Results

March** LABORATORY ANALYSIS 8, REPORT **

Radon test result report for:
POOLESVILLE HIGH SCHOOL
MAIN

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7719492	1001D	2016-02-23 @ 9:00 am	2016-02-26 @ 7:00 am	0.7 ± 0.3	2016-03-01
7729913	1001F	2016-02-23 @ 9:00 am	2016-02-26 @ 7:00 am	< 0.3	2016-03-01
7732168	1001F	2016-02-23 @ 9:00 am	2016-02-26 @ 7:00 am	0.5 ± 0.3	2016-03-01
7732176	1001F	2016-02-23 @ 9:00 am	2016-02-26 @ 7:00 am	< 0.3	2016-03-01
7732177	100E	2016-02-23 @ 9:00 am	2016-02-26 @ 7:00 am	0.6 ± 0.3	2016-03-01
7730693	1045E	2016-02-23 @ 10:00 am	2016-02-26 @ 7:00 am	< 0.3	2016-03-01
7719490	61	2016-02-23 @ 9:00 am	2016-02-26 @ 7:00 am	< 0.3	2016-03-01

March** LABORATORY ANALYSIS 9, REPORT **

Radon test result report for: MCPS

Phase 9 Office Blanks

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7712568	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29
7712584	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29
7719460	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29
7719481	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29
7719497	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29
7719498	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29

March** LABORATORY ANALYSIS 9, REPORT **

Radon test result report for:

MCPS
Phase 9 Office Blanks

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7731626	0	2016-02-23 @ 2:00 pm	2016-02-26 @ 3:00 pm	< 0.3	2016-03-01
7731633	0	2016-02-23 @ 2:00 pm	2016-02-26 @ 3:00 pm	< 0.3	2016-03-01
7735204	0	2016-02-23 @ 2:00 pm	2016-02-26 @ 3:00 pm	< 0.3	2016-03-01
7733204		2010-02-23 @ 2.00 pm	2010-02-20 @ 3.00 pm	V 0.5	2010-03-0

February LABORATORY ANALYSIS 23, REPORT **

Radon test result report for:
TRANSIT- PHASE 7, 8, 9
NONE

Rit# Room Id Started Started PCi/L Analyzed						
7734946 10 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7734955 11 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734956 12 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734959 13 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734959 14 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734953 15 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734954 16 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734940 17 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734943 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734942 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734939 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 21 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 22 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 25 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 25 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 29 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 31 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 31 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 4 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734937	1	2016-02-19 @ 3:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734956 12 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734959 13 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734930 14 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734953 15 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734954 16 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734940 17 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734939 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734929 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734929 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734933 22 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 25 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734937 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734937 31 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734937 31 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734931 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734931 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734931 31 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 201	7734946	10	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734959 13 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734955	11	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734930 14 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am	7734956	12	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734953 15 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am	7734959	13	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734954 16 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734930	14	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734940 17 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734953	15	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734954	16	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734948 19 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734940	17	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734939 2 2016-02-19 @ 3:00 pm 2016-02-22 @ 11:00 am < 0.3	7734949	18	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734942 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734948	19	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734929 21 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734939	2	2016-02-19 @ 3:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734933 22 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734942	20	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734929	21	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734936 24 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734933	22	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734943 25 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734934	23	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734944 26 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734936	24	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734943	25	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734928 28 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734944	26	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734952 29 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734935	27	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734947 3 2016-02-19 @ 3:00 pm 2016-02-22 @ 11:00 am < 0.3	7734928	28	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734931 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734952	29	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734932 31 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734947	3	2016-02-19 @ 3:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7718520 32 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734931	30	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7718523 33 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734932	31	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7718522 34 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7718520	32	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7718521 35 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7718523	33	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734945 4 2016-02-19 @ 3:00 pm 2016-02-22 @ 11:00 am < 0.3	7718522	34	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	
7734960 5 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7718521	35	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734958 6 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734951 7 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734957 8 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23	7734945	4	2016-02-19 @ 3:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734951 7 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734957 8 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23		5	1			2016-02-23
7734957 8 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23	7734958	6	•	2016-02-22 @ 11:00 am		2016-02-23
<u>.</u>	7734951	7	•			2016-02-23
7734938 9 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23			•			
	7734938	9	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23

February LABORATORY ANALYSIS 15, REPORT **

Spike Sample Laboratory Results

Radon test result report for: MCPS

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7718273	101A	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.5 ± 0.6	2016-02-04
7718281	102B	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.4 ± 0.6	2016-02-04
7718282	103C	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.3 ± 0.6	2016-02-04
7718288	104D	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.7 ± 0.6	2016-02-04
7718289	105E	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.6 ± 0.6	2016-02-04
7718291	106F	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.5 ± 0.6	2016-02-04

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Note: Spike samples are test canisters that are deliberately exposed to a controlled high level of radon in a laboratory. They provide a quality control measure in the testing process and do NOT reflect radon levels in the building being tested.

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI Technologica	Inc. Job Number 173704
	pCi/L Rel. Hum 45.9 % Temp. 79.0
Date Start: 1/30/16 Date Stop: 2/1/16	Date Start: Date Stop:
Time Start: <u>O9ab</u> Time Stop: <u>O9ab</u>	Time Start: Time Stop:
Device No.'s: (6) Char. Bags-	Device No.'s:
7718281, 7718282, 7718291,	
7718288, 7718289, 7718273	
E3 Left	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
	· · · · · · · · · · · · · · · · · · ·

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = $7 \mu R/h$ Elevation = 820 ft



Engineers • Planners • Scientists • Construction M anagers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon Phase 9

15. Briggs Chaney MS

Name of Schools:

1.	Rocking Horse Road ES	16.	Broad Acres ES	31.	Rosa Parks MS
2.	Rockwell ES	17.	Belmont ES	32.	Rosemary Hills ES
3.	Oakland Terrace ES	18.	Emory Grove Center	33.	Sequoyah ES
4.	Rosemont ES	19.	Forest Knolls ES	34.	Damascus HS
5.	Beall ES	20.	Baker MS	35.	Einstein ES
6.	Cresthaven ES	21.	MLK MS	36.	Forest Oak MS
7.	Quince Orchard HS	22.	Richard Montgomery HS	37.	Hoover MS
8.	Smith Center	23.	Sherwood HS	38.	Julius West MS
9.	Ashburton ES	24.	Walter Johnson HS	39.	John F. Kennedy HS
10.	Bannockburn ES	25.	Diamond ES	40.	Travilah ES
11.	Bradley Hills ES	26.	Newport Mill MS	41.	Watkins Mill HS
12.	Cannon Road ES	27.	Drew ES	42.	Northwood HS
13.	Flora M. Singer ES	28.	Monocacy ES	43.	Lincoln Center
14.	Clarksburg HS	29.	Potomac ES		

30. Rock Terrace School

	Date	Initials
Radon Test Kits Deployed	2/22/16	JM
Radon Test Kits Collected	2/25/16	JM
Radon Test Kits Shipped to Lab*	2/25/16	M
Radon Test Kits Received by Lab*	2/29/16	JM

^{*}All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759



Engineers • Planners • Scientists • Construction Managers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon Phase 9

Name of Schools:

- 1. Banneker MS
- 2. Bethesda-Chevy Chase HS
- 3. Burtonsville ES
- 4. Chevy Chase ES
- 5. Clopper Mill ES
- 6. Edison HS
- 7. Flower Hill ES
- 8. Flower Valley ES
- 9. Greencastle ES

- 10. Maryvale ES
- 11. Montgomery Blair HS
- 12. Poolesville HS
- 13. Rachel Carson ES
- 14. Stedwick ES
- 15. Watkins Mill ES
- 16. Laytonsville ES
- 17. Lincoln Center

	52.0	
	Date	Initials
Radon Test Kits Deployed	2/23/16	\/M
Radon Test Kits Collected	2/26/16	JM
Radon Test Kits Shipped to Lab*	2/26/16	JM
Radon Test Kits Received by Lab*	3/01/16	JM

^{*}All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

MCPS RADON TESTING

Executive Summary: Poolesville High School

Date of Test Report:	1/26/2016
Round of Testing:	Initial
	Follow-up
	Post Remediation
# Rooms Tested:	115
# Rooms \geq 4.0 pCi/L:	0
Low Value:	< 0.3
High Value:	0.9

Project Status:

Initial testing completed; missing or compromised samples need re-test.

KCI TECHNOLOGIES, INC. WWW.kci.com

ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

January 26, 2016

Mr. Richard Cox Indoor Air Quality Team Leader Montgomery County Public Schools 850 Hungerford Drive Rockville, MD 20850

Re: Radon Testing Services

KCI Job # 12146341.21

Location: Poolesville High School

17501 West Willard Road Poolesville, MD 20837

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to the Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Poolesville High School, located at 17501 West Willard Road in Poolesville, Maryland 20837 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS056) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

KCI visited the site on December 28, 2015 and deployed one hundred thirty-three (133) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted six (6) test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on December 31, 2015 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc. is a NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936

KCI TECHNOLOGIES, INC. WWW.kci.com

Butler Bridge Road, Mills River, North Carolina.

Evaluation of Testing Conditions:

The operating condition that represents the greatest amount of significantly occupied time for this building is; heating active, with outdoor temperature averages $\leq 65^{\circ}$ F.

KCI concludes that the test period reasonably represents normal conditions when the building is significantly occupied. Clear characterization of the radon hazard is most likely to be observed under this normal operating condition. Based on the evaluation of test conditions, this test should reasonably characterize radon hazards.

KCI also conducted observations of field conditions which could affect the results of the test and compiled weather data for the testing period. KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

Results:

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	none	n/a
<4.0 piC/L	See Attachn	nent B

Notes:

D- Duplicate sample

All field blanks, office blanks, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L. Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C). Laboratory results and exposure data for the spike samples are also included in Attachment C.

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 316-7800.

KCI TECHNOLOGIES, INC. WWW.kci.com

Mr. Richard Cox January 26, 2016 Page 4

Sincerely,

James M. Moulsdale

James Makler

Radon Measurement Specialist

KCI Technologies, Inc.

Attachments: A- Floor Plan with Test Locations

B- Table 1-Radon Test Summary Spreadsheet

C- Laboratory Analytical Results

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Chek, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

QC- Quality Control

Name		Radon Testing Results	
Kit Number Room / Area Result 7711808 1 < 0.3 7713914 2 < 0.3 7710194 3 < 0.3 7711827 4 < 0.3 7711918 6 < 0.3 7713916 8 < 0.3 7714899 9 < 0.3 7714891 11 < 0.3 7714821 11 < 0.3 7713831 12 < 0.3 7713834 14 < 0.3 7713833 16 < 0.3 7713833 16 < 0.3 7713833 16 < 0.3 7713833 16 < 0.3 7714823 17 < 0.3 7713835 18 < 0.3 7713875 19 < 0.3 7713876 19 < 0.3 7713877 21 < 0.3 7713871 20 0.6 7713871 20 0.6 7713871	Tes		
7711808 1 < 0.3 7713914 2 < 0.3 7710194 3 < 0.3 7711827 4 < 0.3 771198 6 < 0.3 7713916 8 < 0.3 7714899 9 < 0.3 7714891 10 < 0.3 7713831 12 < 0.3 7713834 14 < 0.3 7713834 14 < 0.3 7713833 16 < 0.3 7713835 18 < 0.3 7713835 18 < 0.3 7713816 19 < 0.3 7713817 < 0.3 7714811 20 0.6 7714811 20 0.6 7710190 22 < 0.3 7714817 26 < 0.3 7714807 21 < 0.3 7714807 26 < 0.3 7714808 29 < 0.3 7714809 30			
7713914 2 <0.3 7710194 3 <0.3 7710198 6 <0.3 7710198 6 <0.3 7714899 9 <0.3 7714891 11 <0.3 7714891 11 <0.3 7713831 12 <0.3 7713834 14 <0.3 7713833 16 <0.3 7713833 16 <0.3 7713835 18 <0.3 7714811 20 <0.6 7714811 20 <0.6 7714811 20 <0.6 7714811 20 <0.6 7714811 20 <0.6 7714813 24 <0.3 7714814 23 <0.3 7714813 24 <0.3 7714813 24 <0.3 7714814 26 <0.3 7714805 28 <0.3 7714829 30 <0.3<	Kit Number	Room / Area	Result
77110194 3 < 0.3 7711827 4 < 0.3 7710198 6 < 0.3 7713916 8 < 0.3 7714899 9 < 0.3 7714891 11 < 0.3 7713831 12 < 0.3 7711824 13 0.6 7713834 14 < 0.3 7713807 15 < 0.3 7713833 16 < 0.3 7713835 18 < 0.3 7713807 15 < 0.3 7713807 19 < 0.3 7714811 20 0.6 7713807 21 < 0.3 7713811 23 < 0.3 7714811 20 0.6 7713811 23 < 0.3 7714813 24 < 0.3 7714807 26 < 0.3 7714808 29 < 0.3 7714809 29 < 0.3 7714810 32	7711808	1	< 0.3
7711827 4 < 0.3	7713914		< 0.3
7710198 6 < 0.3	7710194	3	< 0.3
7713916 8 < 0.3	7711827	4	< 0.3
7714899 9 < 0.3	7710198	6	< 0.3
7714895 10 < 0.3	7713916	8	< 0.3
7714891 11 < 0.3	7714899	9	
7713831 12 < 0.3		10	
7711824 13 0.6 7713834 14 < 0.3	7714891	11	< 0.3
7713834 14 < 0.3	7713831	12	< 0.3
7711807 15 < 0.3	7711824	13	0.6
7713833 16 < 0.3		14	< 0.3
7714823 17 < 0.3	7711807	15	< 0.3
7713835 18 < 0.3	7713833	16	< 0.3
7713915 19 < 0.3	7714823	17	< 0.3
7714811 20 0.6 7713807 21 < 0.3	7713835	18	< 0.3
7713807 21 < 0.3	7713915	19	< 0.3
7710190 22 < 0.3	7714811	20	0.6
7713811 23 < 0.3	7713807	21	< 0.3
7714813 24 < 0.3	7710190	22	< 0.3
7714817 26 < 0.3	7713811	23	< 0.3
7714805 28 < 0.3	7714813	24	< 0.3
7714803 29 < 0.3	7714817	26	< 0.3
7714803 29 < 0.3	7714805	28	< 0.3
7714812 31 0.7 7714810 32 < 0.3	7714803	29	< 0.3
7714810 32 < 0.3	7714829	30	< 0.3
7714820 33 < 0.3	7714812	31	0.7
7714820 33 < 0.3	7714810	32	< 0.3
7714887 34 < 0.3	7714820	33	
7714892 35 < 0.3	7714887	34	
7714890 37 < 0.3	7714892		< 0.3
7714890 37 < 0.3	7714864	36	< 0.3
7714847 38 < 0.3	7714890		
7714843 39 < 0.3	7714847		
7714886 40 0.7 7714828 41 < 0.3			
7714828 41 < 0.3			
7714875 42 < 0.3			_
7714880 43 < 0.3			_
7714863 44 < 0.3			_
7714831 45 0.6 7714868 46 < 0.3			
7714868 46 < 0.3			_
7714832 47 < 0.3			
7714833 48 < 0.3 7714834 49 < 0.3			_
7714834 49 < 0.3			
	7714835	51	< 0.3

Table Note:
* Missing or Compromised Sample

Radon Testing Results Poolesville H.S. Test Period: 12/28/15-12/31/15 Room / Area Kit Number Result 7714836 52 < 0.3 7714896 53 < 0.3 7714838 54 < 0.3 7714842 55 < 0.3 7714802 57 < 0.3 7711802 58 < 0.3 7714859 59 < 0.3 7714845 60 < 0.3 7714865 61 < 0.3 7714907 184 < 0.3 7714849 195 < 0.3 7714853 198 < 0.3 7714874 198 < 0.3 7714893 199 < 0.3 7714854 285 < 0.3 7714879 298 < 0.3 7714908 184A < 0.3 7714877 189A < 0.3 7714850 198B < 0.3 7714851 199B < 0.3 7714906 26B < 0.3 7714816 28B < 0.3 7711803 < 0.3 33AB 7714904 33B < 0.3 7714884 42A 0.6 7714862 61 (tampered) < 0.3 7714872 < 0.3 AS 7714852 AUD < 0.3 7714857 < 0.3 **AUD** 7714858 AUD < 0.3 AUD < 0.3 7714861 7714881 BM < 0.3 7714826 **BSO** < 0.3 С 7714873 0.6 7714806 CAF < 0.3 7714821 CAF < 0.3 7714846 CON < 0.3 7714900 DG 0.6 7714807 **FART** 0.6 7714903 G1 < 0.3 7711801 **GESP** < 0.3 < 0.3 7714889 **GOF** 7714882 GUI < 0.3 7714869 **GUIC** < 0.3 7711829 **GYM** < 0.3 7710199 GYM < 0.3 7713959 GYM < 0.3 7710196 GYM2 0.6 7713808 GYM2 < 0.3 7713838 GYM2 < 0.3

Table Note:

^{*} Missing or Compromised Sample

	Radon Testing Results					
Poolesville H.S.						
Те	Test Period: 12/28/15-12/31/15					
	K't Novel on December 1					
Kit Number	Room / Area	Result				
7714841	IMC	< 0.3				
7714844	IMC	< 0.3				
7714867	JC	< 0.3				
7714878	LO	< 0.3				
7714866	MN	< 0.3				
7714894	OFF	< 0.3				
7714870	PRI	0.6				
7714809	RESOURCE	< 0.3				
7714830	RSC	< 0.3				
7714815	SEMR	< 0.3				
7714814	SERVING	< 0.3				
7714822	SERVING	< 0.3				
7714837	SO	< 0.3				
7714898	SP	0.9				
7714856	TR	< 0.3				
7714848	TV	0.6				
7714885	WR	< 0.3				
7714860	WR2	0.7				
7714804	WSC	< 0.3				

Table Note:
* Missing or Compromised Sample

Radon Testing Results Poolesville H.S.					
Т	Test Period: 12/28/15-12/31/15				
IC:4 November of	00 Toma	Daguit			
Kit Number	QC Type	Result			
7713804	D (12)	< 0.3			
7713829	D (17)	< 0.3			
7714876	D (198)	< 0.3			
7714801	D (24)	< 0.3			
7714819	D (33)	< 0.3			
7714839	D (49)	< 0.3			
7711831	D (8)	< 0.3			
7714883	D (9)	< 0.3			
7714855	D (AUD)	< 0.3			
7714840	D (IMC)	< 0.3			
7714818	D (SERVING)	< 0.3			
7714897	D (SO)	< 0.3			
7713960	FB (1)	< 0.3			
7714808	FB (20)	< 0.3			
7714825	FB (30)	< 0.3			
7714871	FB (42)	< 0.3			
7714911	OB (0)	< 0.3			
7714912	OB (0)	< 0.3			

Table Note:
* Missing or Compromised Sample

ATTACHMENT C

Laboratory Analytical Results

January LABORATORY ANALYSIS REPORT **

Radon test result report for: POOLSVILLE HS BLDG

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7714907	184	2015-12-28 @ 7:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
		_			

January LABORATORY ANALYSIS 16, REPORT **

Radon test result report for: POOLSVILLE HS BLDG 2

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7714908	184A	2015-12-28 @ 7:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714877	189A	2015-12-28 @ 3:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714849	195	2015-12-28 @ 3:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714853	198	2015-12-28 @ 3:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714874	198	2015-12-28 @ 3:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714876	198	2015-12-28 @ 3:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714850	198B	2015-12-28 @ 3:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-04
7714893	199	2015-12-28 @ 3:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714851	199B	2015-12-28 @ 3:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714854	285	2015-12-28 @ 3:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714879	298	2015-12-28 @ 3:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-04

January LABORATORY ANALYSIS 16, REPORT **

Radon test result report for:

POOLSVILLE HS GREEN HOUSE

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7714906	26B	2015-12-28 @ 7:00 pm	2015-12-31 @ 11:00 am	< 0.3	2016-01-05
7714904	33B	2015-12-28 @ 7:00 pm	2015-12-31 @ 11:00 am	< 0.3	2016-01-04
7714903	G1	2015-12-28 @ 7:00 pm	2015-12-31 @ 8:00 am	< 0.3	2016-01-05

Radon test result report for: POOLSVILLE HS MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7714911	0	2015-12-28 @ 7:00 pm	2015-12-31 @ 1:00 pm	< 0.3	2016-01-05
7714912	0	2015-12-28 @ 7:00 pm	2015-12-31 @ 1:00 pm	< 0.3	2016-01-05
7713960	1	2015-12-28 @ 1:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-04
7711808	1	2015-12-28 @ 1:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714895	10	2015-12-28 @ 2:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-04
7714891	11	2015-12-28 @ 2:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-04
7713804	12	2015-12-28 @ 12:00 pm	2015-12-31 @ 11:00 am	< 0.3	2016-01-05
7713831	12	2015-12-28 @ 12:00 pm	2015-12-31 @ 11:00 am	< 0.3	2016-01-05
7711824	13	2015-12-28 @ 12:00 pm	2015-12-31 @ 11:00 am	0.6 ± 0.3	2016-01-05
7713834	14	2015-12-28 @ 12:00 pm	2015-12-31 @ 11:00 am	< 0.3	2016-01-05
7711807	15	2015-12-28 @ 12:00 pm	2015-12-31 @ 11:00 am	< 0.3	2016-01-05
7713833	16	2015-12-28 @ 12:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-04
7714823	17	2015-12-28 @ 12:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7713829	17	2015-12-28 @ 12:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7713835	18	2015-12-28 @ 12:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7713915	19	2015-12-28 @ 11:00 am	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7713914	2	2015-12-28 @ 1:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714808	20	2015-12-28 @ 11:00 am	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714811	20	2015-12-28 @ 11:00 am	2015-12-31 @ 10:00 am	0.6 ± 0.3	2016-01-05
7713807	21	2015-12-28 @ 12:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7710190	22	2015-12-28 @ 11:00 am	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7713811	23	2015-12-28 @ 11:00 am	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714801	24	2015-12-28 @ 11:00 am	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714813	24	2015-12-28 @ 11:00 am	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714817	26	2015-12-28 @ 11:00 am	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714805	28	2015-12-28 @ 11:00 am	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714816	28B	2015-12-28 @ 11:00 am	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714803	29	2015-12-28 @ 10:00 am	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7710194	3	2015-12-28 @ 1:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714825	30	2015-12-28 @ 10:00 am	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714829	30	2015-12-28 @ 10:00 am	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714812	31	2015-12-28 @ 10:00 am	2015-12-31 @ 10:00 am	0.7 ± 0.3	2016-01-05
7714810	32	2015-12-28 @ 10:00 am	2015-12-31 @ 10:00 am	< 0.3	2016-01-04
7714819	33	2015-12-28 @ 10:00 am	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714820	33	2015-12-28 @ 10:00 am	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7711803	33AB	2015-12-28 @ 10:00 am	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714887	34	2015-12-28 @ 7:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05

Radon test result report for: POOLSVILLE HS MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7714892	35	2015-12-28 @ 7:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714864	36	2015-12-28 @ 6:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714890	37	2015-12-28 @ 7:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714847	38	2015-12-28 @ 6:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714843	39	2015-12-28 @ 6:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7711827	4	2015-12-28 @ 1:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714886	40	2015-12-28 @ 6:00 pm	2015-12-31 @ 10:00 am	0.7 ± 0.4	2016-01-05
7714828	41	2015-12-28 @ 6:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714871	42	2015-12-28 @ 5:00 pm	2015-12-31 @ 11:00 am	< 0.3	2016-01-05
7714875	42	2015-12-28 @ 5:00 pm	2015-12-31 @ 11:00 am	< 0.3	2016-01-05
7714884	42A	2015-12-28 @ 5:00 pm	2015-12-31 @ 10:00 am	0.6 ± 0.4	2016-01-05
7714880	43	2015-12-28 @ 5:00 pm	2015-12-31 @ 11:00 am	< 0.3	2016-01-05
7714863	44	2015-12-28 @ 6:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714831	45	2015-12-28 @ 6:00 pm	2015-12-31 @ 10:00 am	0.6 ± 0.4	2016-01-05
7714868	46	2015-12-28 @ 6:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714832	47	2015-12-28 @ 6:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-04
7714833	48	2015-12-28 @ 6:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714839	49	2015-12-28 @ 6:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714834	49	2015-12-28 @ 6:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714835	51	2015-12-28 @ 6:00 pm	2015-12-31 @ 11:00 am	< 0.3	2016-01-05
7714836	52	2015-12-28 @ 6:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-04
7714896	53	2015-12-28 @ 6:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-04
7714838	54	2015-12-28 @ 5:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714842	55	2015-12-28 @ 5:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714802	57	2015-12-28 @ 12:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7711802	58	2015-12-28 @ 12:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714859	59	2015-12-28 @ 4:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7710198	6	2015-12-28 @ 1:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714845	60	2015-12-28 @ 4:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714862	61	2015-12-28 @ 4:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714865	61	2015-12-28 @ 4:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7711831	8	2015-12-28 @ 2:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-04
7713916	8	2015-12-28 @ 2:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714883	9	2015-12-28 @ 2:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714899	9	2015-12-28 @ 2:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714872	AS	2015-12-28 @ 2:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714857	AUD	2015-12-28 @ 4:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-04

Radon test result report for: POOLSVILLE HS MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7714852	AUD	2015-12-28 @ 4:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714855	AUD	2015-12-28 @ 4:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714858	AUD	2015-12-28 @ 4:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714861	AUD	2015-12-28 @ 4:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714881	BM	2015-12-28 @ 2:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714826	BSO	2015-12-28 @ 9:00 am	2015-12-31 @ 10:00 am	< 0.3	2016-01-04
7714873	C	2015-12-28 @ 3:00 pm	2015-12-31 @ 9:00 am	0.6 ± 0.4	2016-01-05
7714821	CAF	2015-12-28 @ 9:00 am	2015-12-31 @ 10:00 am	< 0.3	2016-01-04
7714806	CAF	2015-12-28 @ 9:00 am	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714846	CON	2015-12-28 @ 5:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-04
7714900	DG	2015-12-28 @ 2:00 pm	2015-12-31 @ 9:00 am	0.6 ± 0.3	2016-01-05
7714807	FART	2015-12-28 @ 10:00 am	2015-12-31 @ 10:00 am	0.6 ± 0.3	2016-01-05
7711801	GESP	2015-12-28 @ 11:00 am	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714889	GOF	2015-12-28 @ 2:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-04
7714882	GUI	2015-12-28 @ 2:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-04
7714869	GUIC	2015-12-28 @ 2:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7713959	GYM	2015-12-28 @ 1:00 pm	2015-12-31 @ 11:00 am	< 0.3	2016-01-05
7710199	GYM	2015-12-28 @ 1:00 pm	2015-12-31 @ 11:00 am	< 0.3	2016-01-05
7711829	GYM	2015-12-28 @ 1:00 pm	2015-12-31 @ 11:00 am	< 0.3	2016-01-05
7713838	GYM2	2015-12-28 @ 1:00 pm	2015-12-31 @ 11:00 am	< 0.3	2016-01-05
7710196	GYM2	2015-12-28 @ 1:00 pm	2015-12-31 @ 11:00 am	0.6 ± 0.3	2016-01-05
7713808	GYM2	2015-12-28 @ 1:00 pm	2015-12-31 @ 11:00 am	< 0.3	2016-01-05
7714840	IMC	2015-12-28 @ 5:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714841	IMC	2015-12-28 @ 5:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714844	IMC	2015-12-28 @ 5:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714867	JC	2015-12-28 @ 2:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714878	LO	2015-12-28 @ 4:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714866	MN	2015-12-28 @ 2:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714894	OFF	2015-12-28 @ 5:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714870	PRI	2015-12-28 @ 2:00 pm	2015-12-31 @ 9:00 am	0.6 ± 0.4	2016-01-05
7714809	RESOURCE	2015-12-28 @ 11:00 am	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714830	RSC	2015-12-28 @ 6:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714815	SEMR	2015-12-28 @ 12:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-04
7714814	SERVING	2015-12-28 @ 10:00 am	2015-12-31 @ 11:00 am	< 0.3	2016-01-05
7714818	SERVING	2015-12-28 @ 10:00 am	2015-12-31 @ 11:00 am	< 0.3	2016-01-05
7714822	SERVING	2015-12-28 @ 10:00 am	2015-12-31 @ 11:00 am	< 0.3	2016-01-05
7714837	SO	2015-12-28 @ 6:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05

January LABORATORY ANALYSIS REPORT **

Radon test result report for: POOLSVILLE HS MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7714897	SO	2015-12-28 @ 5:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714898	SP	2015-12-28 @ 2:00 pm	2015-12-31 @ 9:00 am	0.9 ± 0.4	2016-01-05
7714856	TR	2015-12-28 @ 4:00 pm	2015-12-31 @ 10:00 am	< 0.3	2016-01-05
7714848	TV	2015-12-28 @ 5:00 pm	2015-12-31 @ 10:00 am	0.6 ± 0.4	2016-01-05
7714885	WR	2015-12-28 @ 3:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-05
7714860	WR2	2015-12-28 @ 4:00 pm	2015-12-31 @ 10:00 am	0.7 ± 0.3	2016-01-04
7714804	WSC	2015-12-28 @ 12:00 pm	2015-12-31 @ 9:00 am	< 0.3	2016-01-04

January LABORATORY ANALYSIS 15, REPORT **

Radon test result report for: MCPS PHASE 3 & 4 TRANSIT BLANKS

7708200 TRANSIT 1 2015-12 7708190 TRANSIT 10 2015-12 7708189 TRANSIT 11 2015-12 7708181 TRANSIT 12 2015-12 7708188 TRANSIT 13 2015-12 7708186 TRANSIT 14 2015-12 7708186 TRANSIT 15 2015-12 7708185 TRANSIT 16 2015-12 7708184 TRANSIT 17 2015-12 7708182 TRANSIT 18 2015-12 7708187 TRANSIT 18 2015-12 7708180 TRANSIT 2 2015-12 7708181 TRANSIT 20 2015-12 7708183 TRANSIT 21 2015-12 7708184 TRANSIT 22 2015-12 7708178 TRANSIT 23 2015-12 7708179 TRANSIT 24 2015-12 7708176 TRANSIT 25 2015-12 7708176 TRANSIT 26 2015-12 7708177 TRANSIT 27 2015-12 7708173 TRANSIT 28 2015-12 7708175 TRANSIT 29 2015-12 7708175 TRANSIT 29 2015-12 7708175 TRANSIT 29 2015-12 7708176 TRANSIT 29 2015-12 7708177 TRANSIT 29 2015-12 7708178 TRANSIT 29 2015-12 7708179 TRANSIT 29 2015-12 7708170 TRANSIT 29 2015-12 7708171 TRANSIT 29 2015-12 7708172 TRANSIT 30 2015-12	2-18 @ 12:00 pm 2-18 @ 12:00 pm	Ended 2015-12-21 @ 12:00 pm 2015-12-21 @ 12:00 pm	< 0.3 < 0.3 < 0.3 < 0.3 < 0.3 < 0.3	Analyzed 2015-12-23 2015-12-23 2015-12-23 2015-12-23 2015-12-23 2015-12-23 2015-12-23
7708200 TRANSIT 1 2015-12 7708190 TRANSIT 10 2015-12 7708189 TRANSIT 11 2015-12 7708191 TRANSIT 12 2015-12 7708181 TRANSIT 13 2015-12 7708188 TRANSIT 14 2015-12 7708186 TRANSIT 15 2015-12 7708185 TRANSIT 16 2015-12 7708184 TRANSIT 17 2015-12 7708182 TRANSIT 18 2015-12 7708187 TRANSIT 18 2015-12 7708180 TRANSIT 2 2015-12 7708181 TRANSIT 20 2015-12 7708183 TRANSIT 21 2015-12 7708184 TRANSIT 22 2015-12 7708175 TRANSIT 24 2015-12 7708176 TRANSIT 25 2015-12 7708177 TRANSIT 26 2015-12 7708174 TRANSIT 27 2015-12 7708175 TRANSIT 28 2015-12 7708175 TRANSIT 29 2015-12 7708176 TRANSIT 29 2015-12 7708177 TRANSIT 29 2015-12 7708178 TRANSIT 29 2015-12 7708179 TRANSIT 27 2015-12 7708170 TRANSIT 28 2015-12 7708171 TRANSIT 29 2015-12 7708172 TRANSIT 30 2015-12 7708172 TRANSIT 30 2015-12	2-18 @ 12:00 pm 2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm 2015-12-21 @ 12:00 pm	< 0.3 < 0.3 < 0.3 < 0.3 < 0.3 < 0.3	2015-12-23 2015-12-23 2015-12-23 2015-12-23 2015-12-23 2015-12-23
7708190 TRANSIT 10 2015-12 7708189 TRANSIT 11 2015-12 7708191 TRANSIT 12 2015-12 7708188 TRANSIT 13 2015-12 7708197 TRANSIT 14 2015-12 7708186 TRANSIT 15 2015-12 7708185 TRANSIT 16 2015-12 7708184 TRANSIT 17 2015-12 7708182 TRANSIT 18 2015-12 7708187 TRANSIT 18 2015-12 7708199 TRANSIT 2 2015-12 7708180 TRANSIT 20 2015-12 7708183 TRANSIT 21 2015-12 7708179 TRANSIT 22 2015-12 7708179 TRANSIT 23 2015-12 7708179 TRANSIT 24 2015-12 7708170 TRANSIT 25 2015-12 7708171 TRANSIT 26 2015-12 7708172 TRANSIT 27 2015-12 7708173 TRANSIT 27 2015-12 7708174 TRANSIT 27 2015-12 7708175 TRANSIT 29 2015-12 7708176 TRANSIT 29 2015-12 7708177 TRANSIT 29 2015-12 7708178 TRANSIT 29 2015-12 7708179 TRANSIT 29 2015-12 7708170 TRANSIT 29 2015-12 7708171 TRANSIT 29 2015-12 7708172 TRANSIT 30 2015-12	2-18 @ 12:00 pm 2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm 2015-12-21 @ 12:00 pm	< 0.3 < 0.3 < 0.3 < 0.3 < 0.3	2015-12-23 2015-12-23 2015-12-23 2015-12-23 2015-12-23
7708189 TRANSIT 11 2015-12 7708191 TRANSIT 12 2015-12 7708188 TRANSIT 13 2015-12 7708197 TRANSIT 14 2015-12 7708186 TRANSIT 15 2015-12 7708185 TRANSIT 16 2015-12 7708184 TRANSIT 17 2015-12 7708182 TRANSIT 18 2015-12 7708187 TRANSIT 18 2015-12 7708199 TRANSIT 2 2015-12 7708180 TRANSIT 20 2015-12 7708183 TRANSIT 21 2015-12 7708178 TRANSIT 22 2015-12 7708179 TRANSIT 23 2015-12 7708179 TRANSIT 24 2015-12 7708170 TRANSIT 25 2015-12 7708171 TRANSIT 26 2015-12 7708172 TRANSIT 27 2015-12 7708173 TRANSIT 28 2015-12 7708174 TRANSIT 29 2015-12 7708175 TRANSIT 29 2015-12 7708176 TRANSIT 29 2015-12 7708177 TRANSIT 29 2015-12 7708178 TRANSIT 29 2015-12 7708179 TRANSIT 27 2015-12 7708170 TRANSIT 28 2015-12 7708171 TRANSIT 29 2015-12 7708172 TRANSIT 30 2015-12	2-18 @ 12:00 pm 2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm 2015-12-21 @ 12:00 pm	< 0.3 < 0.3 < 0.3 < 0.3 < 0.3	2015-12-23 2015-12-23 2015-12-23 2015-12-23
7708191 TRANSIT 12 2015-12 7708188 TRANSIT 13 2015-12 7708197 TRANSIT 14 2015-12 7708186 TRANSIT 15 2015-12 7708185 TRANSIT 16 2015-12 7708184 TRANSIT 17 2015-12 7708182 TRANSIT 18 2015-12 7708187 TRANSIT 18 2015-12 7708199 TRANSIT 2 2015-12 7708180 TRANSIT 20 2015-12 7708183 TRANSIT 21 2015-12 7708178 TRANSIT 22 2015-12 7708179 TRANSIT 23 2015-12 7708179 TRANSIT 24 2015-12 7708170 TRANSIT 25 2015-12 7708171 TRANSIT 25 2015-12 7708172 TRANSIT 26 2015-12 7708173 TRANSIT 27 2015-12 7708174 TRANSIT 28 2015-12 7708175 TRANSIT 29 2015-12 7708176 TRANSIT 29 2015-12 7708177 TRANSIT 29 2015-12 7708177 TRANSIT 29 2015-12 7708178 TRANSIT 29 2015-12 7708179 TRANSIT 29 2015-12 7708170 TRANSIT 29 2015-12 7708171 TRANSIT 29 2015-12 7708172 TRANSIT 30 2015-12	2-18 @ 12:00 pm 2-18 @ 12:00 pm 2-18 @ 12:00 pm 2-18 @ 12:00 pm 2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm 2015-12-21 @ 12:00 pm 2015-12-21 @ 12:00 pm 2015-12-21 @ 12:00 pm 2015-12-21 @ 12:00 pm	< 0.3 < 0.3 < 0.3	2015-12-23 2015-12-23
7708188 TRANSIT 13 2015-12 7708197 TRANSIT 14 2015-12 7708186 TRANSIT 15 2015-12 7708185 TRANSIT 16 2015-12 7708184 TRANSIT 17 2015-12 7708182 TRANSIT 18 2015-12 7708187 TRANSIT 18 2015-12 7708199 TRANSIT 2 2015-12 7708180 TRANSIT 20 2015-12 7708183 TRANSIT 21 2015-12 7708178 TRANSIT 22 2015-12 7708179 TRANSIT 23 2015-12 7708179 TRANSIT 24 2015-12 7708170 TRANSIT 25 2015-12 7708171 TRANSIT 26 2015-12 7708172 TRANSIT 27 2015-12 7708173 TRANSIT 27 2015-12 7708174 TRANSIT 27 2015-12 7708175 TRANSIT 29 2015-12 7708176 TRANSIT 29 2015-12 7708177 TRANSIT 29 2015-12 7708178 TRANSIT 29 2015-12 7708179 TRANSIT 30 2015-12	2-18 @ 12:00 pm 2-18 @ 12:00 pm 2-18 @ 12:00 pm 2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm 2015-12-21 @ 12:00 pm 2015-12-21 @ 12:00 pm 2015-12-21 @ 12:00 pm	< 0.3 < 0.3 < 0.3	2015-12-23
7708186 TRANSIT 15 2015-12 7708185 TRANSIT 16 2015-12 7708184 TRANSIT 17 2015-12 7708182 TRANSIT 18 2015-12 7708187 TRANSIT 18 2015-12 7708199 TRANSIT 2 2015-12 7708181 TRANSIT 20 2015-12 7708180 TRANSIT 21 2015-12 7708183 TRANSIT 22 2015-12 7708178 TRANSIT 23 2015-12 7708179 TRANSIT 24 2015-12 7708177 TRANSIT 25 2015-12 7708176 TRANSIT 26 2015-12 7708177 TRANSIT 27 2015-12 7708178 TRANSIT 27 2015-12 7708179 TRANSIT 27 2015-12 7708170 TRANSIT 27 2015-12 7708171 TRANSIT 28 2015-12 7708172 TRANSIT 29 2015-12 7708173 TRANSIT 29 2015-12 7708174 TRANSIT 29 2015-12 7708175 TRANSIT 30 2015-12	2-18 @ 12:00 pm 2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm 2015-12-21 @ 12:00 pm 2015-12-21 @ 12:00 pm	< 0.3	
7708186 TRANSIT 15 2015-12 7708185 TRANSIT 16 2015-12 7708184 TRANSIT 17 2015-12 7708182 TRANSIT 18 2015-12 7708187 TRANSIT 18 2015-12 7708199 TRANSIT 2 2015-12 7708181 TRANSIT 20 2015-12 7708180 TRANSIT 21 2015-12 7708183 TRANSIT 22 2015-12 7708178 TRANSIT 23 2015-12 7708179 TRANSIT 24 2015-12 7708177 TRANSIT 25 2015-12 7708176 TRANSIT 26 2015-12 7708177 TRANSIT 27 2015-12 7708178 TRANSIT 27 2015-12 7708179 TRANSIT 27 2015-12 7708170 TRANSIT 27 2015-12 7708171 TRANSIT 28 2015-12 7708172 TRANSIT 29 2015-12 7708173 TRANSIT 29 2015-12 7708174 TRANSIT 29 2015-12 7708175 TRANSIT 30 2015-12	2-18 @ 12:00 pm 2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm 2015-12-21 @ 12:00 pm		2015 12 22
7708185 TRANSIT 16 2015-12 7708184 TRANSIT 17 2015-12 7708182 TRANSIT 18 2015-12 7708187 TRANSIT 18 2015-12 7708199 TRANSIT 2 2015-12 7708180 TRANSIT 20 2015-12 7708183 TRANSIT 21 2015-12 7708178 TRANSIT 22 2015-12 7708179 TRANSIT 23 2015-12 7708179 TRANSIT 24 2015-12 7708170 TRANSIT 25 2015-12 7708171 TRANSIT 26 2015-12 7708172 TRANSIT 27 2015-12 7708173 TRANSIT 27 2015-12 7708174 TRANSIT 28 2015-12 7708175 TRANSIT 29 2015-12 7708176 TRANSIT 29 2015-12 7708177 TRANSIT 29 2015-12 7708178 TRANSIT 29 2015-12 7708179 TRANSIT 30 2015-12	2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm	< 0.3	ZU13-1Z-Z3
7708182 TRANSIT 18 2015-12 7708187 TRANSIT 18 2015-12 7708199 TRANSIT 2 2015-12 7708181 TRANSIT 20 2015-12 7708180 TRANSIT 21 2015-12 7708183 TRANSIT 22 2015-12 7708178 TRANSIT 23 2015-12 7708179 TRANSIT 24 2015-12 7708177 TRANSIT 25 2015-12 7708176 TRANSIT 26 2015-12 7708174 TRANSIT 27 2015-12 7708175 TRANSIT 28 2015-12 7708175 TRANSIT 29 2015-12 7708198 TRANSIT 3 2015-12 7708172 TRANSIT 3 2015-12	2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm		2015-12-23
7708187 TRANSIT 18 2015-12 7708199 TRANSIT 2 2015-12 7708181 TRANSIT 20 2015-12 7708180 TRANSIT 21 2015-12 7708183 TRANSIT 22 2015-12 7708178 TRANSIT 23 2015-12 7708179 TRANSIT 24 2015-12 7708177 TRANSIT 25 2015-12 7708174 TRANSIT 26 2015-12 7708174 TRANSIT 27 2015-12 7708175 TRANSIT 28 2015-12 7708175 TRANSIT 29 2015-12 7708198 TRANSIT 3 2015-12 7708172 TRANSIT 30 2015-12			< 0.3	2015-12-23
7708199 TRANSIT 2 2015-12 7708181 TRANSIT 20 2015-12 7708180 TRANSIT 21 2015-12 7708183 TRANSIT 22 2015-12 7708178 TRANSIT 23 2015-12 7708179 TRANSIT 24 2015-12 7708177 TRANSIT 25 2015-12 7708176 TRANSIT 26 2015-12 7708174 TRANSIT 27 2015-12 7708173 TRANSIT 28 2015-12 7708175 TRANSIT 29 2015-12 7708198 TRANSIT 3 2015-12 7708172 TRANSIT 3 2015-12	2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm	< 0.3	2015-12-23
7708181 TRANSIT 20 2015-12 7708180 TRANSIT 21 2015-12 7708183 TRANSIT 22 2015-12 7708178 TRANSIT 23 2015-12 7708179 TRANSIT 24 2015-12 7708177 TRANSIT 25 2015-12 7708176 TRANSIT 26 2015-12 7708174 TRANSIT 27 2015-12 7708173 TRANSIT 28 2015-12 7708175 TRANSIT 29 2015-12 7708176 TRANSIT 29 2015-12 7708177 TRANSIT 29 2015-12 7708178 TRANSIT 30 2015-12	2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm	< 0.3	2015-12-23
7708180 TRANSIT 21 2015-12 7708183 TRANSIT 22 2015-12 7708178 TRANSIT 23 2015-12 7708179 TRANSIT 24 2015-12 7708177 TRANSIT 25 2015-12 7708176 TRANSIT 26 2015-12 7708174 TRANSIT 27 2015-12 7708173 TRANSIT 28 2015-12 7708175 TRANSIT 29 2015-12 7708198 TRANSIT 3 2015-12 7708172 TRANSIT 30 2015-12	2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm	< 0.3	2015-12-23
7708183 TRANSIT 22 2015-12 7708178 TRANSIT 23 2015-12 7708179 TRANSIT 24 2015-12 7708177 TRANSIT 25 2015-12 7708176 TRANSIT 26 2015-12 7708174 TRANSIT 27 2015-12 7708173 TRANSIT 28 2015-12 7708175 TRANSIT 29 2015-12 7708198 TRANSIT 3 2015-12 7708172 TRANSIT 30 2015-12	2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm	< 0.3	2015-12-23
7708178 TRANSIT 23 2015-12 7708179 TRANSIT 24 2015-12 7708177 TRANSIT 25 2015-12 7708176 TRANSIT 26 2015-12 7708174 TRANSIT 27 2015-12 7708173 TRANSIT 28 2015-12 7708175 TRANSIT 29 2015-12 7708198 TRANSIT 3 2015-12 7708172 TRANSIT 30 2015-12	2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm	< 0.3	2015-12-23
7708179 TRANSIT 24 2015-12 7708177 TRANSIT 25 2015-12 7708176 TRANSIT 26 2015-12 7708174 TRANSIT 27 2015-12 7708173 TRANSIT 28 2015-12 7708175 TRANSIT 29 2015-12 7708198 TRANSIT 3 2015-12 7708172 TRANSIT 30 2015-12	2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm	< 0.3	2015-12-23
7708177 TRANSIT 25 2015-12 7708176 TRANSIT 26 2015-12 7708174 TRANSIT 27 2015-12 7708173 TRANSIT 28 2015-12 7708175 TRANSIT 29 2015-12 7708198 TRANSIT 3 2015-12 7708172 TRANSIT 30 2015-12	2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm	< 0.3	2015-12-23
7708176 TRANSIT 26 2015-12 7708174 TRANSIT 27 2015-12 7708173 TRANSIT 28 2015-12 7708175 TRANSIT 29 2015-12 7708198 TRANSIT 3 2015-12 7708172 TRANSIT 30 2015-12	2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm	< 0.3	2015-12-23
7708174 TRANSIT 27 2015-12 7708173 TRANSIT 28 2015-12 7708175 TRANSIT 29 2015-12 7708198 TRANSIT 3 2015-12 7708172 TRANSIT 30 2015-12	2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm	< 0.3	2015-12-23
7708173 TRANSIT 28 2015-12 7708175 TRANSIT 29 2015-12 7708198 TRANSIT 3 2015-12 7708172 TRANSIT 30 2015-12	2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm	< 0.3	2015-12-23
7708175 TRANSIT 29 2015-12 7708198 TRANSIT 3 2015-12 7708172 TRANSIT 30 2015-12	2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm	< 0.3	2015-12-23
7708198 TRANSIT 3 2015-12 7708172 TRANSIT 30 2015-12	2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm	< 0.3	2015-12-23
7708172 TRANSIT 30 2015-12	2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm	< 0.3	2015-12-23
	2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm	< 0.3	2015-12-23
	, 10 € 12.00 hiii	2015-12-21 @ 12:00 pm	< 0.3	2015-12-23
7708194 TRANSIT 5 2015-12	2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm	< 0.3	2015-12-23
7708196 TRANSIT 6 2015-12	-		< 0.3	2015-12-23
7708193 TRANSIT 7 2015-12	2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm	< 0.3	2015-12-23
7708192 TRANSIT 8 2015-12	2-18 @ 12:00 pm 2-18 @ 12:00 pm	2015-12-21 @ 12:00 pm 2015-12-21 @ 12:00 pm		2015-12-23
7708195 TRANSIT 9 2015-12	2-18 @ 12:00 pm 2-18 @ 12:00 pm 2-18 @ 12:00 pm	•	< 0.3	

December LABORATORY ANALYSIS 23, REPORT **

Spike Sample Laboratory Results

Radon test result report for: MCPS

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7706380	101	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	25.2	2015-12-23
7706381	102	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	26.5	2015-12-23
7706208	103	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	27.7	2015-12-23
7705132	104	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	28.6	2015-12-23
7706366	105	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	26.5	2015-12-23
7706211	106	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	26.1	2015-12-23

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Note: Spike samples are test canisters that are deliberately exposed to a controlled high level of radon in a laboratory. They provide a quality control measure in the testing process and do NOT reflect radon levels in the building being tested.

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI Technologies.	Inc. Job Number 173224
	pCi/L Rel. Hum <u>49.6</u> % Temp. <u>69.9</u>
Date Start: 12/18/15 Date Stop: 12/21/5	Date Start: Date Stop:
Time Start: <u>0929</u> Time Stop: <u>0929</u>	Time Start: Time Stop:
Device No.'s: 7705132,7766208	Device No.'s:
7706211,7706366,	
7706380, 7706381	
F3 Loft	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
	-
1	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = $7 \mu R/h$ Elevation = 820 ft



Engineers • Planners • Scientists • Construction Managers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Chain of Custody

Project Name: MCPS Radon Phase III

Name of Schools:

1. Burnt Mills ES	13. Georgian Frost ES	25. Northlake Center
2. Burtonsville ES	14. Germantown ES	26. Olney ES
3. Cedar Grove ES	15. Goshen ES	27. Rosa Parks MS
4. Cloverly ES	16. Greencastle ES	28. Poolesville ES
5. Cold Spring ES	17. Greenwood ES	29. Poolesville HS
6. Damascus HS	18. Lake Seneca ES	30. Potomac ES
7. Darnestown ES	19. Laytonsville ES	31. Rock Terrace HS
8. Diamond ES	20. Col. E. Brooke MS	32. Rosemary Hills ES
9. Charles R. Drew ES	21. Luxmanor ES	33. Carl Sandburg
10. DuFief ES	22. Magruder HS	34. Sequoyah ES
11. Thomas Edison HS	23. Thur. Marshall ES	35. Stedwick ES
12. Robert Frost MS	24. Monocacy ES	36. Whetstone ES

	Date	Initials
Radon Test Kits Deployed	12/28/15	JM
Radon Test Kits Sampled	12/31/15	JM
Radon Test Kits Shipped to Lab*	12/31/15	JM
Radon Test Kits Received by Lab*	114/16	JM

^{*}All samples sent to Air Check, Inc., 1936 Butler Bridge Road, Mills River, NC 28758