

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

MCPS RADON TESTING – EXECUTIVE SUMMARY

Site Name	Quince Orchard High	
	School	
Date of Test Report	2/16/2023	
Round of Testing	Initial	
	Follow-up	
	Post Remediation	
	2 Year Testing	
	5 Year Testing	
	HVAC Upgrade	
	Window Replacement	
	New Addition	
	New Facility	
# Rooms Tested	94	
# Rooms \geq 4.0 pCi/L	0	
Lowest Value	<0.3 pCi/L	
Highest Value	1.8 pCi/L	

Project Status:

1. 2-Year retesting completed.

KCI Technologies, Inc. WWW.kci.com

ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

February 16, 2023

Mr. Brian Croyle Environmental Specialist Montgomery County Public Schools Gaithersburg, MD 20879

Re: Radon Testing Services

KCI Job # 122210551

Location: Quince Orchard High School

15800 Quince Orchard Road Gaithersburg, MD 20878

Dear Mr. Croyle:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Quince Orchard High School, located at 15800 Quince Orchard Rd. Gaithersburg, MD 20878 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Proficiency Program (NRPP) Radon Measurement Specialist (certification #111004 RT) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from https://www.montgomeryschoolsmd.org or www.epa.gov/radon.

KCI visited the site on January 9, 2023 and deployed one hundred six (106) activated charcoal (AC) radon test kits. KCI deployed radon test kits in all frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance.

A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI also included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on January 12, 2023 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Accustar Labs - MA for analysis by gamma-ray spectroscopy.

KCI Technologies, Inc. www.kci.com

Accustar Labs - MA is a NRSB certified analytical laboratory for radon analysis (certification #ARL0017) located at 2 Saber Way, Ward Hill, MA 01835.

Evaluation of Testing Conditions:

These tests represent:

• Follow up to post mitigation biennial testing.

These tests were conducted to:

- Confirm the success of the mitigation system(s).
- Evaluate radon concentration levels due to Addition/HVAC Upgrades/Replacement.

According to AARST, *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room during the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate temperatures ranged from the 26°F to the mid 56°F. Maximum sustained winds ranged from 0-21 miles per hour. Average humidity was around 68% with .09 inches of precipitation (rain) was recorded during testing period.

Results:

The sampling locations and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). Sampling locations and associated test kit identification numbers and relevant field observations are listed on Table 3 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result	
≥4.0 piC/L	None	N/A	
<4.0 piC/L	See Attachment B		

KCI Technologies, Inc. WWW.kci.com

Quality Control Samples			
Results of Blank Canisters:	The office blanks, and lab transit blanks had test results of		
less than the laboratory detection limit of 0.3 pCi/L.			
Adequate Laboratory Precision? Review of the duplicate sample analysis indicates that			
	adequate laboratory measurement precision was achieved.		
Spike Sample Analysis: The Spike Sample analysis results indicate the laborate			
	operating within statistical control limits.		

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 891-1769.

Sincerely,

Tyler P. McCleaf

Radon Measurement Provider

#111004 RT

KCI Technologies, Inc.

Tyler McCleaf

Attachments: A- Floor Plan with Test Locations

B- Table 1-3, Radon Test Summary Spreadsheets

C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Check, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

OC- Quality Control

Table 1- Radon Testing Results	
Quince Orchard HS	

Test Period: 01/09/2023 - 01/12/2023

Kit Number	Room / Area	Result
11285878	100	< 0.3
11285868	101	< 0.3
11285876	102	0.5
11284853	103	< 0.3
11284864	105	< 0.3
11285886	106	1.1
11285888	108	1.2
11285837	112	< 0.3
11285830	116	0.7
11285843	117	< 0.3
11285822	118	< 0.3
11285809	119	< 0.3
11285817	119	0.8
11285825	120	< 0.3
11285846	120	< 0.3
11284871	121	< 0.3
11284870	122	0.6
11285815	124	< 0.3
11284866	125	< 0.3
11285852	126	0.6
11285834	128	0.5
11285853	129	< 0.3
11285854	130	0.8
11285840	131	1.0
11285841	132	< 0.3
11285842	133	0.6
11285863	138	0.7
11285864	140	< 0.3
11285869	140	< 0.3
11285861	141	0.7
11285860	143	< 0.3
11285859	144	< 0.3
11285871	145	1.1
11285870	148	< 0.3
11285872	148	< 0.3
11284867	149	1.0
11285857	149	0.9
11284865	150	0.6
11285867	151	0.9
11285858	152	0.7
11285849	153	1.1
11285850	154	0.8

Table 1- Radon Testing Results	
Quince Orchard HS	

Test Period: 01/09/2023 - 01/12/2023

Kit Number	Room / Area	Result
11285806	200	< 0.3
11285811	206	0.6
11285827	206	< 0.3
11285819	207	1.0
11285828	207	0.5
11285829	207	< 0.3
11285812	214	< 0.3
11285813	214	< 0.3
11285805	217	0.7
11285804	219	< 0.3
11284861	256	< 0.3
11285836	259	< 0.3
11285891	301	0.7
11285877	101A	0.8
11285875	104A	0.8
11285865	104B	0.6
11285866	104B	0.8
11284860	105B	< 0.3
11284854	105C	< 0.3
11285807	105D	0.6
11284862	105E	< 0.3
11284872	105E	0.6
11285844	105E	< 0.3
11285892	105F	< 0.3
11285808	105G	0.7
11285873	105H	< 0.3
11285881	1051	< 0.3
11285814	105J	< 0.3
11285802	105K	0.5
11285835	105L	< 0.3
11285874	105M	< 0.3
11285882	105M	< 0.3
11285887	105M	0.6
11285885	106B	1.1
11285879	108A	0.8
11285880	108B	1.1
11285883	110A	0.6
11285893	110B	< 0.3
11285884	110C	0.5
11285818	116A	0.5
11285824	116A	< 0.3
11285838	118A	0.7

Table 1- Radon Testing Results			
	Quince Orchard HS		
Tes	t Period: 01/09/2023 - 01/12/2023	3	
Kit Number	Room / Area	Result	
11285823	119B	0.8	
11285845	119E	0.6	
11285831	119F	0.7	
11285801	0.9		
11285816	1.1		
11284869 120A		< 0.3	
11284868	122B	< 0.3	
11285832	125A	0.6	
11285839	125A	0.9	
11285826	134B	1.1	
11285851	134B	0.8	
11285855	134C	< 0.3	
11285847	134D	1.0	
11285848	134D	< 0.3	
	•		

200D

200F

AUDITORIUM

AUDITORIUM

DIRECTOR OFFICE

KITCHEN OFFICE

STAGE

STAGE

0.5

< 0.3

0.7

0.6 1.8

1.3

0.7

0.9

11285820

11285821

11285856

11285862

11285833

11285803

11284846

11285810

Table 2- Radon Testing Results					
	Quince Orchard HS				
	Test Period:	01/09/23 - 01/12/23			
Kit Number	QC Type	Room / Area	Result		
11285817	D	119	0.8		
11285825	FB	120	< 0.3		
11285870 FB 148		< 0.3			
11284867 D 149					
11285829 D 207 <					
11285866 D 104b C		0.8			
11284862	FB	105E < (
11284872	D	105e	0.6		
11285887	D	105m	0.6		
11285832	D	125A	0.6		
11285851	D	134b	0.8		
11285848	FB	134d	< 0.3		
11285160	ОВ	OFFICE BLANK	< 0.3		
11285167 TB TRAVEL BLANK < 0.3					

Summary of Missed Locations					
Quince Orchard HS					
Т	est Period: 01/09/23 - 01/12/23				
Kit Number Room/Area Result					
	N/A				
		-			

Summary of Missing, Compromised and >/= 4 piC/L Tests						
Quince Orchard HS						
	Test Period: 01/09/23 - 01/12/23					
Kit Number Room/Area Result						
	N/A					

Table Note:

^{*} Missing or Compromised Sample

ATTACHMENT C

Laboratory Analytical Results

Radon test result report for: QUINCE ORCHARD HS

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11285878	100	2023-01-09 @ 11:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11285868	101	2023-01-09 @ 11:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11285877	101A	2023-01-09 @ 11:00 am	2023-01-12 @ 9:00 am	0.8 ± 0.4	2023-01-16
11285876	102	2023-01-09 @ 11:00 am	2023-01-12 @ 9:00 am	0.5 ± 0.4	2023-01-16
11284853	103	2023-01-09 @ 9:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11285875	104A	2023-01-09 @ 11:00 am	2023-01-12 @ 9:00 am	0.8 ± 0.4	2023-01-16
11285865	104B	2023-01-09 @ 11:00 am	2023-01-12 @ 9:00 am	0.6 ± 0.4	2023-01-16
11285866	104B	2023-01-09 @ 11:00 am	2023-01-12 @ 9:00 am	0.8 ± 0.3	2023-01-16
11284864	105	2023-01-09 @ 9:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11284860	105B	2023-01-09 @ 9:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11284854	105C	2023-01-09 @ 9:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11285807	105D	2023-01-09 @ 9:00 am	2023-01-12 @ 9:00 am	0.6 ± 0.3	2023-01-16
11284862	105E	2023-01-09 @ 9:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11285844	105E	2023-01-09 @ 9:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11284872	105E	2023-01-09 @ 9:00 am	2023-01-12 @ 9:00 am	0.6 ± 0.3	2023-01-16
11285892	105F	2023-01-09 @ 12:00 pm	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11285808	105G	2023-01-09 @ 9:00 am	2023-01-12 @ 9:00 am	0.7 ± 0.4	2023-01-16
11285873	105H	2023-01-09 @ 12:00 pm	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11285881	105I	2023-01-09 @ 12:00 pm	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11285814	105J	2023-01-09 @ 9:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11285802	105K	2023-01-09 @ 9:00 am	2023-01-12 @ 9:00 am	0.5 ± 0.3	2023-01-16
11285835	105L	2023-01-09 @ 9:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11285874	105M	2023-01-09 @ 12:00 pm	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11285887	105M	2023-01-09 @ 12:00 pm	2023-01-12 @ 9:00 am	0.6 ± 0.4	2023-01-16
11285882	105M	2023-01-09 @ 12:00 pm	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11285886	106	2023-01-09 @ 11:00 am	2023-01-12 @ 9:00 am	1.1 ± 0.4	2023-01-16
11285885	106B	2023-01-09 @ 11:00 am	2023-01-12 @ 9:00 am	1.1 ± 0.4	2023-01-16
11285888	108	2023-01-09 @ 11:00 am	2023-01-12 @ 9:00 am	1.2 ± 0.4	2023-01-16
11285879	108A	2023-01-09 @ 11:00 am	2023-01-12 @ 9:00 am	0.8 ± 0.4	2023-01-16
11285880	108B	2023-01-09 @ 11:00 am	2023-01-12 @ 9:00 am	1.1 ± 0.4	2023-01-16
11285883	110A	2023-01-09 @ 12:00 pm	2023-01-12 @ 9:00 am	0.6 ± 0.4	2023-01-16
11285893	110B	2023-01-09 @ 12:00 pm	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11285884	110C	2023-01-09 @ 12:00 pm	2023-01-12 @ 9:00 am	0.5 ± 0.4	2023-01-16
11285837	112	2023-01-09 @ 9:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11285830	116	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	0.7 ± 0.4	2023-01-16
11285824	116A	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11285818	116A	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	0.5 ± 0.4	2023-01-16

Radon test result report for: QUINCE ORCHARD HS

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11285843	117	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11285822	118	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11285838	118A	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	0.7 ± 0.4	2023-01-16
11285817	119	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	0.8 ± 0.4	2023-01-16
11285809	119	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11285823	119B	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	0.8 ± 0.4	2023-01-16
11285845	119E	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	0.6 ± 0.4	2023-01-16
11285831	119F	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	0.7 ± 0.4	2023-01-16
11285801	119G	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	0.9 ± 0.4	2023-01-16
11285816	119GA	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	1.1 ± 0.4	2023-01-16
11285825	120	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11285846	120	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11284869	120A	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11284871	121	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11284870	122	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	0.6 ± 0.4	2023-01-16
11284868	122B	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11285815	124	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11284866	125	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11285839	125A	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	0.9 ± 0.3	2023-01-16
11285832	125A	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	0.6 ± 0.4	2023-01-16
11285852	126	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	0.6 ± 0.4	2023-01-16
11285834	128	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	0.5 ± 0.3	2023-01-16
11285853	129	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	< 0.3	2023-01-16
11285854	130	2023-01-09 @ 10:00 am	2023-01-12 @ 9:00 am	0.8 ± 0.4	2023-01-16
11285840	131	2023-01-09 @ 10:00 am	2023-01-12 @ 10:00 am	1.0 ± 0.3	2023-01-16
11285841	132	2023-01-09 @ 10:00 am	2023-01-12 @ 10:00 am	< 0.3	2023-01-16
11285842	133	2023-01-09 @ 10:00 am	2023-01-12 @ 10:00 am	0.6 ± 0.3	2023-01-16
11285826	134B	2023-01-09 @ 10:00 am	2023-01-12 @ 10:00 am	1.1 ± 0.4	2023-01-16
11285851	134B	2023-01-09 @ 10:00 am	2023-01-12 @ 10:00 am	0.8 ± 0.4	2023-01-16
11285855	134C	2023-01-09 @ 11:00 am	2023-01-12 @ 10:00 am	< 0.3	2023-01-16
11285847	134D	2023-01-09 @ 10:00 am	2023-01-12 @ 10:00 am	< 0.3	2023-01-16
11285848	134D	2023-01-09 @ 10:00 am	2023-01-12 @ 10:00 am	1.0 ± 0.4	2023-01-16
11285863	138	2023-01-09 @ 11:00 am	2023-01-12 @ 10:00 am	0.7 ± 0.4	2023-01-16
11285869	140	2023-01-09 @ 11:00 am	2023-01-12 @ 10:00 am	< 0.3	2023-01-16
11285864	140	2023-01-09 @ 11:00 am	2023-01-12 @ 10:00 am	< 0.3	2023-01-16
11285861	141	2023-01-09 @ 11:00 am	2023-01-12 @ 10:00 am	0.7 ± 0.4	2023-01-16
11285860	143	2023-01-09 @ 11:00 am	2023-01-12 @ 10:00 am	< 0.3	2023-01-16

Radon test result report for: QUINCE ORCHARD HS

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11285859	144	2023-01-09 @ 11:00 am	2023-01-12 @ 10:00 am	< 0.3	2023-01-16
11285871	145	2023-01-09 @ 11:00 am	2023-01-12 @ 10:00 am	1.1 ± 0.4	2023-01-16
11285870	148	2023-01-09 @ 11:00 am	2023-01-12 @ 10:00 am	< 0.3	2023-01-16
11285872	148	2023-01-09 @ 11:00 am	2023-01-12 @ 10:00 am	< 0.3	2023-01-16
11284867	149	2023-01-09 @ 11:00 am	2023-01-12 @ 10:00 am	1.0 ± 0.3	2023-01-16
11285857	149	2023-01-09 @ 11:00 am	2023-01-12 @ 10:00 am	0.9 ± 0.4	2023-01-16
11284865	150	2023-01-09 @ 11:00 am	2023-01-12 @ 10:00 am	0.6 ± 0.4	2023-01-16
11285867	151	2023-01-09 @ 11:00 am	2023-01-12 @ 10:00 am	0.9 ± 0.4	2023-01-16
11285858	152	2023-01-09 @ 11:00 am	2023-01-12 @ 10:00 am	0.7 ± 0.3	2023-01-16
11285858	152	2023-01-09 @ 11:00 am	2023-01-12 @ 10:00 am	0.7 ± 0.3	2023-01-16
11285849	153	2023-01-09 @ 11:00 am	2023-01-12 @ 10:00 am	1.1 ± 0.4	2023-01-16
11285850	154	2023-01-09 @ 11:00 am	2023-01-12 @ 10:00 am	0.8 ± 0.4	2023-01-16
11285806	200	2023-01-09 @ 9:00 am	2023-01-12 @ 8:00 am	< 0.3	2023-01-16
11285820	200D	2023-01-09 @ 9:00 am	2023-01-12 @ 8:00 am	0.5 ± 0.4	2023-01-16
11285821	200F	2023-01-09 @ 9:00 am	2023-01-12 @ 8:00 am	< 0.3	2023-01-16
11285827	206	2023-01-09 @ 9:00 am	2023-01-12 @ 8:00 am	< 0.3	2023-01-16
11285811	206	2023-01-09 @ 9:00 am	2023-01-12 @ 8:00 am	0.6 ± 0.3	2023-01-16
11285829	207	2023-01-09 @ 9:00 am	2023-01-12 @ 8:00 am	< 0.3	2023-01-16
11285819	207	2023-01-09 @ 9:00 am	2023-01-12 @ 8:00 am	1.0 ± 0.4	2023-01-16
11285828	207	2023-01-09 @ 9:00 am	2023-01-12 @ 8:00 am	0.5 ± 0.4	2023-01-16
11285812	214	2023-01-09 @ 9:00 am	2023-01-12 @ 8:00 am	< 0.3	2023-01-16
11285813	214	2023-01-09 @ 9:00 am	2023-01-12 @ 8:00 am	< 0.3	2023-01-16
11285805	217	2023-01-09 @ 9:00 am	2023-01-12 @ 8:00 am	0.7 ± 0.4	2023-01-16
11285804	219	2023-01-09 @ 9:00 am	2023-01-12 @ 8:00 am	< 0.3	2023-01-16
11284861	256	2023-01-09 @ 9:00 am	2023-01-12 @ 8:00 am	< 0.3	2023-01-16
11285836	259	2023-01-09 @ 9:00 am	2023-01-12 @ 8:00 am	< 0.3	2023-01-16
11285891	301	2023-01-09 @ 12:00 pm	2023-01-12 @ 10:00 am	0.7 ± 0.4	2023-01-16
11285856	AUDITORIUM	2023-01-09 @ 11:00 am	2023-01-12 @ 10:00 am	0.7 ± 0.3	2023-01-16
11285862	AUDITORIUM	2023-01-09 @ 11:00 am	2023-01-12 @ 10:00 am	0.6 ± 0.3	2023-01-16
11285833	DIRECTOR OFFICE	2023-01-09 @ 10:00 am	2023-01-12 @ 10:00 am	1.8 ± 0.4	2023-01-16
11285803	KITCHEN OFFICE	2023-01-09 @ 9:00 am	2023-01-12 @ 8:00 am	1.3 ± 0.4	2023-01-16
11285810	STAGE	2023-01-09 @ 11:00 am	2023-01-12 @ 10:00 am	0.9 ± 0.4	2023-01-16
11284846	STAGE	2023-01-09 @ 11:00 am	2023-01-12 @ 10:00 am	0.7 ± 0.4	2023-01-16

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KC / TECHNOLOGIES	Job Number 208343
NOMINAL Conditions: Radon Conc 34.7	pCi/L Rel. Hum 49.4 % Temp. 69.6 F
Date Start: 12/24/22 Date Stop: 12/27/2	Date Start: Date Stop:
	Time Start: Time Stop:
Device No.'s (5) CHAR BAGS -	Device No.'s:
THRU 11285103	
By Ceff	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = $7 \mu R/h$ Elevation = 820 ft

December 29, 2022

** LABORATORY ANALYSIS REPORT **

Radon test result report for:
OFFICE
MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11285110	SK1	2022-12-24 @ 8:00 am	2022-12-27 @ 8:00 am	31.7 ± 2.5	2022-12-29
11285101	SK2	2022-12-24 @ 8:00 am	2022-12-27 @ 8:00 am	30.1 ± 2.4	2022-12-29
11285103	SK3	2022-12-24 @ 8:00 am	2022-12-27 @ 8:00 am	34.0 ± 2.7	2022-12-29
11285102	SK4	2022-12-24 @ 8:00 am	2022-12-27 @ 8:00 am	30.9 ± 2.5	2022-12-29
11285109	SK5	2022-12-24 @ 8:00 am	2022-12-27 @ 8:00 am	32.0 ± 2.6	2022-12-29



Engineers • Planners • Scientists • Construction Managers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon – Week 1 January Schools

Name of Schools:

- 1. Diamond ES
- 2. Lakelands Park MS
- 3. Quince Orchard HS
- 4. Facilities Maintenance Depot Building A MCPS
- 5. Facilities Maintenance Depot Building B MCPS
- 6. Food and Nutrition Services
- 7. Hadley Farms
- 8. Goshen ES
- 9. Forest Knolls ES

	Date	Initials
Radon Test Kits Deployed	01/09/2023	BMM
Radon Test Kits Collected	01/12/2023	18MM
Radon Test Kits Shipped to Lab*	01/12/2023	BMM
Radon Test Kits Received by Lab*	01/17/2023	BMM

^{*}All samples sent to Air Check, Inc., 2 Saber Way, Ward Hill, MA 01835



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

MCPS RADON TESTING - EXECUTIVE SUMMARY

Site Name	Quince Orchard High School	
Date of Report	2/28/2020	
Round of Testing	Initial	
	Follow-up	
	Post Remediation	
	2 year testing	
	5 year testing	
	HVAC Upgrade	
	Window Replacement	
	New Addition	
	New Facility	
# of Rooms Tested	3	
# Rooms ≥4.0 pCi/L	0	
Lowest Value	<0.3 pCi/L	
Highest Value	1 pCi/L	

Project Status

Current Project Status at this time: Retesting completed; no further action



ENGINEERS . PLANNERS . SCIENTISTS . CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD . SPARKS, MD 21152 . 410-316-7800 . (FAX) 410-316-7935

2/28/2020

Mr. Richard Cox, MS
Team Leader
Montgomery County Public Schools
Division of Maintenance
Gaithersburg, Maryland 20879

Re: Radon Testing Services

KCI Job #1214634188

Location: Quince Orchard High School 15800 Quince Orchard Road Gaithersburg, Maryland 20878

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools pursuant to completing a "short-term" 3-day radon test for the Quince Orchard High School, located at 15800 Quince Orchard Road in Gaithersburg, Maryland 20878 (subject site).

SCOPE OF SERVICES

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #111004 RT) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.montgomer

KCI visited the site on 2/4/2020 and deployed six (6) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance.

KCI sampled the following locations during this follow-up test:

1. Rooms with missing test kits from the December 2019 testing period (i.e. test kit was deployed but not recovered),

- 2. Rooms with invalidated test kits from the December 2019 testing period (e.g. an open window in the room or disturbed test kit),
- 3. Rooms which were locked/inaccessible during the December 2019 testing period,
- 4. Rooms with elevated December 2019 results (i.e. \geq 3.5 piC/L),
- 5. Rooms previously tested for radon but not tested in December 2019, and
- 6. Additional rooms that require testing (if applicable.)

A floor plan map of the building with the test locations is included as Appendix A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted six (6) test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner, Inc. prior to being returned to the laboratory for analysis.

KCI returned to the site on 2/7/2020 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Aircheck, Inc. for analysis by gamma-ray spectroscopy. Aircheck, Inc. is a NRSB certified analytical laboratory for radon analysis (certification #ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

EVALUATION OF TESTING CONDITIONS

These tests represent:

• Follow-up to initial testing.

These tests were conducted to:

• Evaluate radon concentrations at the facility.

According to AARST, *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate low temperatures ranged from the mid-30s to the low-50s; and high temperatures ranged from the upper-40s to the mid-60s. Maximum sustained winds ranged from 13-21 miles per hour. Average humidity was approximately 76%. A total of 1.09 Inches of rain were recorded during the testing period. The weather conditions during the testing period may have resulted in atypical radon test results for this facility.

RESULTS

The sampling locations and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). Follow-up sampling locations and associated test kit identification numbers and relevant field observations are listed on Table 3 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	None	N/A
≤4.0 piC/L	See Attachment B	See Attachment B

Quality Control Samples			
Results of Blank Canisters:	The office blanks, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L.		
Adequate Laboratory Precision?	Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved.		
Spike Sample Analysis:	The Spike sample analysis results indicate the laboratory is operating within statistical control limits.		

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at 410-316-7800.

Sincerely,

Mr. Tyler P. McCleaf Radon Measurement Provider KCI Technologies, Inc.

Attachments

A- Floor Plan with Test Locations

B - Tables 1-3, Radon Test Summary Spreadsheets

C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

Floor Plan Legend

- X-Sample Location (in red)
- X- Previous Sample Location
- 1- Not Samled; No Ground Contact
- 2- Not Samled; Unoccupied (e.g. Storage, Mechanical)
- 3- Not Samled; High Humidity/Moisture
- 4- Not Samled; Bathroom/Hallway

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Chek, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

QC- Quality Control

Table 1- Radon Testing Results			
Q	uince Orchard High Scho	ol	
Test	: Period: 02/04/20-02/07	7/20	
Kit Number	Room / Area	Result	
9348542	124	0.5	
9348521	124	<0.3	
9348541	339	<0.3	
9348520	KITCHEN OFFICE	1	
9334909	OFFICE BLANK	<0.3	
9334910	OFFICE BLANK	<0.3	

Table 2- Radon Testing Results					
	Quince Orchard High School				
	Test Period: 02/	04/20-02/07/20			
Kit Number	QC Type	Room / Area	Result		
9348521	FB	124	<0.3		
9334902	TRANSIT BLANK	NA	<0.3		

ATTACHMENT C

Laboratory Analytical Results

** LABORATORY ANALYSIS REPORT **

Radon test result report for: QUINCE ORCHARD HS 125

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
9348542	124	2020-02-04 @ 12:00 p	m 2020-02-07 @ 11:00 am	0.5 ± 0.3	2020-02-11
9348521	124	2020-02-04 @ 12:00 p	m 2020-02-07 @ 11:00 am	< 0.3	2020-02-11
9348541	339	2020-02-04 @ 12:00 p	m 2020-02-07 @ 11:00 am	< 0.3	2020-02-11
9348520	KITCHEN OFFICE	2020-02-04 @ 12:00 p	m 2020-02-07 @ 10:00 am	1.0 ± 0.3	2020-02-11

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI Technolog	gies, Inc.	Job Number 194523	_
NOMINAL Conditions: Radon Conc 45.8	,		F
Date Start: 2/21/20 Date Stop: 2/24/2	20 Date Start:	Date Stop:	
Time Start: Q745 Time Stop: Q743	Time Start:	Time Stop:	
Device No.'s: (9) Char Bags-	Device No.'s:_		
9341725 thru 9341733			
52 Ceft		1	
Date Start: Date Stop:	Date Start:	Date Stop:	
Time Start: Time Stop:	Time Start:	Time Stop:	
Device No.'s:	Device No.'s:	'se	
22 25			
Date Start: Date Stop:	Date Start:	Date Stop:	
Time Start: Time Stop:	Time Start:	Time Stop:	
Device No.'s:	Device No.'s:		
		φ.	

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = $7 \mu R/h$ Elevation = 820 ft

** LABORATORY ANALYSIS REPORT **

Radon test result report for:

MCPS - Spike Sample Lab Results. Measured values are satisfactory, i.e., within \pm 25% of the chamber's reference value (25.7 pCi/L).

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
9341725	N/A	2020-02-21 @ 8:00 a	am 2020-02-24 @ 8:00 am	26.9 ± 1.6	2020-02-26
9341730	N/A	2020-02-21 @ 8:00 a	am 2020-02-24 @ 8:00 am	26.1 ± 1.6	2020-02-26
9341728	N/A	2020-02-21 @ 8:00 a	am 2020-02-24 @ 8:00 am	26.9 ± 1.6	2020-02-26
9341726	N/A	2020-02-21 @ 8:00 a	am 2020-02-24 @ 8:00 am	25.8 ± 1.5	2020-02-26
9341731	N/A	2020-02-21 @ 8:00 a	am 2020-02-24 @ 8:00 am	25.1 ± 1.5	2020-02-26
9341729	N/A	2020-02-21 @ 8:00 a	am 2020-02-24 @ 8:00 am	26.2 ± 1.6	2020-02-26
9341727	N/A	2020-02-21 @ 8:00 a	am 2020-02-24 @ 8:00 am	27.2 ± 1.6	2020-02-26
9341732	N/A	2020-02-21 @ 8:00 a	am 2020-02-24 @ 8:00 am	27.3 ± 1.6	2020-02-26



Engineers • Planners • Scientists • Construction Managers

Corporate Office: 936 Ridgebrook road • Sparks, Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon 2019 Week 1 Retesting

Name of Schools:

- 1. Belmont E.S.
- 2. Clarksburg H.S.
- 3. Damascus E.S.
- 4. Damascus H.S.
- 5. DuFief E.S.
- 6. Fields Road E.S.
- 7. Gaithersburg E.S.
- 8. McAuliffe E.S.
- 9. Quince Orchard H.S.
- 10. Snowden Farms E.S.
- 11. South Lake E.S.
- 12. Stone Mill E.S.
- 13. Travilah ES
- 14. Watkins Mill ES
- 15. Whitman H.S.

	Date	Initials
Radon Test Kits Deployed	02/03/20 to 02/04/20	m
Radon Test Kits Collected	02/06/20 to 02/07/20	m
Radon Test Kits Shipped to Lab*	02/07/20	- m
Radon Test Kits Received by Lab*	02/10/20	7m

^{*}All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

MCPS RADON TESTING - EXECUTIVE SUMMARY

Site Name	Quince Orchard High School
Date of Report	1/28/2020
Round of Testing	Initial
	Follow-up
	Post Remediation
	2 year testing
	5 year testing
	HVAC Upgrade
	Window Replacement
	New Addition
	New Facility
# of Rooms Tested	81
# Rooms ≥4.0 pCi/L	0
Lowest Value	<0.3 pCi/L
Highest Value	1.9 pCi/L

Project Status

Current Project Status at this time: Testing Complete; missing/compromised tests to be sampled.



936 RIDGEBROOK ROAD . SPARKS, MD 21152 . 410-316-7800 . (FAX) 410-316-7935

1/28/2020

Mr. Richard Cox, MS Environmental Team Leader Montgomery County Public Schools Division of Maintenance Gaithersburg, Maryland 20879

Re: Radon Testing Services

KCI Job #12146341126

Location: Quince Orchard High School 15800 Quince Orchard Road Gaithersburg, Maryland 20878

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools pursuant to completing a "short-term" 3-day radon test for the Quince Orchard High School, located at 15800 Quince Orchard Road in Gaithersburg, Maryland 20878 (subject site).

SCOPE OF SERVICES

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Proficiency Program (NRPP) Radon Measurement Specialist (certification #111004 RT) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from https://www.montgomeryschoolsmd.org/departments/facilities/maintenance/default.aspx?id=458858 or https://www.montgomeryschoolsmd.org/departments/facilities/maintenance/default.aspx?id=458858

KCI visited the site on 12/10/2019 and deployed ninety-seven (97) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance.

A floor plan map of the building with the test locations is included as Appendix A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted sixty (60) test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner, Inc. prior to being returned to the laboratory for analysis.

KCI returned to the site on 12/13/2019 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Aircheck, Inc. for analysis by gamma-ray spectroscopy. Aircheck, Inc. is a NRSB certified analytical laboratory for radon analysis (certification #ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

EVALUATION OF TESTING CONDITIONS

These tests represent:

• Follow-up to initial testing.

These tests were conducted to:

• Evaluate radon concentrations at the facility.

According to AARST, *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- · Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate low temperatures were in the upper-30s and high temperatures ranged from the upper-30s to the mid-50s. Maximum sustained winds ranged from 7-21 miles per hour. Average humidity was around 75%. 0.52 inches of precipitation (rain) was recorded during the testing period.

RESULTS

The sampling locations and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). Sampling locations and associated test kit identification numbers and relevant field observations are listed on Table 3 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	None	N/A
≤4.0 piC/L	See Attachment B	See Attachment B

Quality Control Samples				
Results of Blank Canisters:	The office blanks, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L.			
Adequate Laboratory Precision?	Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved.			
Spike Sample Analysis:	The Spike sample analysis results indicate the laboratory is operating within statistical control limits.			

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at 410-316-7800.

Sincerely,

Mr. Tyler P. McCleaf Radon Measurement Provider 111004 RT

KCI Technologies, Inc.

Attachments:

A- Floor Plan with Test Locations

B - Tables 1-3, Radon Test Summary Spreadsheets

C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Chek, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

QC- Quality Control

Table 1- Radon Testing Results
Quince Orchard High School
Test Period: 12/9/2019-12/12/2019

167. 1		
Kit Number	Room / Area	Result
9334520	129	< 0.3
9334521	130	< 0.3
9334539	207	< 0.3
9334541	301	< 0.3
9334553	131	< 0.3
9334554	132	< 0.3
9334560	152	0.5
9334561	154	0.6
9334563	138	< 0.3
9334564	AUD	< 0.3
9334565	145	< 0.3
9334566	133	0.6
9334567	AUD	8.0
9334568	145	< 0.3
9334570	149	0.6
9334571	148	0.7
9334572	153	0.7
9334573	150	< 0.3
9334574	151	< 0.3
9334575	203	< 0.3
9334577	256	< 0.3
9334578	256	< 0.3
9334581	AUD OFF	1.9
9334582	141	< 0.3
9334586	206	< 0.3
9334587	145	0.8
9334588	144	< 0.3
9334589	143	< 0.3
9334590	140	< 0.3
9334592	207	< 0.3
9334595	210	< 0.3
9334596	206	< 0.3
9334600	AUD OFF	1.8
9334627	117	< 0.3
9334629	122	< 0.3
9334631	117A	< 0.3
9334632	125	< 0.3
9334634	124	MISSING
9334637	128	< 0.3
9334638	126	< 0.3
9334641	105J	< 0.3
9334642	105	< 0.3
9334646	105H	< 0.3
9334647	105G	< 0.3
9334648	105L	< 0.3
9334649	104B	0.6
9334650	108B	0.8
9334651	110B	< 0.3
9334652	110A	< 0.3
9334653	105M	0.6
555.000		5.0

9334654	104A	0.5
9334655	119BA	1.4
9334656	118	< 0.3
9334657	118A	< 0.3
9334658	123B	< 0.3
9334659	119F	< 0.3
9334660	119G	< 0.3
9334661	119B	0.6
9334662	119E	< 0.3
9334663	119BA	1.4
9334664	125A	< 0.3
9334665	116	< 0.3
9334666	119A	< 0.3
9334667	119	0.5
9334668	121	< 0.3
9334669	101	< 0.3
9334670	200A	< 0.3
9334670	200A 124	< 0.3
9334671	124 105D	
		< 0.3
9334673	200D	< 0.3
9334674	200B	< 0.3
9334675	MAIN OFFICE	< 0.3
9334676	ASST PRINCIPAL	< 0.3
9334677	200C	< 0.3
9334678	200K	< 0.3
9334679	200E	< 0.3
9334680	200F	< 0.3
9334681	103	< 0.3
9334682	200G	< 0.3
9334683	200G	< 0.3
9334684	105D	< 0.3
9334685	100	< 0.3
9334686	105C	< 0.3
9334687	102	< 0.3
9334688	217A	< 0.3
9334689	105K	< 0.3
9334690	124	< 0.3
9334691	1051	< 0.3
9334692	112	< 0.3
9334693	105E	< 0.3
9334694	105F	< 0.3
9334695	105L	< 0.3
9334696	106B	< 0.3
9334697	116	< 0.3
9334698	116	< 0.3
9334699	105D	< 0.3
9334700	105B	< 0.3
9334982	OFFICE BLANK	< 0.3

Table 2- Radon Testing Results						
	Quince Orchard High School					
	Test Period: 12/9/	/2019-12/12/2019				
Kit Number	QC Type	Room / Area	Result			
9334699	D	105D	<0.3			
9334648	D	105L	<0.3			
9334698	D	116	<0.3			
9334655	D	119BA	1.4			
9334671	D	124	<0.3			
9334634	FB	124	MISSING			
9334581	D	AUD OFF	1.9			
9334565	D	145	<0.3			
9334568	FB	145	<0.3			
9334577	D	256	<0.3			
9334850	TRANSIT BLANK	NA	< 0.3			
9334914	TRANSIT BLANK	NA	< 0.3			
9334916	TRANSIT BLANK	NA	< 0.3			
9334963	TRANSIT BLANK	NA	< 0.3			

Summary of Missed Locations					
Quince Orchard High School					
Test Period: 12/10/2019 - 12/13/2019					
Kit Number	Room/Area	Result			
	NA				

Summary of Missing, Compromised and >/= 4 piC/L Tests					
O	uince Orchard High School				
Test Period: 12/10/2019-12/13/2019					
Kit Number	Result				
9334634	*124/Field Blank	Missing			

Table Note:

^{*} Missing or Compromised Sample

ATTACHMENT C

Laboratory Analytical Results

Radon test result report for: QUIN ORCHARD HS MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9334685	100	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334669	101	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334687	102	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334681	103	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334654	104A	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	0.5 ± 0.3	2019-12-16
9334649	104B	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	0.6 ± 0.3	2019-12-16
9334642	105	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334700	105B	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334686	105C	2019-12-10 @ 11:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334684	105D	2019-12-10 @ 11:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334672	105D	2019-12-10 @ 11:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334699	105D	2019-12-10 @ 11:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334693	105E	2019-12-10 @ 11:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334694	105F	2019-12-10 @ 11:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334647	105G	2019-12-10 @ 11:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334646	105H	2019-12-10 @ 11:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334691	105I	2019-12-10 @ 11:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334641	105J	2019-12-10 @ 11:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334689	105K	2019-12-10 @ 11:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334648	105L	2019-12-10 @ 11:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334695	105L	2019-12-10 @ 11:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334653	105M	2019-12-10 @ 11:00 am	2019-12-13 @ 9:00 am	0.6 ± 0.3	2019-12-16
9334696	106B	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334650	108B	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	0.8 ± 0.3	2019-12-16
9334652	110A	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334651	110B	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334692	112	2019-12-10 @ 11:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334698	116	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334665	116	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334697	116	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334627	117	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334631	117A	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334656	118	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334657	118A	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334667	119	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	0.5 ± 0.3	2019-12-16
9334666	119A	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334661	119B	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	0.6 ± 0.3	2019-12-16
9334661	119B	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	0.6 ± 0.3	2019-12-16

Radon test result report for: QUIN ORCHARD HS MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9334655	119BA	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	1.4 ± 0.3	2019-12-16
9334663	119BA 119BA	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	1.4 ± 0.3 1.4 ± 0.3	2019-12-16
9334662	119 D A 119E	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334659	119E	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334660	119G	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334668	121	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334629	122	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334658	123B	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334690	124	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334634	124	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	???? UI	2019-12-16
9334671	124	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334632	125	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334664	125A	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334638	126	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334637	128	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334520	129	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334521	130	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334553	131	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334554	132	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334566	133	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	0.6 ± 0.3	2019-12-16
9334563	138	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334590	140	2019-12-10 @ 12:00 pm	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334582	141	2019-12-10 @ 12:00 pm	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334589	143	2019-12-10 @ 12:00 pm	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334588	144	2019-12-10 @ 12:00 pm	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334568	145	2019-12-10 @ 12:00 pm	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334565	145	2019-12-10 @ 12:00 pm	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334587	145	2019-12-10 @ 12:00 pm	2019-12-13 @ 10:00 am	0.8 ± 0.3	2019-12-16
9334571	148	2019-12-10 @ 12:00 pm	2019-12-13 @ 10:00 am	0.7 ± 0.3	2019-12-16
9334570	149	2019-12-10 @ 12:00 pm	2019-12-13 @ 10:00 am	0.6 ± 0.3	2019-12-16
9334573	150	2019-12-10 @ 12:00 pm	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334574	151	2019-12-10 @ 12:00 pm	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334560	152	2019-12-10 @ 12:00 pm	2019-12-13 @ 10:00 am	0.5 ± 0.3	2019-12-16
9334572	153	2019-12-10 @ 12:00 pm	2019-12-13 @ 10:00 am	0.7 ± 0.3	2019-12-16
9334561	154	2019-12-10 @ 12:00 pm	2019-12-13 @ 10:00 am	0.6 ± 0.3	2019-12-16
9334670	200A	2019-12-10 @ 10:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334674	200B	2019-12-10 @ 10:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16

Radon test result report for: QUIN ORCHARD HS MAIN

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
9334677	200C	2019-12-10 @ 10:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334673	200D	2019-12-10 @ 10:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334679	200E	2019-12-10 @ 11:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334680	200F	2019-12-10 @ 10:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334682	200G	2019-12-10 @ 11:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334683	200G	2019-12-10 @ 11:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334678	200K	2019-12-10 @ 10:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334575	203	2019-12-10 @ 12:00 pm	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334596	206	2019-12-10 @ 12:00 pm	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334586	206	2019-12-10 @ 12:00 pm	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334592	207	2019-12-10 @ 12:00 pm	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334539	207	2019-12-10 @ 12:00 pm	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334595	210	2019-12-10 @ 12:00 pm	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334688	217A	2019-12-10 @ 11:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334578	256	2019-12-10 @ 12:00 pm	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334577	256	2019-12-10 @ 12:00 pm	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334541	301	2019-12-10 @ 12:00 pm	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334676	ASS PRINCIPAL	2019-12-10 @ 10:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16
9334564	AUD	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16
9334567	AUD	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	0.8 ± 0.3	2019-12-16
9334581	AUD OFF	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	1.9 ± 0.3	2019-12-16
9334600	AUD OFF	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	1.8 ± 0.4	2019-12-16
9334675	MAIN OFFICE	2019-12-10 @ 10:00 am	2019-12-13 @ 9:00 am	< 0.3	2019-12-16

** LABORATORY ANALYSIS REPORT **

Radon test result report for: QUIN ORCHARD HS MAIN

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
9334626	120	2019-12-10 @ 11:00 am	2019-12-13 @ 10:00 am	< 0.3	2019-12-16

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI Technologi	es Inc.	Job Number <u>193475</u>
NOMINAL Conditions: Radon Conc 25.7	pCi/L Rel. Hum _	74.6 % Temp. 69.9
Date Start: 12/13/19 Date Stop: 12/16/19	Date Start:	Date Stop:
Time Start: 0806 Time Stop: 0806	Time Start:	Time Stop:
Device No.'s: (20) Chan. Bags-	Device No.'s:_	
9334502 +hnu 9334519, 9334314, 9334316, 9334517, 2334517, 9334519		
9334522 4nn 9334528 By		
Date Start: 12/13/19 Date Stop: 12/16/19	Date Start:	Date Stop:
Time Start: Ost acm Time Stop: 0811	Time Start:	Time Stop:
(Group 2) Device No.'s: (20) Chair. Boys-	Device No.'s:_	·\$
9334529 thno 9334538,		
9334542 thno 9334550		
133		
Date Start: 12/13/19 Date Stop: 12/16/19	Date Start:	Date Stop:
Time Start: 0816 Time Stop: 0816	Time Start:	Time Stop:
(Gray 3) Device No.'s: (20) Char. Bags - 9334551, 9334554, 9334562,	Device No.'s:	
9334355 +hno 9334559, 9334369, 9334576, 9334579,		-
9334580, 9334583, 9334584		
9334597, 9334598, 9334599 Ba		

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = 7 μ R/h Elevation = 820 ft

Radon test result report for:

MCPS - Spike Sample Lab Results. Measured values are satisfactory, i.e., within \pm 25% of the chamber's reference value (25.7 pCi/L).

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9334583	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.3 ± 1.4	2019-12-18
9334529	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.3 ± 1.5	2019-12-18
9334597	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.8 ± 1.4	2019-12-18
9334534	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.3 ± 1.4	2019-12-18
9334540	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.9 ± 1.4	2019-12-18
9334546	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.9 ± 1.5	2019-12-18
9334551	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.3 ± 1.4	2019-12-18
9334558	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.6 ± 1.4	2019-12-18
9334579	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.6 ± 1.4	2019-12-18
9334593	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.3 ± 1.4	2019-12-18
9334532	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.6 ± 1.4	2019-12-18
9334537	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.8 ± 1.4	2019-12-18
9334544	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.5 ± 1.4	2019-12-18
9334549	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.4 ± 1.5	2019-12-18
9334556	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.1 ± 1.4	2019-12-18
9334569	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.7 ± 1.4	2019-12-18
9334584	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.4 ± 1.5	2019-12-18
9334530	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.6 ± 1.4	2019-12-18
9334598	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.7 ± 1.4	2019-12-18
9334535	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.0 ± 1.4	2019-12-18
9334542	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.7 ± 1.4	2019-12-18
9334547	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	25.2 ± 1.5	2019-12-18
9334552	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.2 ± 1.4	2019-12-18
9334559	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.1 ± 1.4	2019-12-18
9334580	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.1 ± 1.4	2019-12-18
9334594	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.1 ± 1.4	2019-12-18
9334533	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.3 ± 1.5	2019-12-18
9334538	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.6 ± 1.5	2019-12-18
9334545	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.0 ± 1.4	2019-12-18
9334550	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.1 ± 1.4	2019-12-18
9334557	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.6 ± 1.5	2019-12-18
9334576	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.3 ± 1.4	2019-12-18
9334591	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.7 ± 1.4	2019-12-18
9334531	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.3 ± 1.5	2019-12-18
9334599	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.8 ± 1.4	2019-12-18
9334536	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.4 ± 1.5	2019-12-18
9334543	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.4 ± 1.5	2019-12-18

** LABORATORY ANALYSIS REPORT **

Radon test result report for:

N/A

Kit # Ro	oom Id	Started	Ended	pCi/L	Analyzed
9334548	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.0 ± 1.4	2019-12-18
9334555	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.4 ± 1.4	2019-12-18
9334562	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.5 ± 1.4	2019-12-18

Radon test result report for: S N/A

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
9334505	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.5 ± 1.5	2019-12-18
9334510	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.4 ± 1.5	2019-12-18
9334522	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.9 ± 1.4	2019-12-18
9334527	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	22.6 ± 1.4	2019-12-18
9334503	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.6 ± 1.4	2019-12-18
9334508	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.7 ± 1.5	2019-12-18
9334517	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.5 ± 1.4	2019-12-18
9334525	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.8 ± 1.4	2019-12-18
9334506	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.3 ± 1.5	2019-12-18
9334514	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.5 ± 1.5	2019-12-18
9334523	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.6 ± 1.4	2019-12-18
9334528	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.8 ± 1.4	2019-12-18
9334504	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.8 ± 1.4	2019-12-18
9334509	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.5 ± 1.4	2019-12-18
9334519	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.1 ± 1.4	2019-12-18
9334526	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.3 ± 1.4	2019-12-18
9334502	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	23.7 ± 1.4	2019-12-18
9334507	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.7 ± 1.5	2019-12-18
9334516	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	22.2 ± 1.3	2019-12-18
9334524	N/A	2019-12-13 @ 8:00 am	2019-12-16 @ 8:00 am	24.6 ± 1.5	2019-12-18



Engineers • Planners • Scientists • Construction Managers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon 2019 Week 1

Name of Schools:

 Baker M 	1.S.	
-----------------------------	------	--

2. Belmont E.S.

3. Clarksburg E.S.

4. Clarksburg H.S.

5. Clearspring E.S.

6. Damascus E.S.

7 Damasaus II C

7. Damascus H.S.

8. Dufief E.S.

9. Fields Road E.S.

10. Gaithersburg E.S.

11. Germantown E.S.

12. Great Seneca Creek E.S.

13. Jones Lane E.S.

14. Lake Seneca E.S.

15. McAuliffe E.S.

16. Quince Orchard H.S.

17. Rosa Parks M.S.

18. Snowden Farm E.S.

19. South Lake E.S.

20. Stone Mill E.S.

21. Travilah E.S.

22. Watkins Mill E.S.

23. Watkins Mill H.S.

24. Whitman H.S.

	Date	Initials
Radon Test Kits Deployed	12/09/19 to 12/10/19	TM
Radon Test Kits Collected	12/12/19 to 12/13/19	m
Radon Test Kits Shipped to Lab*	12/13/19	The
Radon Test Kits Received by Lab*	12/16/19	Th

^{*}All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759



MONTGOMERY COUNTY PUBLIC SCHOOLS RADON TESTING

Executive Summary: Quince Orchard High School

15800 Quince Orchard Road Gaithersburg, MD 20878

Date of Test Report:	3/20/2019
Round of Testing:	Initial
	Follow-up
	Post Remediation
	2 Year Testing
	5 Year Testing
	HVAC Upgrade
	Window Replacement
	New Addition
	New Facility
# of Rooms Tested:	8
# of Rooms ≥ 4.0 pCi/L:	0
Low Value:	<0.4
High Value:	1.0

Project Status

Retesting completed: No further action at this time.



March 20, 2019

Mr. Richard Cox Indoor Air Quality Team Leader Montgomery County Public Schools 850 Hungerford Drive Rockville, MD 20850

Re: Radon Testing Services

Location: Quince Orchard High School

15800 Quince Orchard Road Gaithersburg, MD 20878

Dear Mr. Cox:

Intertek-PSI (PSI) is pleased to submit the following report to the Montgomery County Public Schools (MCPS) for completion of a "short-term" 3-day radon test for Quince Orchard High School, located at 15800 Quince Orchard Road, Gaithersburg, MD 20878 (subject site).

Scope of Services:

PSI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. PSI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS007) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.montgomerycoun

PSI visited the site on February 25, 2019 and deployed eight (8) activated charcoal (AC) radon test kit. PSI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. PSI returned to the site on February 28, 2019 to retrieve the radon sampling test kit. A floor plan map of the building with the test location is included as Attachment A of this report.

PSI shipped all radon tests via overnight delivery to AccuStar Labs for analysis by gamma-ray spectroscopy. Accustar Labs is a NRSB certified analytical laboratory for radon analysis located at 929 Mount Zion Road, Lebanon, Pennsylvania (certification # ARL0007).

Evaluation of Testing Conditions:

The operating condition that represents the greatest amount of significantly occupied time for this building is; heating active, with outdoor temperature averages ≤ 65°F.

PSI concludes that the test period reasonably represents normal conditions when the building is significantly occupied. Clear characterization of the radon hazard is most likely to be observed under this normal operating condition. Based on the evaluation of test conditions, this test should reasonably characterize radon hazards.



PSI also conducted observations of field conditions which could affect the results of the test and compiled weather data for the testing period. PSI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

Results:

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥ 4.0 pCi/L	None	NA
≤ 4.0 pCi/L	See Attachment B	

Notes:

D - Duplicate Sample

The office blank and lab transit blanks had test results of less than the laboratory detection limit of 0.4 pCi/L. Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C).

Laboratory results and exposure data for the spike samples are also included in Attachment C. Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (703) 698-9300.

Respectfully Submitted,

INTERTEK - PSI

Nand Kaushik, P.E.

Department Manager, Environmental Services

Nand.Kaushik@intertek.com

Non-April Fourth

Attachments: A – Floor Plan with Test Locations

B – Table 1 – Radon Test Summary Spreadsheet

C – Laboratory Analytical Results

ATTACHMENT B

Radon Test Summary Spreadsheet

	Radon Testing Results				
	Quince Orchard High School				
	Testing period: 2/25/19 - 2/28/19				
Kit Number	Kit Number Room / Area Result (pCi/L)				
3923419	118A	<0.4			
3923418	149	0.4			
3923417	151	<0.4			
3923412	216	<0.4			
3923415	246	0.5			
3923414	255	0.4			
3923413	258	<0.4			
3923411	Kitchen Office	1.0			

Table Notes:

- D Duplicate
- FB Field Blank
- OB Office Blank
- TB Transit Blank
- QC Quality Control

ATTACHMENT C

Laboratory Analytical Results



NRPP 105011 AL NRSB ARL0007 EPA Method #402-R-92-004 Charcoal Canister NRPP Device Code 6048 NRSB Device Code 10317

Laboratory Report for:

Property Tested: Project # 04481387-1

Intertek-PSI (VA)
2930 Eskridge Road
Fairfax VA 22031

MCPS Radon Survey Quince Orchard HS 15800 Quince Orchard Road Gaithersburg MD 20878

Log Device Number Number	Test Exposure Duration:	Area Tested	Result pCi/L
3220741 3923411 02/25/2019	1:00 pm 02/28/2019 1:00 pm	2nd floor Room Kitchen Office	1.0
3220742 3923413 02/25/2019	1:04 pm 02/28/2019 1:04 pm	2nd floor Room 258	< 0.4
3220743 3923414 02/25/2019	1:06 pm 02/28/2019 1:06 pm	2nd floor Room 255	0.4
3220744 3923415 02/25/2019	1:10 pm 02/28/2019 1:10 pm	2nd floor Room 246	0.5
3220745 3923412 02/25/2019	1:12 pm 02/28/2019 1:12 pm	2nd floor Room 216	< 0.4
3220746 3923417 02/25/2019	1:18 pm 02/28/2019 1:18 pm	1st floor Room 151	< 0.4
3220747 3923418 02/25/2019	1:22 pm 02/28/2019 1:22 pm	1st floor Room 149	0.4
3220748 3923419 02/25/2019	1:26 pm 02/28/2019 1:26 pm	1st floor Room 118A	< 0.4

Comment: A copy of this report was e-mailed to Intertek-PSI (VA)

Distributed by: Intertek-PSI (VA)

Date Received: 03/05/2019 Date Logged: 03/05/2019 Date Analyzed: 03/05/2019 Date Reported: 03/06/2019

Report Reviewed By: _

Disclaimer:

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



MONTGOMERY COUNTY PUBLIC SCHOOLS RADON TESTING

Executive Summary: Quince Orchard High School

15800 Quince Orchard Road Gaithersburg, MD 20878

Date of Test Report:	1/15/2019
Round of Testing:	Initial
	Follow-up
	Post Remediation
	2 Year Testing
	5 Year Testing
	HVAC Upgrade
	Window Replacement
	New Addition
	New Facility
# of Rooms Tested:	111
# of Rooms ≥ 4.0 pCi/L:	0
Low Value:	< 0.4
High Value:	1.5

Project Status

Initial testing complete: Missing or compromised samples need re-test.



January 15, 2019

Mr. Richard Cox Indoor Air Quality Team Leader Montgomery County Public Schools 850 Hungerford Drive Rockville, MD 20850

Re: Radon Testing Services

Location: Quince Orchard High School

15800 Quince Orchard Road Gaithersburg, MD 20878

Dear Mr. Cox:

Intertek-PSI (PSI) is pleased to submit the following report to the Montgomery County Public Schools (MCPS) for completion of a "short-term" 3-day radon test for Quince Orchard High School, located at 15800 Quince Orchard Road, Gaithersburg, MD 20878 (subject site).

Scope of Services:

PSI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. PSI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS007) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.montgomerycoun

PSI visited the site on December 04, 2018 and deployed one hundred-thirty (130) activated charcoal (AC) radon test kits. PSI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. PSI returned to the site on December 07, 2018 to retrieve the radon sampling test kits. A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, PSI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, PSI submitted ten (10) test kits to Bowser-Morner Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner Inc. prior to being returned to the laboratory for analysis.

PSI shipped all radon tests via overnight delivery to AccuStar Labs for analysis by gamma-ray spectroscopy. Accustar Labs is a NRSB certified analytical laboratory for radon analysis located at 929 Mount Zion Road, Lebanon, Pennsylvania (certification # ARL0007) and 2 Saber Way, Haverhill, Massachusetts (certification # ARL0017).



Evaluation of Testing Conditions:

The operating condition that represents the greatest amount of significantly occupied time for this building is; heating active, with outdoor temperature averages ≤ 65°F.

PSI concludes that the test period reasonably represents normal conditions when the building is significantly occupied. Clear characterization of the radon hazard is most likely to be observed under this normal operating condition. Based on the evaluation of test conditions, this test should reasonably characterize radon hazards.

PSI also conducted observations of field conditions which could affect the results of the test and compiled weather data for the testing period. PSI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

Results:

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥ 4.0 pCi/L	None	NA
≤ 4.0 pCi/L	See Attachment B	

Notes:

D - Duplicate Sample

The office blank and lab transit blanks had test results of less than the laboratory detection limit of 0.4 pCi/L. Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C).

Laboratory results and exposure data for the spike samples are also included in Attachment C. Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (703) 698-9300.



Respectfully Submitted,

INTERTEK-PSI

Nand Kaushik, P.E.

Department Manager, Environmental Services

Nand.Kaushik@intertek.com

Non-April Coulin

Attachments: A – Floor Plan with Test Locations

B – Table 1 – Radon Test Summary Spreadsheet

C – Laboratory Analytical Results

ATTACHMENT B

Radon Test Summary Spreadsheet

Radon Testing Results Quince Orchard Highschool Testing posied: 12/04/18, 12/07/18				
3926637	100	Result (pCi/L) < 0.4		
3926611	101	< 0.4		
3926612	102	< 0.4		
	103	< 0.4		
3926639 3926640	105	< 0.4		
3926518	104A	< 0.4		
3926519	104A 104C	< 0.4		
3926613	104C 105C	< 0.4		
3926615	105C	< 0.4		
3926614	105E	< 0.4		
3926616	105E	< 0.4		
		< 0.4		
3926618 3926617	105G 105H	< 0.4		
3926619	1051	< 0.4		
3926620	105J	< 0.4		
3926512	105K	< 0.4		
3926511	105L	< 0.4		
3926513	105M	< 0.4		
3926516	106B	0.5		
3926515	108B	0.4		
3926514	112	< 0.4		
3928372	116	0.5		
3928371	116A	< 0.4		
3928374	117	< 0.4		
3928375	118	< 0.4		
	118A (MISSED)			
3926561	119	< 0.4		
3928377	119B	0.5		
3926198	119BA	1.0		
3928380	119E	< 0.4		
3928379	119F	< 0.4		
3928378	119G	0.5		
3926200	120	< 0.4		
3926562	121	< 0.4		
3926564	121A	< 0.4		
3926563	121C	< 0.4		
3926565	122	< 0.4		
3926566	123B	< 0.4		
3926568	124	< 0.4		
3926591	124A	< 0.4		
3926569	125	< 0.4		
3926567	125A	< 0.4		
3926592	128	< 0.4		

Radon Testing Results Quince Orchard Highschool Testing period: 12/04/18 - 12/07/18				
3926593	129	< 0.4		
3926594	130	< 0.4		
3926595	131	< 0.4		
3926596	132	< 0.4		
3926597	133	< 0.4		
3926600	134B	0.6		
3926582	134C	0.8		
3926581	134D	0.7		
3926524	138	< 0.4		
3926525	140	< 0.4		
3926526	143	< 0.4		
3926527	143A	< 0.4		
3926528	143B	< 0.4		
3926530	144A	< 0.4		
3926529	144B	< 0.4		
3926631	145	0.4		
3926632	148	0.5		
	149 (MISSED)			
3926635	150	< 0.4		
	151 (MISSED)			
3926633	152	0.5		
3926634	153	0.4		
3926636	154	0.4		
	155 (INACCESSIBLE)			
3926641	200	< 0.4		
3926642	200A	< 0.4		
3926643	200B	< 0.4		
3926645	200C	< 0.4		
3926644	200D	< 0.4		
3926648	200E	< 0.4		
3926646	200F	< 0.4		
3926649	200G	< 0.4		
3926647	200K	< 0.4		
3928106	207	< 0.4		
3928109	209	< 0.4		
3926610	210	< 0.4		
	216 (INACCESSIBLE)			
3926521	217A	< 0.4		
3926522	217B	< 0.4		
3926523	217C	< 0.4		
3928337	218	< 0.4		
3928338	219	< 0.4		
3928339	220	< 0.4		

Radon Testing Results Quince Orchard Highschool Testing period: 12/04/18 - 12/07/18							
					Kit Number	Room / Area	Result (pCi/L)
					3928340	221	< 0.4
3926571	222	< 0.4					
3926573	223	< 0.4					
3926574	228G	< 0.4					
3926575	239	< 0.4					
	246 (INACCESSIBLE)						
3926589	247	< 0.4					
3926602	247C	< 0.4					
3926604	249	< 0.4					
3926605	254	< 0.4					
3926606	254D	< 0.4					
	255 (INACCESSIBLE)						
3926607	256	< 0.4					
	258 (INACCESSIBLE)						
3926608	259	0.4					
3926609	259	0.4					
3928334	308	< 0.4					
3926580	318	< 0.4					
3926579	325	< 0.4					
3926576	338	< 0.4					
3926577	339	< 0.4					
3926578	352	< 0.4					
3926584	Auditorium	0.4					
3928110	Cafeteria	< 0.4					
3926601	Computer Lab	< 0.4					
3928336	Kitchen	0.4					
	Kitchen Office (INACCESSIBLE)						
3928107	206 (Main Gym)	< 0.4					
3928108	206 (Main Gym)	< 0.4					
3926585	Media Center	< 0.4					
3926588	Media Center Office	< 0.4					
3926603	Production	< 0.4					
3928335	Serving Area	< 0.4					
3926583	Stage	0.6					
3926599	Theatre Office	1.5					
3926587	Workroom	< 0.4					

Radon Testing Results Quince Orchard Highschool Testing period: 12/04/18 - 12/07/18							
					Kit Number	QC Type	Result (pCi/L)
					3926638	100 (D)	< 0.4
3926520	104C (D)	< 0.4					
3928373	105J (D)	< 0.4					
3926517	106B (D)	0.5					
3928376	118 (D)	< 0.4					
3926199	119BA (D)	0.7					
3926570	125 (D)	< 0.4					
3926598	133 (D)	< 0.4					
3926650	200G (D)	< 0.4					
3926572	222 (D)	< 0.4					
3926590	247 (D)	< 0.4					
3926586	Media Center (D)	< 0.4					
3926708	Field Blank	< 0.4					
3926707	Field Blank	< 0.4					
3917553	Office Blank	< 0.4					
3927554	Transit Blank	< 0.4					

Table Notes:

- D Duplicate
- FB Field Blank
- OB Office Blank
- TB Transit Blank
- QC Quality Control

ATTACHMENT C

Laboratory Analytical Results



Laboratory Report for:

Property Tested: Project # 04481387-1

Intertek-PSI (VA)
2930 Eskridge Road
Fairfax VA 22031

MCPS Radon Survey
15800 Quince Orchard Road
Gaithersburg MD 20876

Log Number	Device Number		Test Expo	sure Duratio	on:	Area Tested		Result pCi/L
3202478	3926590	12/04/2018	5:07 pm	12/07/2018	4:25 pm	Floor Second Floor	Room 247 Duplicate	<0.4
3202479	3926641	12/04/2018	3:11 pm	12/07/2018	3:37 pm	Floor Second Floor	Room 200	< 0.4
3202480	3926642	12/04/2018	3:12 pm	12/07/2018	3:38 pm	Floor Second Floor	Room 200A	< 0.4
3202481	3926644	12/04/2018	3:14 pm	12/07/2018	3:40 pm	Floor Second Floor	Room 200D	< 0.4
3202482	3926645	12/04/2018	3:15 pm	12/07/2018	3:41 pm	Floor Second Floor	Room 200C	< 0.4
3202483	3926646	12/04/2018	3:16 pm	12/07/2018	12:00 am	Floor Second Floor	Room 200F	< 0.4
3202484	3926647	12/04/2018	3:17 pm	12/07/2018	3:43 pm	Floor Second Floor	Room 200K	< 0.4
3202485	3926648	12/04/2018	3:17 pm	12/07/2018	3:44 pm	Floor Second Floor	Room 200E	< 0.4
3202486	3926649	12/04/2018	3:19 pm	12/07/2018	3:45 pm	Floor Second Floor	Room 200G	< 0.4
3202487	3926650	12/04/2018	3:19 pm	12/07/2018	3:45 pm	Floor Second Floor	Room 200G Duplicate	< 0.4
3202488	3926521	12/04/2018	3:21 pm	12/07/2018	3:46 pm	Floor Second Floor	Room 217A	< 0.4

Comment: AMENDED REPORT on 12-19-18 and 1-7-19. Stop dates reflected as 12-7-18 for all. Device 3926590 amended to reflect correct device number.

Test Performed By: Lian Zadeng Distributed by: Intertek-PSI (VA)

Report Reviewed By: _

Report Approved By:

Disclaimer:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



Laboratory Report for:

Property Tested: Project # 04481387-1

Intertek-PSI (VA)
2930 Eskridge Road
Fairfax VA 22031

MCPS Radon Survey
15800 Quince Orchard Road
Gaithersburg MD 20876

Log Number	Device Number		Test Expo	sure Duratio	on:	Area Tested		Result pCi/L
3202489	3926522	12/04/2018	3:23 pm	12/07/2018	3:47 pm	Floor Second Floor	Room 217B	< 0.4
3202490	3926523	12/04/2018	3:22 pm	12/07/2018	3:49 pm	Floor Second Floor	Room 217C	< 0.4
3202491	3926524	12/04/2018	3:30 pm	12/07/2018	1:50 pm	Floor First Floor R	oom 138	< 0.4
3202492	3926525	12/04/2018	3:32 pm	12/07/2018	1:52 pm	Floor First Floor R	oom 140	< 0.4
3202493	3926526	12/04/2018	3:33 pm	12/07/2018	1:53 pm	Floor First Floor R	oom 143	< 0.4
3202494	3926527	12/04/2018	3:34 pm	12/07/2018	1:55 pm	Floor First Floor R	oom 143A	< 0.4
3202495	3926528	12/04/2018	3:36 pm	12/07/2018	1:58 pm	Floor First Floor R	oom 143B	< 0.4
3202496	3926529	12/04/2018	3:37 pm	12/07/2018	1:58 pm	Floor First Floor R	oom 144B	< 0.4
3202497	3926530	12/04/2018	3:38 pm	12/07/2018	1:59 pm	Floor First Floor R	oom 144A	< 0.4
3202498	3926631	12/04/2018	3:40 pm	12/07/2018	2:00 pm	Floor First Floor R	oom 145	0.4
3202499	3926632	12/04/2018	3:41 pm	12/07/2018	2:01 pm	Floor First Floor R	oom 148	0.5

Comment: AMENDED REPORT on 12-19-18 and 1-7-19. Stop dates reflected as 12-7-18 for all. Device 3926590 amended to reflect correct device number.

Test Performed By: Lian Zadeng Distributed by: Intertek-PSI (VA)

Report Reviewed By: _

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



Laboratory Report for:

Property Tested: Project # 04481387-1

Intertek-PSI (VA)
2930 Eskridge Road
Fairfax VA 22031

MCPS Radon Survey
15800 Quince Orchard Road
Gaithersburg MD 20876

Log Number	Device Number		Test Expo	sure Duratio	n:	Area Tested		Result pCi/L
3202500	3926633	12/04/2018	3:42 pm	12/07/2018	2:02 pm	Floor First Floor	Room 152	0.5
3202501	3926634	12/04/2018	3:43 pm	12/07/2018	2:03 pm	Floor First Floor	Room 153	0.4
3202502	3926635	12/04/2018	3:45 pm	12/07/2018	2:05 pm	Floor First Floor	Room 150	< 0.4
3202503	3926636	12/04/2018	3:46 pm	12/07/2018	2:06 pm	Floor First Floor	Room 154	0.4
3202504	3926637	12/04/2018	3:49 pm	12/07/2018	2:07 pm	Floor First Floor	Room 100	< 0.4
3202505	3926638	12/04/2018	3:49 pm	12/07/2018	2:07 pm	Floor First Floor	Room 100 Duplicate	< 0.4
3202506	3926639	12/04/2018	3:53 pm	12/07/2018	2:09 pm	Floor First Floor	Room 103	< 0.4
3202507	3926640	12/04/2018	3:52 pm	12/07/2018	2:10 pm	Floor First Floor	Room 105	< 0.4
3202508	3926612	12/04/2018	3:54 pm	12/07/2018	2:11 pm	Floor First Floor	Room 102	< 0.4
3202509	3926613	12/04/2018	3:55 pm	12/07/2018	2:14 pm	Floor First Floor	Room 105C	< 0.4
3202510	3926614	12/04/2018	3:56 pm	12/07/2018	2:15 pm	Floor First Floor	Room 105E	< 0.4

Comment: AMENDED REPORT on 12-19-18 and 1-7-19. Stop dates reflected as 12-7-18 for all. Device 3926590 amended to reflect correct device number.

Test Performed By: Lian Zadeng Distributed by: Intertek-PSI (VA)

Report Reviewed By: _

) James

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.

Report Approved By:



Laboratory Report for:

Property Tested: Project # 04481387-1

Intertek-PSI (VA)
2930 Eskridge Road
Fairfax VA 22031

MCPS Radon Survey
15800 Quince Orchard Road
Gaithersburg MD 20876

Log Number	Device Number		Test Expo	osure Duratio	n:	Area Tested		Result pCi/L
3202511	3926615	12/04/2018	3:56 pm	12/07/2018	2:16 pm	Floor First Floor	Room 105D	< 0.4
3202512	3926616	12/04/2018	3:57 pm	12/07/2018	2:17 pm	Floor First Floor	Room 105F	< 0.4
3202513	3926617	12/04/2018	3:58 pm	12/07/2018	2:17 pm	Floor First Floor	Room 105H	< 0.4
3202514	3926618	12/04/2018	3:59 pm	12/07/2018	2:18 pm	Floor First Floor	Room 105G	< 0.4
3202515	3926619	12/04/2018	4:00 pm	12/07/2018	2:19 pm	Floor First Floor	Room 105I	< 0.4
3202516	3926620	12/04/2018	4:02 pm	12/07/2018	2:20 pm	Floor First Floor	Room 105J	< 0.4
3202517	3928373	12/04/2018	4:02 pm	12/07/2018	2:20 pm	Floor First Floor	Room 105J Duplicate	< 0.4
3202518	3926511	12/04/2018	4:04 pm	12/07/2018	2:21 pm	Floor First Floor	Room 105L	< 0.4
3202519	3926512	12/04/2018	4:05 pm	12/07/2018	2:22 pm	Floor First Floor	Room 105K	< 0.4
3202520	3926513	12/04/2018	4:06 pm	12/07/2018	2:23 pm	Floor First Floor	Room 105M	< 0.4
3202521	3926514	12/04/2018	4:09 pm	12/07/2018	2:24 pm	Floor First Floor	Room 112	< 0.4

Comment: AMENDED REPORT on 12-19-18 and 1-7-19. Stop dates reflected as 12-7-18 for all. Device 3926590 amended to reflect correct device number.

Test Performed By: Lian Zadeng Distributed by: Intertek-PSI (VA)

Report Reviewed By: _

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



Laboratory Report for:

Property Tested: Project # 04481387-1

Intertek-PSI (VA)
2930 Eskridge Road
Fairfax VA 22031

MCPS Radon Survey
15800 Quince Orchard Road
Gaithersburg MD 20876

Log Number	Device Number		Test Expo	sure Duratio	n:	Area Tested		Result pCi/L
3202522	3926515	12/04/2018	4:11 pm	12/07/2018	2:24 pm	Floor First Floor	Room 108B	0.4
3202523	3926517	12/04/2018	4:13 pm	12/07/2018	2:30 pm	Floor First Floor	Room 106B Duplicate	0.5
3202524	3926518	12/04/2018	4:15 pm	12/07/2018	2:32 pm	Floor First Floor	Room 104A	< 0.4
3202525	3926519	12/04/2018	4:16 pm	12/07/2018	2:33 pm	Floor First Floor	Room 104C	< 0.4
3202526	3926520	12/04/2018	4:16 pm	12/07/2018	2:33 pm	Floor First Floor	Room 104C Duplicate	< 0.4
3202527	3928371	12/04/2018	4:18 pm	12/07/2018	2:35 pm	Floor First Floor	Room 116A	< 0.4
3202528	3928372	12/04/2018	4:19 pm	12/07/2018	2:35 pm	Floor First Floor	Room 116	0.5
3202529	3928374	12/04/2018	4:21 pm	12/07/2018	2:36 pm	Floor First Floor	Room 117	< 0.4
3202530	3928375	12/04/2018	4:22 pm	12/07/2018	2:37 pm	Floor First Floor	Room 118	< 0.4
3202531	3928376	12/04/2018	4:22 pm	12/07/2018	2:38 pm	Floor First Floor	Room 118 Duplicate	< 0.4
3202532	3928377	12/04/2018	4:25 pm	12/07/2018	2:39 pm	Floor First Floor	Room 119B	0.5

Comment: AMENDED REPORT on 12-19-18 and 1-7-19. Stop dates reflected as 12-7-18 for all. Device 3926590 amended to reflect correct device number.

Test Performed By: Lian Zadeng Distributed by: Intertek-PSI (VA)

Report Reviewed By: _

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



Laboratory Report for:

Property Tested: Project # 04481387-1

Intertek-PSI (VA)
2930 Eskridge Road
Fairfax VA 22031

MCPS Radon Survey
15800 Quince Orchard Road
Gaithersburg MD 20876

Log Number	Device Number		Test Expo	sure Duratio	on:	Area Tested		Result pCi/L
3202533	3928378	12/04/2018	4:26 pm	12/07/2018	2:41 pm	Floor First Floor	Room 119G	0.5
3202534	3928379	12/04/2018	4:27 pm	12/07/2018	2:41 pm	Floor First Floor	Room 119F	< 0.4
3202535	3928380	12/04/2018	4:28 pm	12/07/2018	2:45 pm	Floor First Floor	Room 119E	< 0.4
3202536	3926198	12/04/2018	4:30 pm	12/07/2018	2:46 pm	Floor First Floor	Room 119BA	1.0
3202537	3926199	12/04/2018	4:30 pm	12/07/2018	2:47 pm	Floor First Floor	Room 119BA Duplicate	0.7
3202538	3926200	12/04/2018	4:32 pm	12/07/2018	2:48 pm	Floor First Floor	Room 120	< 0.4
3202539	3926561	12/04/2018	4:33 pm	12/07/2018	2:48 pm	Floor First Floor	Room 119	< 0.4
3202540	3926562	12/04/2018	4:34 pm	12/07/2018	2:53 pm	Floor First Floor	Room 121	< 0.4
3202541	3926563	12/04/2018	4:35 pm	12/07/2018	2:55 pm	Floor First Floor	Room 121C	< 0.4
3202542	3926565	12/04/2018	4:38 pm	12/07/2018	2:57 pm	Floor First Floor	Room 122	< 0.4
3202543	3926566	12/04/2018	4:39 pm	12/07/2018	2:58 pm	Floor First Floor	Room 123B	< 0.4

Comment: AMENDED REPORT on 12-19-18 and 1-7-19. Stop dates reflected as 12-7-18 for all. Device 3926590 amended to reflect correct device number.

Test Performed By: Lian Zadeng Distributed by: Intertek-PSI (VA)

Report Reviewed By: _

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



Laboratory Report for:

Property Tested: Project # 04481387-1

Intertek-PSI (VA)
2930 Eskridge Road
Fairfax VA 22031

MCPS Radon Survey 15800 Quince Orchard Road Gaithersburg MD 20876

Log Number	Device Number		Test Expo	osure Duratio	n:	Area Tested		Result pCi/L
3202544	3926567	12/04/2018	4:40 pm	12/07/2018	3:00 pm	Floor First Floor	Room 125A	< 0.4
3202545	3926568	12/04/2018	4:42 pm	12/07/2018	3:02 pm	Floor First Floor	Room 124	< 0.4
3202546	3926569	12/04/2018	4:43 pm	12/07/2018	3:06 pm	Floor First Floor	Room 125	< 0.4
3202547	3926570	12/04/2018	4:43 pm	12/07/2018	3:06 pm	Floor First Floor	Room 125 Duplicate	< 0.4
3202548	3926591	12/04/2018	4:45 pm	12/07/2018	3:08 pm	Floor First Floor	Room 124A	< 0.4
3202549	3926592	12/04/2018	4:47 pm	12/07/2018	3:10 pm	Floor First Floor	Room 128	< 0.4
3202550	3926593	12/04/2018	4:48 pm	12/07/2018	3:11 pm	Floor First Floor	Room 129	< 0.4
3202551	3926594	12/04/2018	4:49 pm	12/07/2018	3:13 pm	Floor First Floor	Room 130	< 0.4
3202552	3926595	12/04/2018	4:51 pm	12/07/2018	3:15 pm	Floor First Floor	Room 131	< 0.4
3202553	3926596	12/04/2018	4:52 pm	12/07/2018	3:17 pm	Floor First Floor	Room 132	< 0.4
3202554	3926597	12/04/2018	4:53 pm	12/07/2018	3:18 pm	Floor First Floor	Room 133	< 0.4

Comment: AMENDED REPORT on 12-19-18 and 1-7-19. Stop dates reflected as 12-7-18 for all. Device 3926590 amended to reflect correct device number.

Test Performed By: Lian Zadeng Distributed by: Intertek-PSI (VA)

Report Reviewed By: _

Report Approved By:

Disclaimer:

Shawn Price, Director of Laboratory Operations, AccuStar Labs
The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



Laboratory Report for:

Property Tested: Project # 04481387-1

Intertek-PSI (VA)
2930 Eskridge Road
Fairfax VA 22031

MCPS Radon Survey
15800 Quince Orchard Road
Gaithersburg MD 20876

Log Number	Device Number		Test Expo	osure Duration:	Area Tested		Result pCi/L
3202555	3926598	12/04/2018	4:53 pm	12/07/2018 3:18 pi	m Floor First Floor	Room 133 Duplicate	< 0.4
3202556	3926599	12/04/2018	4:54 pm	12/07/2018 3:22 pi	m Floor First Floor	Room Theatre Office	1.5
3202557	3926600	12/04/2018	4:55 pm	12/07/2018 3:25 pi	m Floor First Floor	Room 134B	0.6
3202558	3926581	12/04/2018	4:55 pm	12/07/2018 3:26 pi	m Floor First Floor	Room 134D	0.7
3202559	3926582	12/04/2018	4:56 pm	12/07/2018 3:27 pi	m Floor First Floor	Room 134C	0.8
3202560	3926583	12/04/2018	4:57 pm	12/07/2018 3:30 pi	m Floor First Floor	Room Stage	0.6
3202561	3926584	12/04/2018	4:59 pm	12/07/2018 3:32 pi	m Floor First Floor	Room Auditorium	0.4
3202562	3926585	12/04/2018	5:04 pm	12/07/2018 4:18 pi	m Floor Second Flo	oor Media Center	< 0.4
3202563	3926586	12/04/2018	5:04 pm	12/07/2018 4:21 pi	m Floor Second Flo	oor Media Center Duplicate	< 0.4
3202564	3926587	12/04/2018	5:05 pm	12/07/2018 4:21 pi	m Floor Second Flo	oor Room Workroom	< 0.4
3202565	3926588	12/04/2018	5:06 pm	12/07/2018 4:23 pi	m Floor Second Flo	oor Room Media Center Office	< 0.4

Comment: AMENDED REPORT on 12-19-18 and 1-7-19. Stop dates reflected as 12-7-18 for all. Device 3926590 amended to reflect correct device number.

Test Performed By: Lian Zadeng Distributed by: Intertek-PSI (VA)

Report Reviewed By: _

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



Laboratory Report for:

Property Tested: Project # 04481387-1

Intertek-PSI (VA)
2930 Eskridge Road
Fairfax VA 22031

MCPS Radon Survey
15800 Quince Orchard Road
Gaithersburg MD 20876

Log Number	Device Number		Test Expo	sure Duratio	n:	Area Tested		Result pCi/L
3202566	3926589	12/04/2018	5:07 pm	12/07/2018	4:25 pm	Floor Second Floor	Room 247	< 0.4
3202567	3926601	12/04/2018	5:08 pm	12/07/2018	4:26 pm	Floor Second Floor	Room Computer Lab	< 0.4
3202568	3926602	12/04/2018	5:09 pm	12/07/2018	4:27 pm	Floor Second Floor	Room 247C	< 0.4
3202569	3926603	12/04/2018	5:09 pm	12/07/2018	4:24 pm	Floor Second Floor	Room Production	< 0.4
3202570	3926604	12/04/2018	5:11 pm	12/07/2018	4:24 pm	Floor Second Floor	Room 249	< 0.4
3202571	3926605	12/04/2018	5:13 pm	12/07/2018	4:25 pm	Floor Second Floor	Room 254	< 0.4
3202572	3926606	12/04/2018	5:15 pm	12/07/2018	4:26 pm	Floor Second Floor	Room 254D	< 0.4
3202573	3926607	12/04/2018	5:15 pm	12/07/2018	4:27 pm	Floor Second Floor	Room 256	< 0.4
3202574	3926608	12/04/2018	5:16 pm	12/07/2018	4:28 pm	Floor Second Floor	Room 259 Concession	0.4
3202575	3926609	12/04/2018	5:17 pm	12/07/2018	4:28 pm	Floor Second Floor	Room 259 Ticket Booth	0.4
3202576	3926610	12/04/2018	5:18 pm	12/07/2018	4:29 pm	Floor Second Floor	Room 210	< 0.4

Comment: AMENDED REPORT on 12-19-18 and 1-7-19. Stop dates reflected as 12-7-18 for all. Device 3926590 amended to reflect correct device number.

Test Performed By: Lian Zadeng Distributed by: Intertek-PSI (VA)

Report Reviewed By: _

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



Laboratory Report for:

Property Tested: Project # 04481387-1

Intertek-PSI (VA)
2930 Eskridge Road
Fairfax VA 22031

MCPS Radon Survey
15800 Quince Orchard Road
Gaithersburg MD 20876

Log Number	Device Number		Test Expo	sure Duratio	n:	Area Tested		Result pCi/L
3202577	3928106	12/04/2018	5:20 pm	12/07/2018	4:31 pm	Floor Second Floor	Room 207 Second Gym	< 0.4
3202578	3928107	12/04/2018	5:21 pm	12/07/2018	4:32 pm	Floor Second Floor	Room Main GYM	< 0.4
3202579	3928108	12/04/2018	5:22 pm	12/07/2018	4:33 pm	Floor Second Floor	Room Main GYM	< 0.4
3202580	3928109	12/04/2018	5:24 pm	12/07/2018	3:51 pm	Floor Second Floor	Room 209	< 0.4
3202581	3928110	12/04/2018	5:25 pm	12/07/2018	3:52 pm	Floor Second Floor	Room Cafeteria	< 0.4
3202582	3928335	12/04/2018	5:26 pm	12/07/2018	3:52 pm	Floor Second Floor	Room Serving Area	< 0.4
3202583	3928336	12/04/2018	5:27 pm	12/07/2018	3:55 pm	Floor Second Floor	Room Kitchen	0.4
3202584	3928337	12/04/2018	5:27 pm	12/07/2018	4:01 pm	Floor Second Floor	Room 218	< 0.4
3202585	3928338	12/04/2018	5:28 pm	12/07/2018	4:03 pm	Floor Second Floor	Room 219	< 0.4
3202586	3928339	12/04/2018	5:29 pm	12/07/2018	4:05 pm	Floor Second Floor	Room 220	< 0.4
3202587	3928340	12/04/2018	5:31 pm	12/07/2018	4:06 pm	Floor Second Floor	Room 221	< 0.4

Comment: AMENDED REPORT on 12-19-18 and 1-7-19. Stop dates reflected as 12-7-18 for all. Device 3926590 amended to reflect correct device number.

Test Performed By: Lian Zadeng Distributed by: Intertek-PSI (VA)

Report Reviewed By: _

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

Disclaimer:

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



Laboratory Report for:

Property Tested: Project # 04481387-1

Intertek-PSI (VA)
2930 Eskridge Road
Fairfax VA 22031

MCPS Radon Survey
15800 Quince Orchard Road
Gaithersburg MD 20876

Log Number	Device Number		Test Expo	osure Duration:	Area Tested	Result pCi/L
3202588	3926571	12/04/2018	5:31 pm	12/07/2018 4:10 pm	Floor Second Floor Room 222	< 0.4
3202589	3926572	12/04/2018	5:32 pm	12/07/2018 4:10 pm	Floor Second Floor Room 222 Duplicate	< 0.4
3202590	3926573	12/04/2018	5:33 pm	12/07/2018 4:11 pm	Floor Second Floor Room 223	< 0.4
3202591	3926574	12/04/2018	5:34 pm	12/07/2018 4:12 pm	Floor Second Floor Room 228G	< 0.4
3202592	3926575	12/04/2018	5:35 pm	12/07/2018 4:14 pm	Floor Second Floor Room 239	< 0.4
3202593	3926576	12/04/2018	5:37 pm	12/07/2018 4:23 pm	Floor Third Floor Room 338	< 0.4
3202594	3926577	12/04/2018	5:37 pm	12/07/2018 4:24 pm	Floor Third Floor Room 339 Office	< 0.4
3202595	3926578	12/04/2018	5:38 pm	12/07/2018 4:27 pm	Floor Third Floor Room 352	< 0.4
3202596	3926579	12/04/2018	5:39 pm	12/07/2018 4:30 pm	Floor Third Floor Room 325	< 0.4
3202597	3926580	12/04/2018	5:41 pm	12/07/2018 4:33 pm	Floor Third Floor Room 318	< 0.4
3202598	3928334	12/04/2018	5:43 pm	12/07/2018 4:35 pm	Floor Third Floor Room 308	< 0.4

Comment: AMENDED REPORT on 12-19-18 and 1-7-19. Stop dates reflected as 12-7-18 for all. Device 3926590 amended to reflect correct device number.

Test Performed By: Lian Zadeng Distributed by: Intertek-PSI (VA)

Report Reviewed By: _

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



Laboratory Report for: Property Tested: Project # 04481387-1

Intertek-PSI (VA) MCPS Radon Survey
2930 Eskridge Road 15800 Quince Orchard Road
Fairfax VA 22031 Gaithersburg MD 20876

Log Number	Device Number		Test Expo	sure Duratio	on:	Area Tested	Result pCi/L
3202599	3917553	12/04/2018	6:00 am	12/07/2018	4:35 pm	Blank	< 0.4
3202600	3926708	12/04/2018	6:50 am	12/07/2018	4:35 pm	Blank	< 0.4
3202601	3926707	12/04/2018	6:50 am	12/07/2018	4:35 pm	Blank	< 0.4
3202602	3927554	12/04/2018	6:00 am	12/07/2018	4:35 pm	Blank	< 0.4
3203160	3926516	12/04/2018	4:13 pm	12/07/2018	2:30 pm	First Floor Room 106B	0.5
3203161	3926611	12/04/2018	3:51 pm	12/07/2018	2:11 pm	First Floor Room 101	< 0.4
3203162	3926564	12/04/2018	4:37 pm	12/07/2018	3:56 pm	First Floor Room 121A	< 0.4

Comment: AMENDED REPORT on 12-19-18 and 1-7-19. Stop dates reflected as 12-7-18 for all. Device 3926590 amended to reflect correct device number.

Test Performed By: Lian Zadeng Distributed by: Intertek-PSI (VA)

Report Reviewed By: _

Report Approved By: _

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.



NRPP 105011 AL NRSB ARL0007 Ohio RL41

EPA Method #402-R-92-004 **Charcoal Canister** NRPP Device Code 6048 NRSB Device Code 10317

Laboratory Report for:

Property Tested:

Intertek-PSI (VA) 2930 Eskridge Road Fairfax VA 22031

MCPS Radon Survey 4514 Taylorsville Road Dayton OH 45424

Log Device Number Number	Test Exposure Duration:	Area Tested	Result pCi/L
3204125 3926831 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	36.1
3204126 3926832 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	34.8
3204127 3926833 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	33.7
3204128 3926834 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	35.8
3204129 3926835 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	35.0
3204130 3926836 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	34.5
3204131 3926837 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	34.6
3204132 3926838 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	34.3
3204133 3926839 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	33.2
3204134 3926840 12/07/2018	3 9:47 am 12/10/2018 9:47 am	Spike	34.0

Comment: A copy of this report was e-mailed to Intertek-PSI (VA)

Test Performed By: Unknown

Distributed by: Intertek-PSI (VA)

Date Received: 12/12/2018 12/12/2018 Date Analyzed: 12/12/2018 Date Reported: 12/13/2018 Date Logged:

Report Reviewed By: _

Report Approved By:

Shawn Price, Director of Laboratory Operations, AccuStar Labs

The uncertainty of this radon measurement is ~+/- 10 %. Factors contributing to uncertainty include statistical variations, daily and seasonal variations in radon concentrations, sample collection techniques and operation of the dwelling. Interference with test conditions may influence the test results.

This report may only be transferred to a third party in its entirety. Analytical results relate to the samples AS RECEIVED BY THE LABORATORY. Results shown on this report represent levels of radon gas measured between the dates shown in the room or area of the site identified above as "Property Tested". Incorrect information will affect results. The results may not be construed as either predictive or supportive of measurements conducted in any area of this structure at any other time. AccuStar Labs, its employees and agents are not responsible for the consequences of any action taken or not taken based upon the results reported or any verbal or written interpretation of the results.

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT Intertell - P5	工	Job Number 187732
NOMINAL Conditions: Radon Conc 39.6	pCi/L Rel. Hum	49.1 % Temp. 70.1
Date Start: 12/7/18 Date Stop: 12/10/18	Pate Start:	Date Stop:
Time Start: <u>0947</u> Time Stop: <u>0947</u>	Time Start:	Time Stop:
Device No.'s: (10) Char. Cans-	Device No.'s:_	
3926831 thro 3926840		
Gu Left		
Date Start: Date Stop:	Date Start:	Date Stop:
Time Start: Time Stop:	Time Start:	Time Stop:
Device No.'s:	Device No.'s:_	74
Date Start: Date Stop:	Date Start:	Date Stop:
Time Start: Time Stop:	Time Start:	Time Stop:
Device No.'s:	Device No.'s:	
		2

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = $7 \mu R/h$ Elevation = 820 ft



Chain of Custody

Project Name: MCPS Radon Survey 2018

Name of Schools:

1. Grosvenor Center (Luxmanor ES)

2. Montrose Center

3. Gibbs ES

4. Westbrook ES

5. Hadley Farms (Resnik ES)

6. Kingsview MS

7. Longview School

8. Lynnbrook Center

9. Magruder HS

10. McAuliffe ES

11. McNair ES

12. Mill Creek Towne ES

13. Martin Luther King MS

14. Montgomery Village MS

15. Great Seneca Creek ES

16. Quince Orchard HS

17. Redland MS

18. North Bethesda MS

19. Spark Matsunaga ES

20. Whetstone ES

21. Wood Acres ES

	Date	Initials
Radon Test Kits Deployed	12/04/2018	NL
Radon Test Kits Sampled	12/07/2018	NL
Radon Test Kits Shipped to Lab*	12/07/2018	NL
Radon Test Kits Received by Lab*	12/08/2018;	1.4.1
Madoli Test Kits Received by Lab.	12/09/2018	NL

^{*}All samples sent to AccuStar Laboratories, 929 Mount Zion Road, Lebanon, PA 17046 and 2 Saber Way, Haverhill, MA 01835

RADON SCREENING SURVEY – FOLLOW-UP QUINCE ORCHARD HIGH SCHOOL

15800 Quince Orchard Rd., Gaithersburg, Maryland 20878

EXECUTIVE SUMMARY

Date of Test Report:	3/7/18	
Round of Testing:	Initial	
	Follow-up	
	Post Remediation	
# Rooms Tested	21	
# Rooms ≥ 4.0 pCi/L:	1	
Low Value:	<0.3	
High Value:	4.5	
Confirmed Rooms ≥ 4.0 pCi/L US EPA	2 (plus 1 location to be evaluated by	
Action Level	mitigation contractor)	

Summary of Sampling Events ≥ 4.0 pCi/L

Room	Result (pCi/L) 2/1/18	Result (pCi/L) 3/7/18	Average Result (pCi/L)
151	6.4	2.6	4.5
152	5.1	2.5	3.8
154	4.6	4.5	4.6
131	4.3	Missing	*
150	4.1	2.1	3.1
153	4.0	2.5	3.3
145	4.0	3.1	3.6

^{* --} To be evaluated by mitigation contractor



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

MCPS RADON TESTING - EXECUTIVE SUMMARY

Site Name	Quince Orchard High School
Date of Report	March 7, 2018
Round of Testing	Initial
	Follow-up
	Post Remediation
	2 year testing
	5 year testing
	HVAC Upgrade
	Window Replacement
	New Addition
	New Facility
# of Rooms Tested	21
# Rooms ≥4.0 pCi/L	1
Lowest Value	< 0.3 pCi/L
Highest Value	4.5 pCi/L

Project Status

Rooms with results $\geq 4.0 \text{ pCi/L}$:

154 (4.5 pCi/L)

Current Project Status at this time: Retesting completed; use the average of the initial and re-test results in a room to determine if remediation is necessary.

Room 131 requires re-test.



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

March 7, 2018

Mr. Richard Cox, MS
Team Leader
Montgomery County Public Schools
Division of Maintenance
Rockville, Maryland 20855

Re: Radon Testing Services

KCI Job #1214634188

Location: Quince Orchard High School 15800 Quince Orchard Rd. Gaithersburg, Maryland 20878

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools pursuant to completing a "short-term" 3-day radon test for the Quince Orchard High School, located at 15800 Quince Orchard Rd. in Gaithersburg, Maryland 20878 (subject site).

SCOPE OF SERVICES

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS056) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.montgomeryco

KCI visited the site on February 6, 2018 and deployed twenty-three (23) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance.

KCI sampled the following locations during this follow-up test:

- 1. Rooms not successfully tested,
- 2. Rooms with elevated November 2017 results (i.e. \geq 3.5 piC/L).

A floor plan map of the building with the test locations is included as Appendix A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted six (6) test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner, Inc. prior to being returned to the laboratory for analysis.

KCI returned to the site on February 9, 2018 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Aircheck, Inc. for analysis by gamma-ray spectroscopy. Aircheck, Inc. is a NRSB certified analytical laboratory for radon analysis (certification #ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

EVALUATION OF TESTING CONDITIONS

These tests represent:

• Follow-up to HVAC upgrade testing.

These tests were conducted to:

• Evaluate radon concentrations following the installation of a new HVAC system.

According to AARST, *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate low temperatures were in the teens and 20s and high temperatures ranged from the mid-30s to low-40s. Maximum sustained winds ranged from 10-17 miles per hour. Average humidity was around 75%. 0.41 Inches of precipitation was recorded during the testing period.

RESULTS

The sampling locations and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). The laboratory analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	154	4.5
≤4.0 piC/L	See Attachment B	See Attachment B

Quality Control Samples			
Results of Blank Canisters: The office blanks and lab transit blanks had test resul			
	less than the laboratory detection limit of 0.3 pCi/L.		
Adequate Laboratory Precision?	Review of the duplicate sample analysis indicates that		
adequate laboratory measurement precision was achieve			
Spike Sample Analysis:	The Spike sample analysis results indicate the laboratory		
is operating within statistical control limits.			

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at 410-316-7800.

Sincerely,

Radon Measurement Specialist

James Makler

KCI Technologies, Inc.

Attachments:

B - Radon Test Summary Spreadsheets

C- Laboratory Analytical Results

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Chek, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

QC- Quality Control

	Table 1- Radon Testing Results				
	Quince Orchard High School				
	Test Period: 02/06/18-02/09/18				
Kit Number	Room / Area	Result			
7193841	133	0.8			
7983836	145	3.1			
7983881	150	2.1			
7983873	151	2.6			
7983818	152	2.5			
7193842	153	2.5			
7983875	154	4.5			
7193853	206	0.7			
7193848	104A	0.7			
7193845	104B	< 0.3			
7193844	106B	1.1			
7983870	* 110A (Missing)	-			
7193849	110B	0.7			
7983880	120A	< 0.3			
7983885	* 121C (Missing)	-			
7193839	123A-122A	< 0.3			
7983815	125B	< 0.3			
7983886	* 131 (Missing)	-			
7193850	200C	< 0.3			
7193854	ISI	< 0.3			

Table 2- Radon Testing Results				
	Quince Orchard High School			
	Test Period: 02/06/18-02/09/18			
Kit Number QC Type Result				
7983884	D (152)	2.3		
7193852	D (206)	0.7		

ATTACHMENT C

Laboratory Analytical Results

Radon test result report for:
QUINCE ORCHARD HIGH SCHOOL
MAIN

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7193848	104A	2018-02-06 @ 11:00 am	2018-02-09 @ 12:00 pm	0.7 ± 0.3	2018-02-12
7193845	104B	2018-02-06 @ 12:00 pm	2018-02-09 @ 12:00 pm	< 0.3	2018-02-12
7193844	106B	2018-02-06 @ 11:00 am	2018-02-09 @ 11:00 am	1.1 ± 0.3	2018-02-12
7983870	110A	@	@		
7193849	110B	2018-02-06 @ 11:00 am	2018-02-09 @ 11:00 am	0.7 ± 0.3	2018-02-12
7983880	120A	2018-02-06 @ 10:00 am	2018-02-09 @ 12:00 pm	< 0.3	2018-02-12
7983885	121C	@	@		
7193839	123A-122A	2018-02-06 @ 10:00 am	2018-02-09 @ 11:00 am	< 0.3	2018-02-12
7983815	125B	2018-02-06 @ 10:00 am	2018-02-09 @ 11:00 am	< 0.3	2018-02-12
7983886	131	@	@		
7193841	133	2018-02-06 @ 10:00 am	2018-02-09 @ 11:00 am	0.8 ± 0.3	2018-02-12
7983836	145	2018-02-06 @ 10:00 am	2018-02-09 @ 11:00 am	3.1 ± 0.4	2018-02-12
7983881	150	2018-02-06 @ 10:00 am	2018-02-09 @ 11:00 am	2.1 ± 0.4	2018-02-12
7983873	151	2018-02-06 @ 10:00 am	2018-02-09 @ 11:00 am	2.6 ± 0.4	2018-02-12
7983884	152	2018-02-06 @ 10:00 am	2018-02-09 @ 11:00 am	2.3 ± 0.4	2018-02-12
7983818	152	2018-02-06 @ 10:00 am	2018-02-09 @ 11:00 am	2.5 ± 0.4	2018-02-12
7193842	153	2018-02-06 @ 11:00 am	2018-02-09 @ 11:00 am	2.5 ± 0.4	2018-02-12
7983875	154	2018-02-06 @ 11:00 am	2018-02-09 @ 11:00 am	4.5 ± 0.5	2018-02-12
7193850	200C	2018-02-06 @ 11:00 am	2018-02-09 @ 12:00 pm	< 0.3	2018-02-12
7193852	206	2018-02-06 @ 11:00 am	2018-02-09 @ 11:00 am	0.7 ± 0.3	2018-02-12
7193853	206	2018-02-06 @ 11:00 am	2018-02-09 @ 11:00 am	0.7 ± 0.3	2018-02-12
7193854	ISI	2018-02-06 @ 11:00 am	2018-02-09 @ 11:00 am	< 0.3	2018-02-12

Engineers • Planners • Scientists • Construction Managers

Corporate Office: 936 Ridgebrook Road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon

Names of Schools:

- 1. English Manor
- 2. Forest Oak Middle School
- 3. Robert Frost Middle
- 4. Damascus Elementary School
- 5. Quince Orchard High School
- 6. Blair G. Ewing Center

	Date	Initials
Radon Test Kits Deployed	02/06/18	M
Radon Test Kits Collected	02/09/18	M
Radon Test Kits Shipped to Lab*	02/09/18	M
Radon Test Kits Received by Lab*	02/12/18	IM

^{*}All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759

Radon test result report for: OFFICE BLANKS

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7979482	1	2018-02-13 @ 1:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986991	10	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7985684	11	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986987	12	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986993	13	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986990	14	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7979485	2	2018-02-13 @ 1:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7985686	3	2018-02-13 @ 1:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986995	4	2018-02-13 @ 1:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986989	5	2018-02-13 @ 1:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986998	6	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986986	7	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986985	8	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986997	9	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20

Radon test result report for: TRANSIT BLANKS

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7984188	1	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7984044	10	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986582	11	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986999	12	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7987000	13	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7984196	14	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986996	2	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986994	3	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7986992	4	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7985680	5	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7985698	6	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7985699	7	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7985700	8	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20
7985872	9	2018-02-13 @ 2:00 pm	2018-02-16 @ 2:00 pm	< 0.3	2018-02-20

** LABORATORY ANALYSIS REPORT **

February 28, 2018

Radon test result report for:

MCPS - Spike Sample Laboratory Results. Measured values are satisfactory, i.e. within $\pm 25\%$ of the chamber's reference value (20.9 pCi/L).

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7984181	1	2018-02-16 @ 11:00 am	2018-02-19 @ 11:00 am	19.7 ± 0.8	2018-02-21
7986621	2	2018-02-16 @ 11:00 am	2018-02-19 @ 11:00 am	19.4 ± 0.8	2018-02-21
7985683	3	2018-02-16 @ 11:00 am	2018-02-19 @ 11:00 am	19.5 ± 0.8	2018-02-21
7984168	4	2018-02-16 @ 11:00 am	2018-02-19 @ 11:00 am	20.5 ± 0.8	2018-02-21
7986618	5	2018-02-16 @ 11:00 am	2018-02-19 @ 11:00 am	19.9 ± 0.8	2018-02-21
7984169	6	2018-02-16 @ 11:00 am	2018-02-19 @ 11:00 am	20.4 ± 0.8	2018-02-21

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI Technologies	Job Number 183530
NOMINAL Conditions: Radon Conc	pCi/L Rel. Hum 49.8 % Temp. 79.1
Date Start: 2/16/18 Date Stop: 2/19/18	Date Start: Date Stop:
Time Start: 1052 Time Stop: 1053	Time Start: Time Stop:
Device No.'s: (6) Char. Bags.	Device No.'s:
7984181, 7986621, 7985683	
7984168, 7986618, 7984169	
G3 Middle	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = $7 \mu R/h$ Elevation = 820 ft



936 RIDGEBROOK ROAD . SPARKS, MD 21152 . 410-316-7800 . (FAX) 410-316-7935

MCPS RADON TESTING - EXECUTIVE SUMMARY

Site Name	Quince Orchard High School
Date of Report	February 1, 2018
	•
Round of Testing	Initial
	Follow-up
	Post Remediation
	2 year testing
	5 year testing
	HVAC Upgrade
	Window Replacement
	New Addition
	New Facility
# of Rooms Tested	79
# Rooms ≥4.0 pCi/L	7
Lowest Value	< 0.3 pCi/L
Highest Value	6.4 pCi/L

Rooms with results $\geq 4.0 \text{ pCi/L}$:

151 (6.4 pCi/L), 152 (5.1 pCi/L), 154 (4.6 pCi/L), 131 (4.3 pCi/L), 150 (4.1 pCi/L), 153 (4.0 pCi/L), 145 (4.0 pCi/L),

Current Project Status at this time: Testing Completed; retesting needed for results ≥ 4.0 pCi/L.

Missing or compromised samples need re-test.



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

February 1, 2018

Mr. Richard Cox, MS
Team Leader
Montgomery County Public Schools
Division of Maintenance
Rockville, Maryland 20855

Re: Radon Testing Services

KCI Job #1214694182

Location: Quince Orchard High School 15800 Quince Orchard Rd. Gaithersburg, Maryland 20878

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to Montgomery County Public Schools pursuant to completing a "short-term" 3-day radon test for the Quince Orchard High School, located at 15800 Quince Orchard Rd. in Gaithersburg, Maryland 20878 (subject site).

SCOPE OF SERVICES

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS056) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.montgomeryco

KCI visited the site on December 4, 2017 and deployed ninety-nine (99) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. A floor plan map of the building with the test locations is included as Appendix A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted six (6) test kits to

Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner, Inc. prior to being returned to the laboratory for analysis.

KCI returned to the site on December 7, 2017 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Aircheck, Inc. for analysis by gamma-ray spectroscopy. Aircheck, Inc. is a NRSB certified analytical laboratory for radon analysis (certification #ARL1402) located at 1936 Butler Bridge Road, Mills River, North Carolina.

EVALUATION OF TESTING CONDITIONS

These tests represent:

• HVAC upgrade testing.

These tests were conducted to:

• Evaluate radon concentrations following the installation of a new HVAC system.

According to AARST, *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*, ideal testing conditions would be when the building is fully occupied and the heating system is active. For this test, the facility's HVAC system was operating in heating mode; therefore, KCI concludes that this test was conducted during ideal testing conditions.

KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

KCI also compiled weather data for the testing period and conducted observations of relevant field conditions. During the test period, weather records indicate low temperatures were in the high-20s to mid-40s and high temperatures ranged from the low-40s to mid-50s. Maximum sustained winds ranged from 12-17 miles per hour. Average humidity was around 65%. 0.16 Inches of precipitation was recorded during the testing period.

RESULTS

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The quality control sample locations and analytical results are listed on Table 2 (Attachment B). Missing/compromised tests, missed rooms, and locked rooms are listed on Table 3 (Attachment B). The laboratory

analytical results are included in Attachment C. Laboratory results and exposure data for the spike samples are also included in Attachment C.

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	151	6.4
≥4.0 piC/L	152	5.1
≥4.0 piC/L	154	4.6
≥4.0 piC/L	131	4.3
≥4.0 piC/L	150	4.1
≥4.0 piC/L	153	4.0
≥4.0 piC/L	145	4.0
≤4.0 piC/L	See Attachment B	See Attachment B

Quality Control Samples				
Results of Blank Canisters:	The field blanks, office blank, and lab transit blanks had test			
	results of less than the laboratory detection limit of 0.3 pCi/L.			
Adequate Laboratory Precision? Review of the duplicate sample analysis indicates that				
	adequate laboratory measurement precision was achieved.			
Spike Sample Analysis:	The Spike sample analysis results indicate the laboratory is			
	operating within statistical control limits.			

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at 410-316-7800.

Sincerely,

James Moulsdale, CHMM Radon Measurement Specialist

Jams Makler

KCI Technologies, Inc.

Attachments:

B- Tables 1-3, Radon Test Summary Spreadsheets

C- Laboratory Analytical Results

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Chek, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

QC- Quality Control

	Radon Testing Results					
	Quince Orchard High School					
I ·	est Period: 12/04/17-12/07/17					
Kit Number Room / Area Result						
7978220	100	1.6				
7978582	101	0.7				
7978219	102	0.9				
7978264	105	0.7				
7978260	112	0.8				
7978277	116	< 0.3				
7978285	117	< 0.3				
7978271	118	0.5				
7978295	119	0.5				
7978298	120	< 0.3				
7978276	121	< 0.3				
7978283	122	0.7				
7978292	125	0.6				
7978291	128	2.1				
7978290	129	2.6				
7978293	130	1.1				
7978288	131	4.3				
7978289	132	1.4				
7978213	138	< 0.3				
7978043	140	0.5				
7978600	143	< 0.3				
7978227	145	4.0				
7978597	148	3.5				
7978598	149	3.2				
7978250	150	4.1				
7978202	151	6.4				
7978585	152	5.1				
7978591	153	4.0				
7978592	154	4.6				
7975377	200	< 0.3				
7975378	206	1.0				
7975379	206	1.1				
7978084	207	0.9				
7978214	207	0.9				
7978085	207	1.0				
7978090	207	0.7				
7978588	210	< 0.3				
7975397	339	0.7				
7975385	340	< 0.3				
7975383	341	0.6				
7975389	342	< 0.3				
7975380	344	0.6				
7975381	345	0.5				
7978262	105B	< 0.3				
7978586	105C	0.6				
7978595	105D	0.9				

Table Note:
* Missing or Compromised Sample

	Radon Testing Results				
	Quince Orchard High School Test Period: 12/04/17-12/07/17				
	Test Feriou. 12/04/17-12/07/17				
Kit Number	Room / Area	Result			
7978594	105E	< 0.3			
7978280	105F	0.5			
7978589	105G	0.5			
7978279	105H	< 0.3			
7978261	1051	< 0.3			
7978590	105J	0.6			
7978593	105K	< 0.3			
7978278	105L	< 0.3			
7978266	105M	0.7			
7978265	108B	1.0			
7978282	117A	< 0.3			
7978281	118A	< 0.3			
7978270	119B	1.3			
7978296	119E	0.6			
7978215	119F	< 0.3			
7978297	119G	1.1			
7978286	122B	< 0.3			
7978284	124A	1.1			
7978259	124B	0.5			
7978294	125A	< 0.3			
7978287	* 133 (Missing)	1.0			
7978080	143A	< 0.3			
7978092	143B	< 0.3			
7978599	144A	< 0.3			
7978587	144B	< 0.3			
7975376	200A	< 0.3			
7975375	200B	< 0.3			
7975373	* 200C (Tampered)	< 0.3			
7975374	200D	< 0.3			
7975372	200F	< 0.3			
7975399	200G	< 0.3			
7975400	200K	< 0.3			
7978238	* 206 (Missing)	-			
7975396	339A	0.7			
7975382	341A	< 0.3			
7978273	AUDITORIUM	< 0.3			
7978274	AUDITORIUM	0.8			
7978272	AUDITORIUM	1.0			
7975384	KIT OFF	1.1			
7978275	THEATRE OFFICE	1.7			

^{*} Missing or Compromised Sample

	Radon Testing Results				
	Quince Orchard High School				
1	Test Period: 12/04/17-12/07/17				
Kit Number	QC Type	Result			
7978596	D (105D)	8.0			
7978268	D (105K)	< 0.3			
7978300	D (119)	< 0.3			
7978269	D (119G)	0.8			
7978091	D (143A)	0.8			
7978263	D (148)	3.9			
7975398	D (200G)	< 0.3			
7978249	D (206)	0.7			
7978299	D (AUDITORIUM)	< 0.3			
7978267	FB (105K)	< 0.3			
7978093	FB (143A)	< 0.3			
7975395	FB (339)	< 0.3			
7983845	OB (OFFICE BLANK)	< 0.3			

Summary of Missed Locations						
	Quince Orchard High School					
	Test Period: 12/04/17-12/07/17					
Kit Number	Room / Area	Result				
-	103 (Missed location)	-				
-	124 (Missed location)	-				
-	133 (Missed location)	-				
-	106B (Missed location)	-				
-	119A (Missed location)	-				
-	120A (Missed location)	-				
-	121C (Missed location)	-				
-	123B (Missed location)	-				
-	125B (Missed location)	-				
-	ISI (Missed location)	-				
-	GLR Office (Missed location)	-				
-	123A (Missed location)	-				
-	Team Rm 1 (Missed location)	-				
-	Team Rm 2 (Missed location)	-				

Summ	ary of Missing, Compromised and ≥4 p	iC/L Tests		
Quince Orchard High School Test Period: 12/04/17-12/07/17				
		•		
Kit Number	Room / Area	Result		
7978288	131	4.3		
7978227	145	4.0		
7978250	150	4.1		
7978202	151	6.4		
7978585	152	5.1		
7978591	153	4.0		
7978592	154	4.6		
7978287	* 133 (Missing)	1.0		
7975373	* 200C (Tampered)	< 0.3		
7978238	* 206 (Missing)	-		
	+	_		
	1	+		
		+		
		_		
	+			

ATTACHMENT C

Laboratory Analytical Results

December 29, 2017

Radon test result report for:
QUINCE ORCHARD HIGH SCHOOL
MAIN

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7978220	100	2017-12-04 @ 10:00 am	2017-12-07 @ 8:00 am	1.6 ± 0.3	2017-12-11
7978582	101	2017-12-04 @ 10:00 am	2017-12-07 @ 8:00 am	0.7 ± 0.3	2017-12-11
7978219	102	2017-12-04 @ 10:00 am	2017-12-07 @ 8:00 am	0.9 ± 0.4	2017-12-12
7978264	105	2017-12-04 @ 10:00 am	2017-12-07 @ 7:00 am	0.7 ± 0.4	2017-12-12
7978262	105B	2017-12-04 @ 10:00 am	2017-12-07 @ 7:00 am	< 0.3	2017-12-12
7978586	105C	2017-12-04 @ 10:00 am	2017-12-07 @ 7:00 am	0.6 ± 0.4	2017-12-12
7978596	105D	2017-12-04 @ 10:00 am	2017-12-07 @ 7:00 am	0.8 ± 0.4	2017-12-12
7978595	105D	2017-12-04 @ 10:00 am	2017-12-07 @ 7:00 am	0.9 ± 0.4	2017-12-12
7978594	105E	2017-12-04 @ 10:00 am	2017-12-07 @ 7:00 am	< 0.3	2017-12-12
7978280	105F	2017-12-04 @ 10:00 am	2017-12-07 @ 7:00 am	0.5 ± 0.4	2017-12-12
7978589	105G	2017-12-04 @ 10:00 am	2017-12-07 @ 7:00 am	0.5 ± 0.3	2017-12-12
7978279	105H	2017-12-04 @ 10:00 am	2017-12-07 @ 7:00 am	< 0.3	2017-12-12
7978261	105I	2017-12-04 @ 10:00 am	2017-12-07 @ 7:00 am	< 0.3	2017-12-12
7978590	105J	2017-12-04 @ 10:00 am	2017-12-07 @ 7:00 am	0.6 ± 0.3	2017-12-12
7978267	105K	2017-12-04 @ 10:00 am	2017-12-07 @ 7:00 am	< 0.3	2017-12-11
7978593	105K	2017-12-04 @ 10:00 am	2017-12-07 @ 7:00 am	< 0.3	2017-12-12
7978268	105K	2017-12-04 @ 10:00 am	2017-12-07 @ 7:00 am	< 0.3	2017-12-12
7978278	105L	2017-12-04 @ 10:00 am	2017-12-07 @ 7:00 am	< 0.3	2017-12-11
7978266	105M	2017-12-04 @ 10:00 am	2017-12-07 @ 7:00 am	0.7 ± 0.3	2017-12-12
7978265	108B	2017-12-04 @ 10:00 am	2017-12-07 @ 8:00 am	1.0 ± 0.4	2017-12-12
7978260	112	2017-12-04 @ 10:00 am	2017-12-07 @ 7:00 am	0.8 ± 0.4	2017-12-12
7978277	116	2017-12-04 @ 9:00 am	2017-12-07 @ 7:00 am	< 0.3	2017-12-12
7978285	117	2017-12-04 @ 9:00 am	2017-12-07 @ 7:00 am	< 0.3	2017-12-12
7978282	117A	2017-12-04 @ 9:00 am	2017-12-07 @ 7:00 am	< 0.3	2017-12-12
7978271	118	2017-12-04 @ 9:00 am	2017-12-07 @ 7:00 am	0.5 ± 0.4	2017-12-12
7978281	118A	2017-12-04 @ 9:00 am	2017-12-07 @ 7:00 am	< 0.3	2017-12-12
7978300	119	2017-12-04 @ 9:00 am	2017-12-07 @ 7:00 am	< 0.3	2017-12-12
7978295	119	2017-12-04 @ 9:00 am	2017-12-07 @ 7:00 am	0.5 ± 0.4	2017-12-12
7978270	119B	2017-12-04 @ 9:00 am	2017-12-07 @ 7:00 am	1.3 ± 0.4	2017-12-12
7978296	119E	2017-12-04 @ 9:00 am	2017-12-07 @ 7:00 am	0.6 ± 0.4	2017-12-12
7978215	119F	2017-12-04 @ 9:00 am	2017-12-07 @ 7:00 am	< 0.3	2017-12-12
7978297	119G	2017-12-04 @ 9:00 am	2017-12-07 @ 9:00 am	1.1 ± 0.3	2017-12-12
7978269	119G	2017-12-04 @ 9:00 am	2017-12-07 @ 9:00 am	0.8 ± 0.3	2017-12-12
7978298	120	2017-12-04 @ 9:00 am	2017-12-07 @ 7:00 am	< 0.3	2017-12-12
7978276	121	2017-12-04 @ 9:00 am	2017-12-07 @ 7:00 am	< 0.3	2017-12-12
7978283	122	2017-12-04 @ 9:00 am	2017-12-07 @ 7:00 am	0.7 ± 0.4	2017-12-12
7978286	122B	2017-12-04 @ 9:00 am	2017-12-07 @ 7:00 am	< 0.3	2017-12-12

December 29, 2017

Radon test result report for:
QUINCE ORCHARD HIGH SCHOOL
MAIN

7978284 124A 2017-12-04 @ 9:00 am 2017-12-07 @ 7:00 am 0.5 ± 0.4 2017-12-12 2017-12-04 @ 9:00 am 2017-12-07 @ 7:00 am 0.5 ± 0.4 2017-12-12 2017-12-04 @ 9:00 am 2017-12-07 @ 7:00 am 0.5 ± 0.4 2017-12-12 2017-12-04 @ 9:00 am 2017-12-07 @ 7:00 am 0.5 ± 0.4 2017-12-12 2017-12-04 @ 9:00 am 2017-12-07 @ 7:00 am 0.5 ± 0.4 2017-12-12 2017-12-04 @ 8:00 am 2017-12-07 @ 7:00 am 2.1 ± 0.3 2017-12-12 2017-12-04 @ 8:00 am 2017-12-07 @ 7:00 am 2.6 ± 0.4 2017-12-12 2017-12-04 @ 8:00 am 2017-12-07 @ 7:00 am 1.1 ± 0.4 2017-12-12 2017-12-04 @ 8:00 am 2017-12-07 @ 7:00 am 1.1 ± 0.4 2017-12-12 2017-12-04 @ 8:00 am 2017-12-07 @ 7:00 am 1.1 ± 0.4 2017-12-12 2017-12-04 @ 8:00 am 2017-12-07 @ 7:00 am 1.4 ± 0.4 2017-12-12 2017-12-04 @ 8:00 am 2017-12-07 @ 7:00 am 1.4 ± 0.4 2017-12-12 2017-12-04 @ 8:00 am 2017-12-07 @ 9:00 am 1.0 ± 0.3 2017-12-12 2017-12-04 @ 11:00 am 2017-12-07 @ 9:00 am 1.0 ± 0.3 2017-12-12 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am 0.5 ± 0.3 2017-12-12 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am 0.5 ± 0.3 2017-12-12 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am 0.8 ± 0.3 2017-12-12 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am 0.8 ± 0.3 2017-12-12 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am 0.8 ± 0.3 2017-12-12 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am 0.8 ± 0.3 2017-12-12 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am 0.3 2017-12-12 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am 0.3 2017-12-12 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am 0.3 2017-12-12 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am 0.3 2017-12-12 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am 0.3 2017-12-12 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am 0.3 2017-12-12 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am 0.3 2017-12-12 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am 0.3 2017-12-12 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am 0.3 2017-12-12 2017-1	Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7978292 125 2017-12-04 @ 8:00 am 2017-12-07 @ 7:00 am	7978284	124A	2017-12-04 @ 9:00 am	2017-12-07 @ 7:00 am	1.1 ± 0.4	2017-12-12
$\begin{array}{cccccccccccccccccccccccccccccccccccc$	7978259	124B	2017-12-04 @ 9:00 am	2017-12-07 @ 7:00 am	0.5 ± 0.4	2017-12-12
$\begin{array}{cccccccccccccccccccccccccccccccccccc$	7978292	125	2017-12-04 @ 8:00 am	2017-12-07 @ 7:00 am	0.6 ± 0.4	2017-12-12
$\begin{array}{cccccccccccccccccccccccccccccccccccc$	7978294	125A	2017-12-04 @ 9:00 am	2017-12-07 @ 7:00 am	< 0.3	2017-12-12
$\begin{array}{cccccccccccccccccccccccccccccccccccc$	7978291	128	2017-12-04 @ 8:00 am	2017-12-07 @ 9:00 am	2.1 ± 0.3	2017-12-11
$\begin{array}{cccccccccccccccccccccccccccccccccccc$	7978290	129	2017-12-04 @ 8:00 am	2017-12-07 @ 7:00 am	2.6 ± 0.4	2017-12-12
$\begin{array}{cccccccccccccccccccccccccccccccccccc$	7978293	130	2017-12-04 @ 8:00 am	2017-12-07 @ 7:00 am	1.1 ± 0.4	2017-12-12
7978287 133 2017-12-04 @ 8:00 am 2017-12-07 @ 9:00 am 1.0 ± 0.3 2017-12-12 7978213 138 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am < 0.3	7978288	131	2017-12-04 @ 8:00 am	2017-12-07 @ 7:00 am	4.3 ± 0.5	2017-12-12
7978213 138 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am < 0.3	7978289	132	2017-12-04 @ 8:00 am	2017-12-07 @ 7:00 am	1.4 ± 0.4	2017-12-12
$\begin{array}{cccccccccccccccccccccccccccccccccccc$	7978287	133	2017-12-04 @ 8:00 am	2017-12-07 @ 9:00 am	1.0 ± 0.3	2017-12-12
$\begin{array}{cccccccccccccccccccccccccccccccccccc$	7978213	138	2017-12-04 @ 11:00 am	2017-12-07 @ 8:00 am	< 0.3	2017-12-12
7978091 143A 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am 0.8 ± 0.3 2017-12-12 7978080 143A 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am < 0.3 2017-12-12 7978093 143A 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am < 0.3 2017-12-12 7978092 143B 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am < 0.3 2017-12-12 7978599 144A 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am < 0.3 2017-12-12 7978587 144B 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am < 0.3 2017-12-11 7978597 148 2017-12-04 @ 10:00 am 2017-12-07 @ 8:00 am < 0.3 2017-12-12 7978597 148 2017-12-04 @ 10:00 am 2017-12-07 @ 8:00 am < 0.3 < 0.0 < 0.0 < 0.0 < 0.0 < 0.0 < 0.0 < 0.0 < 0.0 < 0.0 < 0.0 < 0.0 < 0.0 < 0.0 < 0.0 < 0.0 < 0.0 < 0.0 < 0.0 < 0.0 < 0.0 <td< td=""><td>7978043</td><td>140</td><td>2017-12-04 @ 11:00 am</td><td>2017-12-07 @ 8:00 am</td><td>0.5 ± 0.3</td><td>2017-12-12</td></td<>	7978043	140	2017-12-04 @ 11:00 am	2017-12-07 @ 8:00 am	0.5 ± 0.3	2017-12-12
7978080 143A 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am < 0.3	7978600		2017-12-04 @ 11:00 am	2017-12-07 @ 8:00 am		2017-12-12
7978093 143A 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am < 0.3	7978091		2017-12-04 @ 11:00 am	2017-12-07 @ 8:00 am		
7978092 143B 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am < 0.3	7978080	143A	2017-12-04 @ 11:00 am	2017-12-07 @ 8:00 am		2017-12-12
7978599 144A 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am < 0.3						
$\begin{array}{cccccccccccccccccccccccccccccccccccc$						
79782271452017-12-04 @ 10:00 am2017-12-07 @ 8:00 am 4.0 ± 0.5 2017-12-1279785971482017-12-04 @ 10:00 am2017-12-07 @ 8:00 am 3.5 ± 0.4 2017-12-1179782631482017-12-04 @ 10:00 am2017-12-07 @ 8:00 am 3.9 ± 0.5 2017-12-1279785981492017-12-04 @ 11:00 am2017-12-07 @ 8:00 am 3.2 ± 0.4 2017-12-1279782501502017-12-04 @ 11:00 am2017-12-07 @ 8:00 am 4.1 ± 0.5 2017-12-1279782021512017-12-04 @ 11:00 am2017-12-07 @ 8:00 am 6.4 ± 0.6 2017-12-1279785851522017-12-04 @ 11:00 am2017-12-07 @ 8:00 am 5.1 ± 0.4 2017-12-1179785911532017-12-04 @ 11:00 am2017-12-07 @ 8:00 am 4.0 ± 0.5 2017-12-1279785921542017-12-04 @ 11:00 am2017-12-07 @ 8:00 am 4.6 ± 0.5 2017-12-1279753772002017-12-04 @ 1:00 pm2017-12-07 @ 8:00 am <0.3 2017-12-127975375200B2017-12-04 @ 1:00 pm2017-12-07 @ 8:00 am <0.3 2017-12-117975373200C2017-12-04 @ 1:00 pm2017-12-07 @ 8:00 am <0.3 2017-12-117975374200D2017-12-04 @ 1:00 pm2017-12-07 @ 8:00 am <0.3 2017-12-117975378200G2017-12-04 @ 1:00 pm2017-12-07 @ 8:00 am <0.3 2017-12-117975379200G2017-12-04 @ 1:00 pm2017-12-07 @ 8:00 am <0.3 2017-12-117975399200G2017-1						
79785971482017-12-04 @ 10:00 am2017-12-07 @ 8:00 am 3.5 ± 0.4 2017-12-1179782631482017-12-04 @ 10:00 am2017-12-07 @ 8:00 am 3.9 ± 0.5 2017-12-1279785981492017-12-04 @ 11:00 am2017-12-07 @ 8:00 am 3.2 ± 0.4 2017-12-1279782501502017-12-04 @ 11:00 am2017-12-07 @ 8:00 am 4.1 ± 0.5 2017-12-1279782021512017-12-04 @ 11:00 am2017-12-07 @ 8:00 am 6.4 ± 0.6 2017-12-1279785851522017-12-04 @ 11:00 am2017-12-07 @ 8:00 am 5.1 ± 0.4 2017-12-1179785911532017-12-04 @ 11:00 am2017-12-07 @ 8:00 am 4.0 ± 0.5 2017-12-1279785921542017-12-04 @ 11:00 am2017-12-07 @ 8:00 am 4.6 ± 0.5 2017-12-1279753772002017-12-04 @ 1:00 pm2017-12-07 @ 8:00 am < 0.3 2017-12-127975375200B2017-12-04 @ 1:00 pm2017-12-07 @ 8:00 am < 0.3 2017-12-117975373200C2017-12-04 @ 1:00 pm2017-12-07 @ 8:00 am < 0.3 2017-12-117975374200D2017-12-04 @ 1:00 pm2017-12-07 @ 8:00 am < 0.3 2017-12-117975372200F2017-12-04 @ 1:00 pm2017-12-07 @ 8:00 am < 0.3 2017-12-117975398200G2017-12-04 @ 1:00 pm2017-12-07 @ 8:00 am < 0.3 2017-12-117975399200G2017-12-04 @ 1:00 pm2017-12-07 @ 8:00 am < 0.3 2017-12-117975399200G2017						
$\begin{array}{cccccccccccccccccccccccccccccccccccc$						
$\begin{array}{cccccccccccccccccccccccccccccccccccc$						
$\begin{array}{cccccccccccccccccccccccccccccccccccc$						
79782021512017-12-04 @ 11:00 am2017-12-07 @ 8:00 am 6.4 ± 0.6 2017-12-1279785851522017-12-04 @ 11:00 am2017-12-07 @ 8:00 am 5.1 ± 0.4 2017-12-1179785911532017-12-04 @ 11:00 am2017-12-07 @ 8:00 am 4.0 ± 0.5 2017-12-1279785921542017-12-04 @ 11:00 am2017-12-07 @ 8:00 am 4.6 ± 0.5 2017-12-1279753772002017-12-04 @ 1:00 pm2017-12-07 @ 8:00 am < 0.3 2017-12-127975376200A2017-12-04 @ 1:00 pm2017-12-07 @ 8:00 am < 0.3 2017-12-117975375200B2017-12-04 @ 1:00 pm2017-12-07 @ 8:00 am < 0.3 2017-12-127975373200C2017-12-04 @ 1:00 pm2017-12-07 @ 8:00 am < 0.3 2017-12-117975374200D2017-12-04 @ 1:00 pm2017-12-07 @ 8:00 am < 0.3 2017-12-117975372200F2017-12-04 @ 1:00 pm2017-12-07 @ 8:00 am < 0.3 2017-12-117975398200G2017-12-04 @ 1:00 pm2017-12-07 @ 8:00 am < 0.3 2017-12-117975399200G2017-12-04 @ 1:00 pm2017-12-07 @ 8:00 am < 0.3 2017-12-11						
7978585 152 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am 5.1 ± 0.4 2017-12-11 7978591 153 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am 4.0 ± 0.5 2017-12-12 7978592 154 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am 4.6 ± 0.5 2017-12-12 7975377 200 2017-12-04 @ 1:00 pm 2017-12-07 @ 8:00 am < 0.3						
7978591 153 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am 4.0 ± 0.5 2017-12-12 7978592 154 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am 4.6 ± 0.5 2017-12-12 7975377 200 2017-12-04 @ 1:00 pm 2017-12-07 @ 8:00 am < 0.3						
7978592 154 2017-12-04 @ 11:00 am 2017-12-07 @ 8:00 am 4.6 ± 0.5 2017-12-12 7975377 200 2017-12-04 @ 1:00 pm 2017-12-07 @ 8:00 am < 0.3						
7975377 200 2017-12-04 @ 1:00 pm 2017-12-07 @ 8:00 am < 0.3						
7975376 200A 2017-12-04 @ 1:00 pm 2017-12-07 @ 8:00 am < 0.3						
7975375 200B 2017-12-04 @ 1:00 pm 2017-12-07 @ 8:00 am < 0.3			•			
7975373 200C 2017-12-04 @ 1:00 pm 2017-12-07 @ 8:00 am < 0.3			•			
7975374 200D 2017-12-04 @ 1:00 pm 2017-12-07 @ 8:00 am < 0.3			•			
7975372 200F 2017-12-04 @ 1:00 pm 2017-12-07 @ 8:00 am < 0.3			•			
7975398 200G 2017-12-04 @ 1:00 pm 2017-12-07 @ 8:00 am <0.3 2017-12-11 7975399 200G 2017-12-04 @ 1:00 pm 2017-12-07 @ 8:00 am <0.3 2017-12-12			•			
7975399 200G 2017-12-04 @ 1:00 pm 2017-12-07 @ 8:00 am < 0.3 2017-12-12			•			
•			•			
7975400 200K 2017-12-04 @ 1:00 pm 2017-12-07 @ 8:00 am < 0.3 2017-12-11			_			
	/9/5400	200K	2017-12-04 @ 1:00 pm	2017-12-07 @ 8:00 am	< 0.3	2017-12-11

December 29, 2017

Radon test result report for:
QUINCE ORCHARD HIGH SCHOOL
MAIN

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7978238	206	@	@	_	-
7978249	206	2017-12-04 @ 12:00 pm	2017-12-07 @ 8:00 am	0.7 ± 0.4	2017-12-12
7975378	206	2017-12-04 @ 12:00 pm	2017-12-07 @ 8:00 am	1.0 ± 0.4	2017-12-12
7975379	206	2017-12-04 @ 12:00 pm	2017-12-07 @ 8:00 am	1.1 ± 0.4	2017-12-12
7978085	207	2017-12-04 @ 12:00 pm	2017-12-07 @ 8:00 am	1.0 ± 0.3	2017-12-12
7978090	207	2017-12-04 @ 12:00 pm	2017-12-07 @ 8:00 am	0.7 ± 0.3	2017-12-12
7978214	207	2017-12-04 @ 12:00 pm	2017-12-07 @ 8:00 am	0.9 ± 0.3	2017-12-12
7978084	207	2017-12-04 @ 12:00 pm	2017-12-07 @ 8:00 am	0.9 ± 0.3	2017-12-12
7978588	210	2017-12-04 @ 12:00 pm	2017-12-07 @ 8:00 am	< 0.3	2017-12-11
7975395	339	2017-12-04 @ 1:00 pm	2017-12-07 @ 8:00 am	< 0.3	2017-12-12
7975397	339	2017-12-04 @ 1:00 pm	2017-12-07 @ 8:00 am	0.7 ± 0.4	2017-12-12
7975396	339A	2017-12-04 @ 1:00 pm	2017-12-07 @ 8:00 am	0.7 ± 0.4	2017-12-12
7975385	340	2017-12-04 @ 1:00 pm	2017-12-07 @ 8:00 am	< 0.3	2017-12-11
7975383	341	2017-12-04 @ 1:00 pm	2017-12-07 @ 8:00 am	0.6 ± 0.4	2017-12-12
7975382	341A	2017-12-04 @ 1:00 pm	2017-12-07 @ 8:00 am	< 0.3	2017-12-11
7975389	342	2017-12-04 @ 1:00 pm	2017-12-07 @ 8:00 am	< 0.3	2017-12-12
7975380	344	2017-12-04 @ 1:00 pm	2017-12-07 @ 8:00 am	0.6 ± 0.4	2017-12-12
7975381	345	2017-12-04 @ 1:00 pm	2017-12-07 @ 8:00 am	0.5 ± 0.3	2017-12-12
7978272	AUDITORIUM	2017-12-04 @ 11:00 am	2017-12-07 @ 7:00 am	1.0 ± 0.4	2017-12-12
7978299	AUDITORIUM	2017-12-04 @ 11:00 am	2017-12-07 @ 7:00 am	< 0.3	2017-12-12
7978273	AUDITORIUM	2017-12-04 @ 11:00 am	2017-12-07 @ 7:00 am	< 0.3	2017-12-12
7978274	AUDITORIUM	2017-12-04 @ 11:00 am	2017-12-07 @ 7:00 am	0.8 ± 0.4	2017-12-12
7975384	KIT OFF	2017-12-04 @ 12:00 pm	2017-12-07 @ 8:00 am	1.1 ± 0.4	2017-12-12
7983845	OFFICE BLANK	2017-12-04 @ 11:00 am	2017-12-07 @ 11:00 am	< 0.3	2017-12-11
7978275	THEATRE OFFICE	2017-12-04 @ 8:00 am	2017-12-07 @ 7:00 am	1.7 ± 0.4	2017-12-12



Engineers • Planners • Scientists • Construction Managers

Corporate Office: 936 Ridgebrook Road • Sparks, Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon Phase

Names of Schools:

- 1. Brooke Grove Elementary School
- 2. Brown Station Elementary School
- 3. Diamond Elementary School Addition
- 4. Dufief Elementary School
- 5. Emory Grove Center
- 6. Fields Road Elementary School
- 7. Facilities Maintenance Depot
- 8. Forest Oak Middle School
- 9. Francis Scott Key Middle School
- 10. Gaithersburg Elementary School
- 11. Gaithersburg Middle School
- 12. Germantown Elementary School
- 13. Greenwood Elementary School
- 14. Jones Lane Elementary School

- 14. Newport Mill Middle School
- 15. Oakview Elementary School
- 16. Quince Orchard High School
- 17. Robert Frost Middle School
- 18. Rosa Parks Middle School
- 19. South Lake Elementary School

	Date	Initials
Radon Test Kits Deployed	12/04/17	VM
Radon Test Kits Collected	12/07/17	IM
Radon Test Kits Shipped to Lab*	12/07/17	UM
Radon Test Kits Received by Lab*	12/11/17	JM

^{*}All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759

Radon test result report for: TRANSIT 2 MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7193838	TRANSIT 1	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7979384	TRANSIT 10	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7979385	TRANSIT 11	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7984056	TRANSIT 12	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7983834	TRANSIT 13	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7194097	TRANSIT 14	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7194092	TRANSIT 15	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7193840	TRANSIT 16	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7979072	TRANSIT 17	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7979071	TRANSIT 18	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7979065	TRANSIT 19	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	0.6 ± 0.4	2017-12-13
7978194	TRANSIT 2	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7985660	TRANSIT 20	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7985661	TRANSIT 21	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	0.7 ± 0.4	2017-12-13
7193843	TRANSIT 22	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7984055	TRANSIT 23	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7983813	TRANSIT 24	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7983827	TRANSIT 25	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7978193	TRANSIT 3	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7978189	TRANSIT 4	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	0.5 ± 0.4	2017-12-13
7986187	TRANSIT 5	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7986188	TRANSIT 6	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7986177	TRANSIT 7	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7979077	TRANSIT 8	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13
7979386	TRANSIT 9	2017-12-05 @ 2:00 pm	2017-12-08 @ 2:00 pm	< 0.3	2017-12-13

** LABORATORY ANALYSIS REPORT **

Radon test result report for:

MCPS - Spike Sample Laboratory Results. Measured values are satisfactory, i.e. within $\pm 25\%$ of the chamber's reference value (27.7 pCi/L).

Kit #	Room Id	Started		Ended	pCi/L	Analyzed
7975075	S 1	2017-12-01	@ 11:00 am	2017-12-04 @ 11:00 am	25.6 ± 0.7	2017-12-07
7975064	S2	2017-12-01	@ 11:00 am	2017-12-04 @ 11:00 am	27.4 ± 0.8	2017-12-07
7975063	S3	2017-12-01	@ 11:00 am	2017-12-04 @ 11:00 am	26.3 ± 0.7	2017-12-07
7975065	S4	2017-12-01	@ 11:00 am	2017-12-04 @ 11:00 am	23.0 ± 0.7	2017-12-07
7975069	S5	2017-12-01	@ 11:00 am	2017-12-04 @ 11:00 am	25.6 ± 0.7	2017-12-07
7975070	S 6	2017-12-01	@ 11:00 am	2017-12-04 @ 11:00 am	23.0 ± 0.7	2017-12-07

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI Technology	gies Inc. Job Number 182393
	_pCi/L Rel. Hum <u>49.1</u> % Temp. <u>70.</u> /
Date Start: 12/1/17 Date Stop: 12/4/	Date Start: Date Stop:
Time Start: <u>L949</u> Time Stop: <u>1949</u>	Time Start: Time Stop:
Device No.'s: (6) Chan Bags.	Deviçe No.'s:
7973065, 1975069, 7975079	
Fy Ront	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = $7 \mu R/h$ Elevation = 820 ft

RADON SCREENING SURVEY – FOLLOW-UP QUINCE ORCHARD HIGH SCHOOL

15800 Quince Orchard Road, Gaithersburg, Maryland 20878

EXECUTIVE SUMMARY

Date of Test Report:	3/15/16 Follow-Up
Round of Testing:	Initial
	Follow-up
	Post Remediation
# Rooms Tested	3
# Rooms ≥ 4.0 pCi/L:	0
Low Value:	<0.3
High Value:	3.1
Confirmed Rooms ≥ 4.0 pCi/L US EPA	0
Action Level	

Summary of Sampling Events ≥ 4.0 pCi/L

Room	Result (pCi/L)	Result (pCi/L)	Average Result
	2/29/16 (Rev 1 Initial)	3/15/16 Follow-Up	(pCi/L)
125B	<0.3 Tampered	<0.3	<0.3
ISI	<0.3 Tampered	<0.3	<0.3
Lower AUDI	Missing	3.0	3.0
Lower AUDI	2.5 Tampered	3.1	2.8



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

MCPS RADON TESTING

Executive Summary: Quince Orchard High School

Date of Test Report:	3/15/2016
Round of Testing:	Initial
	Follow-up
	Post Remediation
# Rooms Tested:	3
# Rooms \geq 4.0 pCi/L:	0
Low Value:	< 0.3
High Value:	3.1

Project Status:

Retesting completed; no further action at this time.

KCI TECHNOLOGIES, INC. WWW.kci.com



ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

March 15, 2016

Mr. Richard Cox Indoor Air Quality Team Leader Montgomery County Public Schools 850 Hungerford Drive Rockville, MD 20850

Re: Radon Testing Services

KCI Job # 12146341.29

Location: Quince Orchard High School

15800 Quince Orchard Road Gaithersburg, MD 20878

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to the Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Quince Orchard High School, located at 15800 Quince Orchard Road in Gaithersburg, Maryland 20878 (subject site).

Scope of Services:

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS056) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

KCI visited the site on February 22, 2016 and deployed six (6) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted six (6) test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on February 25, 2016 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc. is a NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936

KCI TECHNOLOGIES, INC. WWW.kci.com

Butler Bridge Road, Mills River, North Carolina.

Evaluation of Testing Conditions:

The operating condition that represents the greatest amount of significantly occupied time for this building is; heating active, with outdoor temperature averages $\leq 65^{\circ}$ F.

KCI concludes that the test period reasonably represents normal conditions when the building is significantly occupied. Clear characterization of the radon hazard is most likely to be observed under this normal operating condition. Based on the evaluation of test conditions, this test should reasonably characterize radon hazards.

KCI also conducted observations of field conditions which could affect the results of the test and compiled weather data for the testing period. Note that strong storms and heavy rainfall were recorded during the test period. The unusual weather conditions may have resulted in atypical radon test results for this facility.

KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

Results:

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result	
≥4.0 piC/L	none	n/a	
<4.0 piC/L	See Attachn	nent B	

Notes:

D- Duplicate sample

The field blank, office blanks, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L. Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C). Laboratory results and exposure data for the spike samples are also included in Attachment C.

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 316-7800.

KCI TECHNOLOGIES, INC. WWW.kci.com

Mr. Richard Cox March 15, 2016 Page 4

Sincerely,

James M. Moulsdale

James Makler

Radon Measurement Specialist

KCI Technologies, Inc.

Attachments: A- Floor Plan with Test Locations

B- Table 1-Radon Test Summary Spreadsheet

C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Chek, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank*

PM- Project Manager

QC- Quality Control

*Office blanks were submitted at a rate of 1% for all samples deployed in Phase 9 testing. Office blanks were not submitted under each school individually.

Radon Testing Results						
	Quince Orchard HS					
7	Test Period: 02/22/16-02/25/16					
Kit Number Room / Area Result						
7719459	125 B	< 0.3				
7712552	7712552 ISI < 0.3					
7712564	Lower Auditorium	3.1				
7712567 Lower Auditorium 3.0						

	Radon Testing Results						
	Quince Orchard HS						
	Test Period: 02/22/16-02/25/16						
Kit Number	QC Type	Result					
7712583	D (125B)	< 0.3					
7712572	FB (125B)	< 0.3					

ATTACHMENT C

Laboratory Analytical Results

March** LABORATORY ANALYSIS 8, REPORT **

Radon test result report for: QUINCE ORCHARD HS MAIN

Kit#	Room Id	Started		Ended	pCi/L	Analyzed
7719459	125 B	2016-02-22	@ 2:00 pm	2016-02-25 @ 2:00 pm	< 0.3	2016-02-29
7712572	125B	2016-02-22	@ 2:00 pm	2016-02-25 @ 2:00 pm	< 0.3	2016-02-29
7712583	125B	2016-02-22	@ 2:00 pm	2016-02-25 @ 2:00 pm	< 0.3	2016-02-29
7712552	ISI	2016-02-22	@ 2:00 pm	2016-02-25 @ 2:00 pm	< 0.3	2016-02-29
7712564	Lower Audi.	2016-02-22	@ 2:00 pm	2016-02-25 @ 2:00 pm	3.1 ± 0.4	2016-02-29
7712567	Lower Audi.	2016-02-22	@ 2:00 pm	2016-02-25 @ 2:00 pm	3.0 ± 0.4	2016-02-29

March** LABORATORY ANALYSIS 9, REPORT **

Radon test result report for: MCPS

Phase 9 Office Blanks

Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7712568	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29
7712584	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29
7719460	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29
7719481	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29
7719497	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29
7719498	0	2016-02-22 @ 6:00 pm	2016-02-25 @ 3:00 pm	< 0.3	2016-02-29

March** LABORATORY ANALYSIS 9, REPORT **

Radon test result report for:

MCPS
Phase 9 Office Blanks

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7731626	0	2016-02-23 @ 2:00 pm	2016-02-26 @ 3:00 pm	< 0.3	2016-03-01
7731633	0	2016-02-23 @ 2:00 pm	2016-02-26 @ 3:00 pm	< 0.3	2016-03-01
7735204	0	2016-02-23 @ 2:00 pm	2016-02-26 @ 3:00 pm	< 0.3	2016-03-01
7733204		2010-02-23 @ 2.00 pm	2010-02-20 @ 3.00 pm	V 0.5	2010-03-0

February LABORATORY ANALYSIS 23, REPORT **

Radon test result report for:
TRANSIT- PHASE 7, 8, 9
NONE

Rit# Room Id Started Started PCi/L Analyzed						
7734946 10 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	Kit#	Room Id	Started	Ended	pCi/L	Analyzed
7734955 11 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734956 12 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734959 13 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734959 14 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734953 15 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734954 16 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734940 17 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734939 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734942 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734939 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734939 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 21 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 25 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 25 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 29 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 31 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734931 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 4 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 20	7734937	1	2016-02-19 @ 3:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734956 12 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734959 13 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734930 14 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734953 15 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734954 16 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734940 17 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734949 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734939 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734929 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734929 2 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734933 22 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734934 25 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734931 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734931 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734931 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734931 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734931 31 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 201	7734946	10	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734959 13 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734955	11	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734930 14 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am	7734956	12	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734953 15 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am	7734959	13	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734954 16 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734930	14	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734940 17 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734953	15	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734949 18 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734954	16	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734948 19 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734940	17	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734939 2 2016-02-19 @ 3:00 pm 2016-02-22 @ 11:00 am < 0.3	7734949	18	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734942 20 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734948	19	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734929 21 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734939	2	2016-02-19 @ 3:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734933 22 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734942	20	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734934 23 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734929	21	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734936 24 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734933	22	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734943 25 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734934	23	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734944 26 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734936	24	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734935 27 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734943	25	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734928 28 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734944	26	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734952 29 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734935	27	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734947 3 2016-02-19 @ 3:00 pm 2016-02-22 @ 11:00 am < 0.3	7734928	28	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734931 30 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734952	29	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734932 31 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734947	3	2016-02-19 @ 3:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7718520 32 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734931	30	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7718523 33 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7734932	31	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7718522 34 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7718520	32	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7718521 35 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7718523	33	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734945 4 2016-02-19 @ 3:00 pm 2016-02-22 @ 11:00 am < 0.3	7718522	34	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	
7734960 5 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3	7718521	35	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734958 6 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734951 7 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734957 8 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23	7734945	4	2016-02-19 @ 3:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23
7734951 7 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23 7734957 8 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23		5	1			2016-02-23
7734957 8 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23	7734958	6	•	2016-02-22 @ 11:00 am		2016-02-23
<u>.</u>	7734951	7	•			2016-02-23
7734938 9 2016-02-19 @ 4:00 pm 2016-02-22 @ 11:00 am < 0.3 2016-02-23			•			
	7734938	9	2016-02-19 @ 4:00 pm	2016-02-22 @ 11:00 am	< 0.3	2016-02-23

February LABORATORY ANALYSIS 15, REPORT **

Spike Sample Laboratory Results

Radon test result report for: MCPS

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7718273	101A	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.5 ± 0.6	2016-02-04
7718281	102B	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.4 ± 0.6	2016-02-04
7718282	103C	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.3 ± 0.6	2016-02-04
7718288	104D	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.7 ± 0.6	2016-02-04
7718289	105E	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.6 ± 0.6	2016-02-04
7718291	106F	2016-01-30 @ 9:00 am	2016-02-01 @ 9:00 am	6.5 ± 0.6	2016-02-04

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Note: Spike samples are test canisters that are deliberately exposed to a controlled high level of radon in a laboratory. They provide a quality control measure in the testing process and do NOT reflect radon levels in the building being tested.

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

s Inc. Job Number 173704
pCi/L Rel. Hum 45.9 % Temp. 79.0
Date Start: Date Stop:
Time Start: Time Stop:
Device No.'s:
Date Start: Date Stop:
Time Start: Time Stop:
Device No.'s:
Date Start: Date Stop:
Time Start: Time Stop:
Device No.'s:
·

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = $7 \mu R/h$ Elevation = 820 ft



Engineers • Planners • Scientists • Construction M anagers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon Phase 9

15. Briggs Chaney MS

Name of Schools:

1	Packing Harca Boad ES	16. Broad Acres ES	31. Rosa Parks MS
1.	Rocking Horse Road ES	10. Broad Acres ES	31. ROSA PATKS IVIS
2.	Rockwell ES	17. Belmont ES	32. Rosemary Hills ES
3.	Oakland Terrace ES	18. Emory Grove Center	33. Sequoyah ES
4.	Rosemont ES	19. Forest Knolls ES	34. Damascus HS
5.	Beall ES	20. Baker MS	35. Einstein ES
6.	Cresthaven ES	21. MLK MS	36. Forest Oak MS
7.	Quince Orchard HS	22. Richard Montgomery HS	37. Hoover MS
8.	Smith Center	23. Sherwood HS	38. Julius West MS
9.	Ashburton ES	24. Walter Johnson HS	39. John F. Kennedy HS
10	. Bannockburn ES	25. Diamond ES	40. Travilah ES
11	. Bradley Hills ES	26. Newport Mill MS	41. Watkins Mill HS
12	. Cannon Road ES	27. Drew ES	42. Northwood HS
13	. Flora M. Singer ES	28. Monocacy ES	43. Lincoln Center
14	. Clarksburg HS	29. Potomac ES	

30. Rock Terrace School

	Date	Initials
Radon Test Kits Deployed	2/22/16	JM
Radon Test Kits Collected	2/25/16	JM
Radon Test Kits Shipped to Lab*	2/25/16	UM
Radon Test Kits Received by Lab*	2/29/16	JM

^{*}All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759



Engineers • Planners • Scientists • Construction M anagers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon Phase 9

Name of Schools:

- 1. Banneker MS
- 2. Bethesda-Chevy Chase HS
- 3. Burtonsville ES
- 4. Chevy Chase ES
- 5. Clopper Mill ES
- 6. Edison HS
- 7. Flower Hill ES
- 8. Flower Valley ES
- 9. Greencastle ES

- 10. Maryvale ES
- 11. Montgomery Blair HS
- 12. Poolesville HS
- 13. Rachel Carson ES
- 14. Stedwick ES
- 15. Watkins Mill ES
- 16. Laytonsville ES
- 17. Lincoln Center

	Date	Initials
Radon Test Kits Deployed	2/23/16	(/M
Radon Test Kits Collected	2/26/16	JM
Radon Test Kits Shipped to Lab*	2/26/16	JM
Radon Test Kits Received by Lab*	3/01/16	JM

^{*}All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759



936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

MCPS RADON TESTING

Executive Summary: Quince Orchard High School

Date of Test Report:	2/29/2016 (Rev 1)
Round of Testing:	Initial
	Follow-up
	Post Remediation
# Rooms Tested:	70
# Rooms \geq 4.0 pCi/L:	0
Low Value:	< 0.3
High Value:	2.6

Project Status:

Initial testing completed; missing or compromised samples need re-test.

KCI TECHNOLOGIES, INC. WWW.kci.com

ENGINEERS • PLANNERS • SCIENTISTS • CONSTRUCTION MANAGERS

936 RIDGEBROOK ROAD • SPARKS, MD 21152 • 410-316-7800 • (FAX) 410-316-7935

February 29, 2016 (Rev 1)

Mr. Richard Cox Indoor Air Quality Team Leader Montgomery County Public Schools 850 Hungerford Drive Rockville, MD 20850

Re: Radon Testing Services

KCI Job # 12146341.19

Location: Quince Orchard High School

15800 Quince Orchard Road Gaithersburg, MD 20878

Dear Mr. Cox:

KCI Technologies, Inc. (KCI) is pleased to submit the following report to the Montgomery County Public Schools (MCPS) pursuant to completing a "short-term" 3 day radon test for the Quince Orchard High School, located at 15800 Quince Orchard Road in Gaithersburg, Maryland 20878 (subject site).

Scope of Services:

KCI TECHNOLOGIES, INC.

KCI conducted radon testing at the subject site to evaluate indoor radon levels relative to the USEPA's recommended action level of 4.0 picocuries per Liter (pCi/L) - the level at which EPA recommends that schools take action to reduce the level. KCI conducted the radon testing in accordance with American Association of Radon Scientists and Technologists (AARST) *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings*. A National Radon Safety Board (NRSB) Radon Measurement Specialist (certification #14SS056) supervised the testing. Additional information on radon management and the health effects of radon exposure is available from www.montgomerycountymd.gov/dep/air/radon or www.epa.gov/radon.

KCI visited the site on December 15, 2016 and deployed ninth-two (92) activated charcoal (AC) radon test kits. KCI deployed radon test kits in frequently-occupied ground contact rooms, and other areas, (if applicable) in accordance with AARST guidance. A floor plan map of the building with the test locations is included as Attachment A of this report.

As a quality control measure, KCI included duplicate samples, field blanks, lab transit blanks, and office blanks in accordance with AARST recommendations. In addition, KCI submitted six (6) test kits to Bowser-Morner, Inc. as spike samples. The spiked tests were exposed to a known radon concentration by Bowser-Morner prior to being returned to the laboratory for analysis.

KCI returned to the site on December 18, 2016 to retrieve the radon sampling test kits. KCI shipped all radon tests via overnight delivery to Airchek, Inc. for analysis by gamma-ray spectroscopy. Airchek, Inc. is a NRSB certified analytical laboratory for radon analysis (certification # ARL1402) located at 1936

www.kci.com

Butler Bridge Road, Mills River, North Carolina.

Evaluation of Testing Conditions:

The operating condition that represents the greatest amount of significantly occupied time for this building is; heating active, with outdoor temperature averages $\leq 65^{\circ}$ F.

KCI concludes that the test period reasonably represents normal conditions when the building is significantly occupied. Clear characterization of the radon hazard is most likely to be observed under this normal operating condition. Based on the evaluation of test conditions, this test should reasonably characterize radon hazards.

KCI also conducted observations of field conditions which could affect the results of the test and compiled weather data for the testing period. KCI recorded observations of the following conditions in each room at the time of deployment and collection of the radon test kits:

- Indoor temperature,
- HVAC Operation,
- Dehumidifier operation,
- Humidifier operation,
- Ceiling fan operation, and
- Open windows or doors.

Results:

The results of the radon test analysis indicated the following:

Radon Concentration	Room	Result
≥4.0 piC/L	none	n/a
<4.0 piC/L	See Attachment B	

Notes:

D- Duplicate sample

All field blanks, office blank, and lab transit blanks had test results of less than the laboratory detection limit of 0.3 pCi/L. Review of the duplicate sample analysis indicates that adequate laboratory measurement precision was achieved. The Spike sample analysis results indicate the laboratory is operating within statistical control limits.

The sampling locations, field observations, and analytical results are listed on Table 1 (Attachment B). The laboratory analytical results are also attached (Attachment C). Laboratory results and exposure data for the spike samples are also included in Attachment C.

Our professional services have been performed in accordance with customary principles and practices in the field of industrial hygiene and engineering. If you have any questions or comments regarding this report, please feel free to contact me at (410) 316-7800.

Mr. Richard Cox February 29, 2016 Page 4

Sincerely,

James M. Moulsdale

James Makler

Radon Measurement Specialist

KCI Technologies, Inc.

Attachments: A- Floor Plan with Test Locations

B- Table 1-Radon Test Summary Spreadsheet

C- Laboratory Analytical Results

ATTACHMENT A

Floor Plan With Test Locations

ATTACHMENT B

Radon Test Summary Spreadsheet

Table Notes:

AC- Activated Charcoal

ACI- Air Chek, Inc.

D- Duplicate

FB- Field Blank

KCI- KCI Technologies, Inc.

OB- Office Blank

PM- Project Manager

QC- Quality Control

	Radon Testing Results	
	Quince Orchard HS	
<u> </u>	est Period: 12/15/15-12/18/15	
Kit Number	Room / Area	Result
7704349	100	< 0.3
7704348	101	< 0.3
7705078	102	< 0.3
7705076	103	< 0.3
7705081	105	< 0.3
7705074	112	< 0.3
7705082	116	< 0.3
7705088	116	< 0.3
7705087	117	< 0.3
7705092	117	< 0.3
7705040	118	< 0.3
7705133	118	< 0.3
7705138	118	< 0.3
7705072	119	0.5
7705130	120	< 0.3
7705145	121	0.8
7705123	122	0.5
7705073	124	0.6
7705077	125	< 0.3
7705046	128	0.6
7705048	129	< 0.3
7705042	130	< 0.3
7705094	131	0.7
7705044	132	0.6
7705066	133	< 0.3
7704324	138	0.5
7704375	140	< 0.3
7704284	143	< 0.3
7704323	145	2.6
7704380	145	2.5
7704321	148	1.1
7704283	149	1.1
7704383	150	1.2
7705136	151	1.9
7704357	152	1.5
7704384	153	1.4
7704388	153	1.5
7705028	200	< 0.3
7705003	216	< 0.3
7705015	221	< 0.3
7705058	226	< 0.3
7705067	232	< 0.3
7705096	252	< 0.3
7705016	254	< 0.3
7705049 7705090	352 105C	< 0.3 < 0.3

Table Note:
* Missing or Compromised Sample

	Radon Testing Results						
	Quince Orchard Hs						
	Test Period: 12/15/15-12/18/15						
ICH NI	Kit Number Room / Area Result						
	Kit Number Room / Area						
7705045	105E	< 0.3					
7705114	105F	< 0.3					
7705101	105G	< 0.3					
7705099	105H	< 0.3					
7705086	1051	< 0.3					
7705080	105J	< 0.3					
7705093	105K	< 0.3					
7705071	105L	< 0.3					
7705098	105M	< 0.3					
7705064	106B	1.1					
7705025	108B	1.1					
7705105	116A	< 0.3					
7705115	118A	< 0.3					
7705111	119A	< 0.3					
7705089	119B	0.9					
7705079	119BA	1.3					
7705100	119E	< 0.3					
7705075	119F	< 0.3					
7705140	119G	0.6					
7705055	120A	0.6					
7705070	121C	< 0.3					
7705054	123B	< 0.3					
7705122	125A	< 0.3					
7705112	* 125B (Tampered)	< 0.3					
7704358	143A	< 0.3					
7704362	143B	< 0.3					
7704367	144A	< 0.3					
7704281	144B						
7705021	* ISI (Tampered)	< 0.3					
7705030	* LOWER AUDI (Missing)	-					
7705063	* LOWER AUDI (Tampered)	2.5					

Table Note:
* Missing or Compromised Sample

	Radon Testing Results				
	Quince Orchard HS				
	Test Period: 12/15/15-12/18/15				
Kit Number	QC Type	Result			
7705083	D (100)	0.5			
7705102	D (103)	0.6			
7705059	D (108B)	0.9			
7705091	D (112)	< 0.3			
7705051	D (120)	< 0.3			
7705041	D (124)	< 0.3			
7705137	D (130)	< 0.3			
7705017	D (131)	0.8			
7705053	D (133)	< 0.3			
7704322	D (143)	< 0.3			
7705084	FB (100)	< 0.3			
7705095	FB (105E)	< 0.3			
7705141	FB (120)	< 0.3			
7705085	FB (125)	< 0.3			
7708213	OB (OFFICE BLANK)	< 0.3			

Table Note:
* Missing or Compromised Sample

ATTACHMENT C

Laboratory Analytical Results

December LABORATORY ANALYSIS 31, REPORT **

Radon test result report for: QUINCE ORCHARD HS MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7704349	100	2015-12-15 @ 10:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705083	100	2015-12-15 @ 10:00 am	2015-12-18 @ 9:00 am	0.5 ± 0.3	2015-12-22
7705084	100	2015-12-15 @ 10:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7704348	101	2015-12-15 @ 10:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705078	102	2015-12-15 @ 10:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705076	103	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705102	103	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	0.6 ± 0.3	2015-12-22
7705081	105	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705090	105C	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705095	105E	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705045	105E	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705114	105F	2015-12-15 @ 11:00 am	2015-12-18 @ 12:00 pm	< 0.3	2015-12-22
7705101	105G	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705099	105H	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705086	105I	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705080	105J	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705093	105K	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705071	105L	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705098	105M	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705064	106B	2015-12-15 @ 3:00 pm	2015-12-18 @ 9:00 am	1.1 ± 0.3	2015-12-22
7705025	108B	2015-12-15 @ 3:00 pm	2015-12-18 @ 9:00 am	1.1 ± 0.3	2015-12-22
7705059	108B	2015-12-15 @ 3:00 pm	2015-12-18 @ 9:00 am	0.9 ± 0.3	2015-12-22
7705091	112	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705074	112	2015-12-15 @ 11:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705082	116	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705088	116	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705105	116A	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705087	117	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705092	117	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705040	118	2015-12-15 @ 12:00 pm	2015-12-18 @ 12:00 pm	< 0.3	2015-12-22
7705133	118	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705138	118	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705115	118A	2015-12-15 @ 12:00 pm	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705072	119	2015-12-15 @ 1:00 pm	2015-12-18 @ 9:00 am	0.5 ± 0.3	2015-12-22
7705111	119A	2015-12-15 @ 1:00 pm	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705089	119B	2015-12-15 @ 1:00 pm	2015-12-18 @ 9:00 am	0.9 ± 0.3	2015-12-22
7705079	119BA	2015-12-15 @ 1:00 pm	2015-12-18 @ 9:00 am	1.3 ± 0.3	2015-12-22

December LABORATORY ANALYSIS 31, REPORT **

Radon test result report for: QUINCE ORCHARD HS MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7705100	119E	2015-12-15 @ 1:00 pm	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705075	119F	2015-12-15 @ 1:00 pm	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705140	119G	2015-12-15 @ 1:00 pm	2015-12-18 @ 9:00 am	0.6 ± 0.3	2015-12-22
7705051	120	2015-12-15 @ 1:00 pm	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7705130	120	2015-12-15 @ 1:00 pm	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7705141	120	2015-12-15 @ 1:00 pm	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7705055	120A	2015-12-15 @ 1:00 pm	2015-12-18 @ 10:00 am	0.6 ± 0.3	2015-12-22
7705145	121	2015-12-15 @ 1:00 pm	2015-12-18 @ 10:00 am	0.8 ± 0.3	2015-12-22
7705070	121C	2015-12-15 @ 1:00 pm	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7705123	122	2015-12-15 @ 1:00 pm	2015-12-18 @ 10:00 am	0.5 ± 0.2	2015-12-22
7705054	123B	2015-12-15 @ 1:00 pm	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7705041	124	2015-12-15 @ 1:00 pm	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7705073	124	2015-12-15 @ 1:00 pm	2015-12-18 @ 10:00 am	0.6 ± 0.3	2015-12-22
7705077	125	2015-12-15 @ 2:00 pm	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7705085	125	2015-12-15 @ 2:00 pm	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7705122	125A	2015-12-15 @ 2:00 pm	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7705112	125B	2015-12-15 @ 2:00 pm	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7705046	128	2015-12-15 @ 2:00 pm	2015-12-18 @ 10:00 am	0.6 ± 0.3	2015-12-22
7705048	129	2015-12-15 @ 2:00 pm	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7705042	130	2015-12-15 @ 2:00 pm	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7705137	130	2015-12-15 @ 2:00 pm	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7705017	131	2015-12-15 @ 2:00 pm	2015-12-18 @ 11:00 am	0.8 ± 0.3	2015-12-22
7705094	131	2015-12-15 @ 2:00 pm	2015-12-18 @ 10:00 am	0.7 ± 0.3	2015-12-22
7705044	132	2015-12-15 @ 2:00 pm	2015-12-18 @ 10:00 am	0.6 ± 0.3	2015-12-22
7705053	133	2015-12-15 @ 2:00 pm	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7705066	133	2015-12-15 @ 2:00 pm	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7704324	138	2015-12-15 @ 9:00 am	2015-12-18 @ 10:00 am	0.5 ± 0.3	2015-12-22
7704375	140	2015-12-15 @ 9:00 am	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7704284	143	2015-12-15 @ 9:00 am	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7704322	143	2015-12-15 @ 9:00 am	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7704358	143A	2015-12-15 @ 9:00 am	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7704362	143B	2015-12-15 @ 9:00 am	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7704367	144A	2015-12-15 @ 9:00 am	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7704281	144B	2015-12-15 @ 9:00 am	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7704380	145	2015-12-15 @ 9:00 am	2015-12-18 @ 10:00 am	2.5 ± 0.3	2015-12-22
7704323	145	2015-12-15 @ 9:00 am	2015-12-18 @ 10:00 am	2.6 ± 0.3	2015-12-22
7704321	148	2015-12-15 @ 10:00 am	2015-12-18 @ 10:00 am	1.1 ± 0.3	2015-12-22

December ABORATORY ANALYSIS 31, REPORT **

Radon test result report for: QUINCE ORCHARD HS MAIN

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
704283	149	2015-12-15 @ 10:00 ar	n 2015-12-18 @ 9:00 am	1.1 ± 0.3	2015-12-22
7704383	150	2015-12-15 @ 10:00 ar	n 2015-12-18 @ 10:00 am	1.2 ± 0.3	2015-12-22
7705136	151	2015-12-15 @ 10:00 ar	n 2015-12-18 @ 10:00 am	1.9 ± 0.3	2015-12-22
7704357	152	2015-12-15 @ 10:00 ar	n 2015-12-18 @ 10:00 am	1.5 ± 0.3	2015-12-22
7704384	153	2015-12-15 @ 9:00 am	2015-12-18 @ 10:00 am	1.4 ± 0.3	2015-12-22
7704388	153	2015-12-15 @ 9:00 am	2015-12-18 @ 10:00 am	1.5 ± 0.3	2015-12-22
7705028	200	2015-12-15 @ 3:00 pm	2015-12-18 @ 9:00 am	< 0.3	2015-12-22
7705003	216	2015-12-15 @ 3:00 pm	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7705015	221	2015-12-15 @ 3:00 pm	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7705058	226	2015-12-15 @ 3:00 pm	2015-12-18 @ 11:00 am	< 0.3	2015-12-22
7705067	232	2015-12-15 @ 3:00 pm	2015-12-18 @ 11:00 am	< 0.3	2015-12-22
7705096	252	2015-12-15 @ 3:00 pm	2015-12-18 @ 11:00 am	< 0.3	2015-12-22
7705016	254	2015-12-15 @ 3:00 pm	2015-12-18 @ 11:00 am	< 0.3	2015-12-22
7705049	352	2015-12-15 @ 3:00 pm	2015-12-18 @ 11:00 am	< 0.3	2015-12-22
7705021	ISI	2015-12-15 @ 3:00 pm	2015-12-18 @ 10:00 am	< 0.3	2015-12-22
7705063 LOV	WER AUDITORI	UM 2015-12-15 @ 2:00 pm	2015-12-18 @ 11:00 am	2.5 ± 0.3	2015-12-22

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

December LABORATORY ANALYSIS 31, REPORT **

Radon test result report for:
QUINCE ORCHARD HS
OFFICE BLANK

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7708213	OFFICE BLANK	2015-12-15 @ 3:00 pm	2015-12-18 @ 3:00 pm	< 0.3	2015-12-22
		_			

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

December LABORATORY ANALYSIS 29, REPORT **

Radon test result report for:
TRANSIT DEC 14 2015
NONE

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7704395	TRANSIT 1	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
					2010 12 10
7706508	TRANSIT 10	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706510	TRANSIT 11	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706511	TRANSIT 12	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706505	TRANSIT 13	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704371	TRANSIT 14	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706506	TRANSIT 15	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704381	TRANSIT 16	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704399	TRANSIT 17	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704390	TRANSIT 18	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704396	TRANSIT 2	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704364	TRANSIT 3	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704370	TRANSIT 4	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7704368	TRANSIT 5	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706524	TRANSIT 6	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706526	TRANSIT 7	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706518	TRANSIT 8	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16
7706516	TRANSIT 9	2015-12-13 @ 10:00 am	2015-12-15 @ 10:00 am	< 0.3	2015-12-16

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

December LABORATORY ANALYSIS 23, REPORT **

Spike Sample Laboratory Results

Radon test result report for: MCPS

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
7706380	101	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	25.2	2015-12-23
7706381	102	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	26.5	2015-12-23
7706208	103	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	27.7	2015-12-23
7705132	104	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	28.6	2015-12-23
7706366	105	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	26.5	2015-12-23
7706211	106	2015-12-18 @ 9:00 am	2015-12-21 @ 9:00 am	26.1	2015-12-23

Air Chek, Inc. 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Note: Spike samples are test canisters that are deliberately exposed to a controlled high level of radon in a laboratory. They provide a quality control measure in the testing process and do NOT reflect radon levels in the building being tested.

EXPOSURE IN BOWSER-MORNER RADON CHAMBER

CLIENT KCI Technologies.	Inc. Job Number 173224
	pCi/L Rel. Hum <u>49.6</u> % Temp. <u>69.9</u>
Date Start: 12/18/15 Date Stop: 12/21/5	Date Start: Date Stop:
Time Start: <u>0929</u> Time Stop: <u>0929</u>	Time Start: Time Stop:
Device No.'s: 7705132,7766208	Device No.'s:
7706211,7706366,	
7706380, 7706381	
F3 Loft	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:
	-
1	
Date Start: Date Stop:	Date Start: Date Stop:
Time Start: Time Stop:	Time Start: Time Stop:
Device No.'s:	Device No.'s:

Note: All times are in 24-hour (military) notation, Eastern Standard Time (EST) Background = $7 \mu R/h$ Elevation = 820 ft



Engineers • Planners • Scientists • Construction Managers

Corporate Office: 936 Ridgebrook road • Sparks , Maryland 21152 • 410-316-7800 • (Fax) 410-316-7935

Radon Test Kit Chain of Custody

Project Name: MCPS Radon Phase I

Name of Schools:

1. Westland M.S.

6. South Lake E.S.

11. Highland View E.S. 16. Ridgeview M.S.

2. East Silver Spring E.S.

7. Jones Lane E.S.

12. Cresthaven E.S.

17. Rockwell E.S.

3. Oakland Terrace E.S.

8. Quince Orchard H.S. 13. Viers Mill E.S.

18. Oak View E.S.

4. Rocking Horse Road E.S.

9. Damascus E.S.

14. Smith Center

19. Jackson Road E.S.

5. Beall E.S.

10. Westbrooke E.S.

15. Rosemont E.S.

20. Highland E.S.

21. Watkins Mill E.S.

	Date	Initials
Radon Test Kits Deployed	12/15/15	14 M
Radon Test Kits Collected	12/18/15	KM
Radon Test Kits Shipped to Lab*	12/18/15	KM
Radon Test Kits Received by Lab*	12/22/15	KM

^{*}All samples sent to Air Check, Inc., 1936 Butler Bridge Rd, Mills River, NC 28759